

*Cross Reference of*  
*NPL-FRUS-2-73*  
**National Priorities List**

Superfund hazardous waste site listed under the  
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) as amended in 1986

*Unadjusted Final*  
*NPL-47-2-227*  
*2/90*

**PASCO SANITARY LANDFILL**  
Pasco, Washington

Conditions at listing (June 1988): Pasco Sanitary landfill covers 250 acres 1.5 miles northeast of Pasco, Franklin County, Washington, in an area dominated by irrigated agricultural fields and range land. The landfill is privately owned and operated and was converted from a burning dump to a sanitary landfill in 1971. Since 1982, it has had a conditional use permit from the Washington Department of Ecology (WDOE) to accept municipal wastes.

In 1972, Resource Recovery Corp. leased a portion of the landfill and operated a regional hazardous waste disposal site under a WDOE permit until December 1974, when the lease terminated.

According to WDOE files, over 47,000 drums of hazardous substances including paint wastes, pesticides, organic solvents, cadmium, and mercury, were deposited in the leased portion of the landfill. In 1974, the area was covered by 3 feet of soil.

In 1985, EPA detected tetrachloroethylene and trichloroethylene in on-site ground water. A well on-site supplies drinking water to two nearby residences. Ground water within 3 miles of the site is used by over 1,000 people for drinking and is also used to irrigate almost 10,000 acres of land.

In October 1986, WDOE issued an Administrative Order requiring Resource Recovery Corp. to monitor on-site wells on a quarterly basis. The company is currently complying with the order.

Status (December 1989): Resource Recovery Corp. has completed a hydrogeological evaluation of the site and continues to monitor on-site wells on a quarterly basis.



**National Priorities List**

Superfund hazardous waste site listed under the  
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) as amended in 1986

---

PASCO SANITARY LANDFILL  
Pasco, Washington

Pasco Sanitary Landfill covers 250 acres 1.5 miles northeast of Pasco, Franklin County, Washington, in an area dominated by irrigated agricultural fields and range land. The landfill is privately owned and operated and was converted from a burning dump to a sanitary landfill in 1971. Since 1982, it has had a conditional use permit from the Washington Department of Ecology (WDOE) to accept municipal wastes.

In 1972, Resource Recovery Corp. leased a portion of the landfill and operated a regional hazardous waste disposal site under a WDOE permit until December 1974, when the lease terminated.

According to WDOE files, over 47,000 drums of hazardous substances, including paint wastes, pesticides, organic solvents, cadmium, and mercury, were deposited in the leased portion of the landfill. In 1974, the area was covered by 3 feet of soil.

In 1985, EPA detected tetrachloroethylene and trichloroethylene in on-site ground water. A well on-site supplies drinking water to two nearby residences. Ground water within 3 miles of the site is used by over 1,000 people for drinking and is also used to irrigate almost 10,000 acres of land.

In October 1986, WDOE issued an Administrative Order requiring Pasco to monitor on-site wells on a quarterly basis. The company is currently complying with the order.

Facility name: Pasco Sanitary Landfill

Location: Pasco, Washington

EPA Region: 10

Person(s) in charge of the facility: Larry Dietrich

Name of Reviewer: Lynn Guilford Date: 5/27/87

General description of the facility:  
 (For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

Resource Recovery Corporation operated a portion of Pasco Sanitary Landfill as a hazardous waste disposal site from 1972 to 1974. Currently the disposal areas are all covered with three feet of soil. This cover gives both the surface water and direct contact routes scores of 0. The ground water route has an observed release and a large ground water population giving the site an overall score of 44.46

Scores:  $S_M = 44.46$  ( $S_{gw} = 76.92$   $S_{sw} = 0$   $S_a = 0$ )  
 $S_{FE} = 0$   
 $S_{DC} = 0$

**FIGURE 1**  
**HRS COVER SHEET**

*Handwritten signature*  
 7-16-87

Ground Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Release	0 <u>45</u>	1	45	45	3.1	
If observed release is given a score of 45, proceed to line <b>4</b> . If observed release is given a score of 0, proceed to line <b>2</b> .						
<b>2</b> Route Characteristics					3.2	
Depth to Aquifer of Concern	0 1 2 3	2		6		
Net Precipitation	0 1 2 3	1		3		
Permeability of the Unsaturated Zone	0 1 2 3	1		3		
Physical State	0 1 2 3	1		3		
Total Route Characteristics Score				15		
<b>3</b> Containment	0 1 2 3	1		3	3.3	
<b>4</b> Waste Characteristics					3.4	
Toxicity/Persistence	0 3 6 9 <u>12</u> 15 18	1	12	18		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 <u>8</u>	1	8	8		
Total Waste Characteristics Score			20	26		
<b>5</b> Targets					3.5	
Ground Water Use	0 1 2 <u>3</u>	3	9	9		
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 20 24 30 32 35 <u>40</u>	1	40	40		
Total Targets Score			49	49		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>			44100	57.330		
<b>7</b> Divide line <b>6</b> by 57,330 and multiply by 100			S <sub>gw</sub> = 76.92			

**FIGURE 2**  
**GROUND WATER ROUTE WORK SHEET**

*Handwritten signature*  
7-17-87



Surface Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Release	0      45	1		45	4.1	
If observed release is given a value of 45, proceed to line <b>4</b> . If observed release is given a value of 0, proceed to line <b>2</b> .						
<b>2</b> Route Characteristics					4.2	
Facility Slope and Intervening Terrain	① 1 2 3	1		3		
1-yr. 24-hr. Rainfall	① 1 2 3	1		3		
Distance to Nearest Surface Water	① 1 2 3	2		6		
Physical State	① 1 2 3	1		3		
Total Route Characteristics Score			0	15		
<b>3</b> Containment	① 1 2 3	1	0	3	4.3	
<b>4</b> Waste Characteristics					4.4	
Toxicity/Persistence	① 3 6 9 12 15 18	1	0	18		
Hazardous Waste Quantity	① 1 2 3 4 5 6 7 8	1	0	8		
Total Waste Characteristics Score			0	26		
<b>5</b> Targets					4.5	
Surface Water Use	① 1 2 3	3	0	9		
Distance to a Sensitive Environment	① 1 2 3	2	0	6		
Population Served/Distance to Water Intake Downstream	① 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40		
Total Targets Score			0	55		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>				64,350		
<b>4</b> Divide line <b>6</b> by 64,350 and multiply by 100				S <sub>sw</sub> = 0		

**FIGURE 7**  
**SURFACE WATER ROUTE WORK SHEET**

*[Handwritten Signature]*  
7-17-87

Air Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>[1]</b> Observed Release	(0) 45	1	0	45	5.1	
Date and Location:						
Sampling Protocol:						
If line <b>[1]</b> is 0, the $S_a = 0$ . Enter on line <b>[5]</b> . If line <b>[1]</b> is 45, then proceed to line <b>[2]</b> .						
<b>[2]</b> Waste Characteristics					5.2	
Reactivity and Incompatibility	0 1 2 3	1		3		
Toxicity	0 1 2 3	3		9		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8		
Total Waste Characteristics Score				20		
<b>[3]</b> Targets					5.3	
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30	1		30		
Distance to Sensitive Environment	0 1 2 3	2		6		
Land Use	0 1 2 3	1		3		
Total Targets Score				39		
<b>[4]</b> Multiply <b>[1]</b> x <b>[2]</b> x <b>[3]</b>				35,100		
<b>[5]</b> Divide line <b>[4]</b> by 35,100 and multiply by 100				$S_a = 0$		

**FIGURE 9**  
**AIR ROUTE WORK SHEET**

*Handwritten:*  
7-17-87

	s	s <sup>2</sup>
Groundwater Route Score (S <sub>gw</sub> )	76.92	5916.69
Surface Water Route Score (S <sub>sw</sub> )	0	0
Air Route Score (S <sub>a</sub> )	0	0
$S_{gw}^2 + S_{sw}^2 + S_a^2$		5916.69
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		76.92
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		44.46

**FIGURE 10**  
**WORKSHEET FOR COMPUTING S<sub>M</sub>**

*[Handwritten signature]*  
7-17-87

Fire and Explosion Work Sheet						
Rating Factor	Assigned Value (Circle One)		Multi- plier	Score	Max. Score	Ref. (Section)
<b>1</b> Containment	1	3	1		3	7.1
<b>2</b> Waste Characteristics						7.2
Direct Evidence	0	3	1		3	
Ignitability	0	1 2 3	1		3	
Reactivity	0	1 2 3	1		3	
Incompatibility	0	1 2 3	1		3	
Hazardous Waste Quantity	0	1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score					20	
<b>3</b> Targets						7.3
Distance to Nearest Population	0	1 2 3 4 5	1		5	
Distance to Nearest Building	0	1 2 3	1		3	
Distance to Sensitive Environment	0	1 2 3	1		3	
Land Use	0	1 2 3	1		3	
Population Within 2-Mile Radius	0	1 2 3 4 5	1		5	
Buildings Within 2-Mile Radius	0	1 2 3 4 5	1		5	
Total Targets Score					24	
<b>4</b> Multiply <b>1</b> x <b>8</b> x <b>3</b>					1,440	
<b>8</b> Divide line <b>4</b> by 1,440 and multiply by 100				SFE =	0	

FIGURE 11  
FIRE AND EXPLOSION WORK SHEET

*Handwritten signature*  
7-17-87

Direct Contact Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<input type="checkbox"/> 1 Observed Incident	0      45	1		45	8.1	
If line <input type="checkbox"/> 1 is 45, proceed to line <input type="checkbox"/> 1 If line <input type="checkbox"/> 1 is 0, proceed to line <input type="checkbox"/> 1						
<input type="checkbox"/> 1 Accessibility	0 <input type="checkbox"/> 1 2 3	1	1	3	8.2	
<input type="checkbox"/> 1 Containment	<input type="checkbox"/> 0 15	1	0	15	8.3	
<input type="checkbox"/> 4 Waste Characteristics Toxicity	<input type="checkbox"/> 0 1 2 3	5	0	15	8.4	
<input type="checkbox"/> 5 Targets					8.5	
Population Within a 1-Mile Radius	<input type="checkbox"/> 0 1 2 3 4 5	4	0	20		
Distance to a Critical Habitat	<input type="checkbox"/> 0 1 2 3	4	0	12		
Total Targets Score			0	32		
<input type="checkbox"/> 6 If line <input type="checkbox"/> 1 is 45, multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 1 x <input type="checkbox"/> 1 If line <input type="checkbox"/> 1 is 0, multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 1 x <input type="checkbox"/> 1 x <input type="checkbox"/> 1			0	21.600		
<input type="checkbox"/> 1 Divide line <input type="checkbox"/> 1 by 21,600 and multiply by 100			SDC = 0			

FIGURE 12  
DIRECT CONTACT WORK SHEET

*Handwritten signature*  
7-17-8-



## ecology and environment, inc.

101 YESLER WAY, SEATTLE, WASHINGTON, 98104, TEL. 206/624-9537

International Specialists in the Environment

### DOCUMENTATION RECORDS

FOR

### HAZARD RANKING SYSTEM

Instructions: The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility/site. As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste Quantity = 4320 drums plus 800 cubic yards of sludges"). The source of the information should be provided for each entry and should be a biographical-type reference that will make the source used for the data point easier to find. Include the location of the source and consider appending a copy of the relevant page(s) for ease in review.

FACILITY NAME: Pasco Sanitary Landfill

LOCATION: Kahlotus Road and Highway 12  
Pasco, Washington 99301

REVIEWER: Lynn Guilford

TDD: TDD F10-8701-04

ECOLOGY AND ENVIRONMENT, INC.

DATE: June 1987

*Handwritten signature*  
7-17-87

## GROUND WATER ROUTE

### 1. OBSERVED RELEASE

#### 1a. Contaminants Detected (5 maximum) in Ground Water

Tetrachloroethylene was found in monitoring well EE2.  
Trichloroethylene was found in monitoring wells EE2, EE3, and JUB 2.  
The levels found were significantly over background (JUB-CATR)

#### - Rationale for attributing the contaminants to the facility:

These compounds, tetrachloroethylene and trichloroethylene, were not found in background wells, but were only found in wells downgradient and adjacent to zone A and the old landfill burn and demolition disposal area. Paint wastes were disposed in Zone A.

HRS Section Score: 45 (Ref. 1 p5d)

\* \* \* \* \*

### 2. ROUTE CHARACTERISTICS

#### 2a. Depth to Aquifer of Concern

#### - Name and description of aquifer(s) of concern:

water table aquifer, unconfined, which overlies Yakima Basalts. Groundwater occurs 38.5 to 68.7 feet below ground surface at site. See table 4.1 and figures 4.2 and 4.3 of Reference 1 for description of geologic units and cross-sections.

HRS Section Score: (Ref. )

#### 2b. Net Precipitation

#### - Mean annual or seasonal precipitation (list months for seasonal):

#### - Mean annual lake evaporation rate (list months for seasonal):

#### - Net precipitation (subtract above figures):

HRS Section Score: (Ref. )

*[Handwritten signature]*  
7-17-8

2c. Permeability of Unsaturated Zone

- Soil type in unsaturated zone:
- Permeability associated with soil type:

HRS Section Score: (Ref. )

2d. Physical State

- Physical state of substance at time of disposal (or at present time for generated gases):

HRS Section Score: (Ref. )

\* \* \* \* \*

3. CONTAINMENT

3a. Containment

- Method(s) of waste or leachate containment evaluated:
- Method with highest score:

HRS Section Score: (Ref. )

\* \* \* \* \*

4. WASTE CHARACTERISTICS

4.a Toxicity and Persistence

- Compound(s) evaluated:

Compound	Toxicity	Persistence	Total
Trichloroethylene	2	2	12
Tetrachloroethylene	2	2	12

- Compound(s) with highest score:

Tetrachloroethylene and Trichloroethylene

HRS Section Score: 12 (Ref. 2)

*Handwritten signature*  
7-17-8



4b. Hazardous Waste Quantity

- Total amount of hazardous substance at the facility, excluding those with a containment score of zero. (Give a reasonable estimate, even if the quantity is above maximum.):

The total waste quantity is estimated to be approximately 47,000 drums.

- Basis of estimating and/or computing waste quantity (must be documented quantity and not assumed):

Paint Wastes - 26,426 drums  
2,4-D Mfg. wastes - 5,080 drums  
Carcinogenics - 9 drums  
Aromatic Tar - 1,159 drums  
Cadmium Waste - 11 drums

Pesticides - 425 drums  
Metal Finishing/Cleaning  
- 10,947 drums  
Solvents - 253 drums  
Barium with Mercury  
- 2,896 drums

HRS Section Score: 8 (Ref. 1,3,4,5)

\* \* \* \* \*

5. TARGETS

5a. Ground Water Use

- Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Ground water is used for drinking water and irrigation within three miles of the site. Some of the wells used for drinking water are beyond the perimeter of the public water supply system.

HRS Section Score: 3 (Ref. 6,7,8,  
9,10,11,12,13)

5b. Distance to Nearest Well

- Location of nearest well drawing from the "aquifer of concern" or occupied building not served by a public water supply:

SW 1/4, NW 1/4, Section 22, Township 9N, Range 30E.

- Distance from site to above well or building:

The well is on site, approximately 800 feet north of monitoring wells EE2, EE3, and JUB 2, which are contaminated.

HRS Section Score: 4 (Ref. 11,13 )

*Handwritten signature*  
7-1787

5c. Population Served by Ground Water within a 3-Mile Radius

- Identify water supply well(s) drawing from the "aquifer of concern" within a 3-mile radius and populations served by each:

See sheet 4A

Total 1048

- Compute land area irrigated by supply well(s) drawing from the "aquifer of concern" and convert to population (1.5 people per acre):

See Sheets 4B,C,D

- Total population served by ground water:

$$1048 + 14820 = 15868$$

HRS Section Score: 40 (Ref. 7,8,9,  
10,11,12,13,14)

*Handwritten signature*  
7-17-87

6/5/87

Pasco Sanitary Landfill

GW used for drinking water within 3 miles of above site

<u>Name</u>	<u>Pop. served</u>	<u>Reference #</u>
1. Washington Idaho Laborers	3.8	7
2. Paul Savage	3.8	7
3. Al Yenny	3.8	7
4. Tom Kidwell	3.8	7
5. Van Warner	3.8	7
6. Lakeview Mobile Home Park	800	8
7. Rada Sons	16	8
9. AZTLAN Construction Inc	20	8
10. BPA - Franklin	16	8
11. Bonne Brac Trailer Court	65	8
12. De Vries Water system	12	8
13. Palmarez	3.8	10
14. Marquez	3.8	10
15. Johnson & Boxbaum	3.8	10
16. Bumgarner	3.8	10
17. Dall	3.8	10
18. Cunningham	3.8	10
19. Rasmussen	3.8	10
20. Western Farm Services	24	8
21. Frontier Machinery	50	8
Total	1048.6	

*[Signature]*  
7-17-87

Pasco Sanitary Landfill

6/10/87

EW used for irrigation within 3 miles of above site:

<u>Name</u>	<u>Acres</u>	<u>Reference #</u>
Burlington Northern	520	9
"	130	
Conn Mut Life Ins	145	
Burlington Northern	520	
"	520	
"	300	
Middleton	142	
"	20	
Columbia East	268	
Burlington Northern	137	
"	160	
"	400	
"	315	
"	107	
"	300	
"	200	
Sullivan	20	
Burlington Northern	107	
"	300	
"	40	
Alderson	150	
Columbia East	500	
Burlington Northern	315	
"	40	
"	75	
Hill	15	
USCE	10	

*Handwritten:*  
 7-11-87  
 [Signature]  
 [Signature]

Standard Oil	.75
Minnahan	40
Conn Mut Life Ins	137
Tippett	135
"	160
Conn Mut Life Ins.	160
Worsham	157
Cox	157
"	5
Conn Mut Life Ins	130
"	155
Worsham	157
Burlington Northern	480
WA ST DNR	520
Columbia East	130
Burlington Northern	130
Seattle Hardware	4
Clase	1
Modd	2
Fanning	7
Frontier Machinery	12.5
Pasco, City of	15
Columbia	268
Dietrich	38
Tomlinson	345
Palomarez	26
Burden	20
Eastern Wa ID	5
Spooner	1
Reisinger	2

Hatched Back  
 7-17-8-

Reisinger

6.5

Mann

10

Johnson

5.5

Lourdes

1.5

Pasco, City of

10

Pasco, Port of

3

Columbia East

495

Story

73

Hill

20

USCE

100

Total

9879.75

acres

 $\times 1.5$ 

people per acre

14820

people



*[Signature]*  
7-17-87

## SURFACE WATER ROUTE

### 1. OBSERVED RELEASE

#### 1a. Contaminants Detected in the Surface Water at the Facility or Down Gradient from It (5 maximum)

No observed release.

- Rationale for attributing contaminants to the facility:

HRS Section Score: (Ref. )

\* \* \* \* \*

### 2. ROUTE CHARACTERISTICS

#### 2a. Facility Slope and Intervening Terrain

- Average slope of facility/site in percent:

The site is relatively flat (less than 1%).

- Name description of nearest down-slope surface water:

The only down slope water within two miles is a man-made dairy pond.

- Average slope of terrain between facility and above-cited surface water body in percent:

The average slope is less than 1%.

- Is the facility located either totally or partially in surface water?  
Yes / No (circle one)

- Is the facility completely surrounded by areas of higher elevation?  
Yes / No (circle one)

HRS Section Score: 0 (Ref. 1,12,13)

#### 2b. 1-Year 24-Hour Rainfall in Inches

Less than 0.75

HRS Section Score: 0 (Ref. 2 )

*[Handwritten signature]*  
7-174

2c. Distance to Nearest Down-slope Surface Water

The man-made dairy pond is approximately 1,500 feet southwest of the site. No natural water is located within two miles of the site.

HRS Section Score: 0 (Ref. 1,12,13,  
15,16)

2d. Physical State of Substance at Time of Disposal

No known waste is available to surface water migration.

HRS Section Score: 0 (Ref. 1 )

\* \* \* \* \*

3. CONTAINMENT

3a. Containment

- Method(s) of waste or leachate containment:

All known hazardous wastes have been covered.

- Method with highest score:

All known hazardous wastes are covered with three feet of soil, four mil polyethylene sheeting, and capped with an additional two feet of soil.

HRS Section Score: 0 (Ref. 1 )

\* \* \* \* \*

4. WASTE CHARACTERISTICS

4a. Toxicity and Persistence

- Compound(s) evaluated:

Compound	Toxicity	Persistence	Total

*Handwritten signature*  
2-17-87



- Compound(s) with highest score:

No known compounds are available to migration.

HRS Section Score: 0 (Ref. 1 )

4b. Hazardous Waste Quantity

- Total amount of hazardous substance at the facility/site, excluding those with a containment score of zero. (Give a reasonable estimate, even if the quantity is above maximum.):

No known waste is available to surface water migration.

- Basis of estimating and/or computing waste quantity (must be documented and not assumed):

HRS Section Score: 0 (Ref. 1 )

\* \* \* \* \*

5. TARGETS

5a. Surface Water Uses

- Use(s) of surface water within 3-miles downstream of the hazardous substance:

No natural surface water is used within two miles of the site and no known hazardous wastes are available to migration.

- Is there tidal influence? Yes / No (circle one)

HRS Section Score: (Ref. 1 )

5b. Distance to Sensitive Environment

- Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:
- Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:
- Distance to critical habitat of federal endangered species or national wildlife refuge, if 1 mile or less:

HRS Section Score: 0 (Ref. 1

*[Handwritten signature]*  
7-17-8-

5c. Population Served by Surface Water

- Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static bodies) downstream of the hazardous substance and population served by each intake:

No known wastes are available to surface water. No natural surface water is located within two miles of the site.

- Compute land area irrigated by above-cited intake(s) and convert to population (1.5 people per acre):

- Total population served: 0

- Name and description of nearest above-cited water bodies:

- Distance from probable point of entry to above-cited intakes (stream miles):

HRS Section Score: 0 (Ref. 1,12,13,  
15,16)

\* \* \* \* \*

*Handwritten signature*  
7-17-07

## AIR ROUTE

### 1. OBSERVED RELEASE

#### 1a. Contaminants Detected in Ambient Air

None observed.

- Date and location of detection of contaminants:
- Method used to detect contaminants:
- Rationale for attributing contaminants to the site:

HRS Section Score: 0 (Ref. 1,15 )

\* \* \* \* \*

### 2. WASTE CHARACTERISTICS

#### 2a. Reactivity and Incompatibility

- Most reactive compound:
- Most incompatible pair of compounds:

HRS Section Score: (Ref. )

#### 2b. Toxicity

- Most toxic compound:

<u>Compound</u>	<u>Toxicity</u>

HRS Section Score: (Ref. )

#### 2c. Hazardous Waste Quantity

- Total quantity of hazardous waste at the facility/site:

*Handwritten signature and date:*  
7-17-88

- Basis of estimating and/or computing waste quantity:

HRS Section Score: (Ref. )

\* \* \* \* \*

### 3. TARGETS

#### 3a. Population Within 4-mile Radius

- Enter data under respective radius and indicate how determined:

0 to 4 miles	0 to 1 mile	0 to 1/2 mile	0 to 1/4 mile

HRS Section Score: (Ref. )

#### 3b. Distance to Sensitive Environment

- Distance to 5-acre (minimum) coastal wetlands, if 2 miles or less:
- Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:
- Distance to critical habitat of an endangered species, if 1 mile or less:

HRS Section Score: (Ref. )

#### 3c. Land Use

- Distance to commercial/industrial area, if 1 mile or less:
- Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:
- Distance to residential area, if 2 miles or less:
- Distance to agricultural land in production within past 5 years, if 1 mile or less:

*Handwritten signature*  
7-17-87

- Distance to prime agricultural land in production within past 5 years, if 2 miles or less:
- Is a historic or landmark site (National Register of Historic Places and National Natural Landmarks) within the view of the site:

HRS Section Score: (Ref. )

*Handwritten signature*  
7-17-87

## FIRE AND EXPLOSION

### FIRE MARSHAL'S STATEMENT:

This site poses no fire/explosive potential (Ref. 16).

#### 1. CONTAINMENT

- Hazardous substance present:
- Type of containment, if applicable:

HRS Section Score: (Ref. )

\* \* \* \* \*

#### 2. WASTE CHARACTERISTICS

##### 2a. Direct Evidence

- Type of Instrument and Measurement:

HRS Section Score: (Ref. )

##### 2b. Ignitability

- Compound considered:

HRS Section Score: (Ref. )

##### 2c. Reactivity

- Most reactive compound:

HRS Section Score: (Ref. )

##### 2d. Incompatibility

- Most incompatible pair of compounds:

HRS Section Score: (Ref. )

*Handwritten signature*  
7-17-87

2e. Hazardous Waste Quantity

- Total quantity of hazardous substance(s) at the facility/site:
- Basis for estimating and/or computing waste quantity:

HRS Section Score: (Ref. )

\* \* \* \* \*

3. TARGETS

3a. Distance to Nearest Population

HRS Section Score: (Ref. )

3b. Distance to Nearest Building

HRS Section Score: (Ref. )

3c. Distance to Nearest Sensitive Environment

- Distance to wetlands:
- Distance to critical habitat:

HRS Section Score: (Ref. )

3d. Land Use

- Distance to commercial/industrial area, if 1 mile or less:
- Distance to national or state park, forest, or wildlife refuge, if 2 miles or less:
- Distance to residential area, if 2 miles or less:
- Distance to agricultural land in production within past 5 years, if 1 mile or less:

*[Handwritten signature]*  
7-17-8

- Distance to prime agricultural land in production within past 5 years,  
if 2-miles or less:

- Is a historic or landmark site within view of the site?  
Yes / No (circle one)

HRS Section Score: (Ref. )

3e. Population Within 2-Mile Radius

HRS Section Score: (Ref. )

3f. Buildings Within 2-Mile Radius

HRS Section Score: (Ref. )

*[Handwritten signature]*  
7-17-87



DIRECT CONTACT

1. OBSERVED INCIDENT

1a. Date, Location, and Pertinent Details of Incident

No observed incident reported.

HRS Section Score: 0 (Ref. 1,15 )

\* \* \* \* \*

2. ACCESSIBILITY

2a. Describe Type of Barrier(s)

Site is not fenced. However, the operator's residence is on site.

HRS Section Score: 1 (Ref. 17 )

\* \* \* \* \*

3. CONTAINMENT

3a. Type of Containment, if Applicable

The known hazardous waste is covered with three feet of soil, four mil polyethylene sheeting, and capped with an additional two feet of soil.

HRS Section Score: 0 (Ref. 1 )

\* \* \* \* \*

4. WASTE CHARACTERISTICS

4a. Toxicity

- Compounds evaluated:

<u>Compound</u>	<u>Toxicity</u>
No compounds available for contact.	

- Compound with highest score:

HRS Section Score: 0 (Ref. 1 )

*[Handwritten signature]*  
7-17-87

\* \* \* \* \*

5. TARGETS

5a. Population Within 1-mile Radius of Site

No compounds available for contact.

HRS Section Score: (Ref. ~1 )

5b. Distance to Critical Habitat (of Endangered Species)

HRS Section Score: (Ref. )

\* \* \* \* \*

*Handwritten signature*  
7-17-87

## REFERENCES

1. Ecology and Environment, Inc., June 1986. Final Report for Resource Recovery Corporation, Pasco, Washington.
2. U.S. Environmental Protection Agency (USEPA), 1984, Uncontrolled Hazardous Waste Site Ranking System, A User's Manual. 47FR 31220-31241.
3. Kimberly Jr., John R., President, Resource Recovery Corporation, July 2, 1980. Letter to Department of Ecology.
4. Washington Department of Ecology, Dec. 1973. Industrial Waste Disposal Site Evaluation.
5. Resource Recovery Corporation, June 11, 1973 to January 17, 1975, Monthly Waste Summaries to Washington Department of Ecology.
6. Personal Communication, May 27, 1987. Pat Barttels, City of Pasco Engineering Department, Engineering Technician, to Charles F. Pitz, E&E, Seattle.
7. Washington State Well Logs.
8. State of Washington Public Water Supply System Listing.
9. Washington State Water Rights Data.
10. U.S. Geological Survey Well Records.
11. Washington State Well Log for John Dietrich's Well located at SW 1/4, NW 1/4, Sec. 22, T9N, R30E.
12. U.S. Geological Survey (USGS), 1964. Pasco, Washington, Quadrangle Map, 7.5 Minute Series, Photo Revised 1973.
13. U.S. Geological Survey (USGS)), 1979. Glade, Washington Quadrangle Map, 7.5 Minute Series.
14. Personal Communication, May 28, 1987. Cindy Christian, Washington Department of Ecology, Eastern District Office, to Charles F. Pitz, E&E, Seattle.
15. Personal Communication, May 29, 1987. Jean Tomlinson to Gloria Skinner, E&E, Seattle.
16. Personal Communication, June 1, 1987. Don Carter, Franklin County Fire Marshall to Gloria Skinner, E&E, Seattle.
17. Ecology and Environment, Inc., January 1985. Preliminary Site Inspection Report of Resource Recovery Corporation, Pasco, Washington.
18. Personal Communication with Richard Heinemeyer, 7/17/87

*Charles F. Pitz*  
7-17-87



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, D.C. 20460

OFFICE OF  
SOLID WASTE AND EMERGENCY RESPONSE

MAY 17 1988

MEMORANDUM

SUBJECT: Municipal Landfill Support Documentation

FROM: Scott Parrish, Chief  
Hazard Ranking and Listing Branch

TO: The Record

In an effort to ensure that the worst sites are being addressed first, the Agency has elected to require some special documentation for sites considered to be municipal landfills. This position was detailed in an August 21, 1987 memorandum from Henry Longest II to the Regional Offices. Consequently, for each municipal landfill being proposed in Update #7 to the National Priorities List, a cover letter is being included with the Hazard Ranking System package. This cover letter summarizes the health and environmental concerns at the landfill. Specifically, the cover letter examines the site history to indicate the types of materials disposed or believed disposed at the site (if known), presents any monitoring data indicating a release from the site, and provides a general assessment of the environmental and public health risks at the site.

Attached is the municipal landfill cover letter for this site.

Attachment

## PASCO SANITARY LANDFILL

The Pasco Sanitary Landfill covers 250 acres and is located 1.5 miles northeast of Pasco, Washington in an area dominated by irrigated agricultural fields and range land. The landfill is privately owned and operated and was converted from a waste burning dump to sanitary landfill in 1971. In 1972, Resource Recovery Corporation leased a portion of the landfill and operated a regional hazardous waste disposal site under a Washington Department of Ecology (Ecology) permit until December 1974 when the lease terminated.

Over 47,000 drums of various hazardous substances were deposited in the leased portions of the landfill and covered by three feet of soil. Wastes known to be deposited include chlor-alkali sludge, paints, resins, herbicide manufacturing wastes, caustics, and empty pesticide containers.

In a 1985 site inspection by EPA, tetrachloroethylene (32 ppb) and trichloroethylene (480 ppb) were detected in monitoring wells on site. When sampled in 1986 by EPA, low-level organics contamination was detected in three domestic wells downgradient of the landfill. Further investigation by EPA in 1987 revealed that levels of tetrachloroethylene had increased to 72 ppb in an on-site monitoring well and trichloroethylene had increased to 1900 ppb, also in an on-site monitoring well. Low-level organics contamination was detected in only one domestic well downgradient at levels much lower than drinking water standards. Highly variable levels of inorganics had been detected in the 1985, 1986, and 1987 on-site groundwater samples. The variability has been attributed to siltation, different sampling techniques, and a highly channelized groundwater flow beneath the landfill.

The Pasco Sanitary Landfill poses potential risks to the environment and public health. There is a drinking water well on site which supplies water to two nearby residences. Low level organics contamination has been detected in nearby drinking water wells, although it is not clear at this time whether this contamination can be directly attributed to the landfill. Groundwater is used by over 1,000 people within three miles for drinking and is also used to irrigate almost 10,000 acres of land.

The landfill is currently operating under an Ecology permit and is under an Ecology administrative order to conduct a quarterly groundwater monitoring program using on-site monitoring wells. In addition, the landfill had been proposed for expansion.



## ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

FINAL REPORT FOR  
RESOURCE RECOVERY CORPORATION  
PASCO, WASHINGTON

TDD R10-8410-14

Report Prepared By: Ecology and Environment, Inc.  
Project Leader: Andrew Hafferty  
Report Date: June 1986

Submitted To: J.E. Osborn, Regional Project Officer  
Field Operations and Technical Support Branch  
U.S. Environmental Protection Agency  
Region X

## ABSTRACT

Ecology and Environment, Inc. (E&E), Seattle, Washington conducted a Field Investigation at the Resource Recovery Corporation Waste Disposal Site in Pasco, Washington during July and August 1985. The investigation was designed to determine if industrial wastes buried at the site between 1972 and 1974 had migrated from several known buried disposal zones.

Resource Recovery Corporation (RRC) received and disposed of several million gallons of liquid industrial wastes consisting primarily of chlor-alkali sludge, acidic metal cleaning and metal finishing wastes, paints, resins, resin by-products, cutting oil, and other industrial materials; and 50,000 drums of material, including herbicide manufacturing wastes, paint and oil sludges, caustics, and empty pesticide containers.

Two monitoring wells were installed by E&E during this investigation downgradient of the ground water flow beneath each of the four disposal zones. One upgradient well was completed to establish background levels of contaminants.

Stainless steel monitoring wells were constructed and developed, and sampled together with several nearby existing monitoring wells. Ground water samples were collected for standard Hazardous Substance List (HSL) compounds and herbicides, and analyzed using the Environmental Protection Agency's Contract Laboratory Program (CLP) and EPA Region X Laboratory.

Soil samples were analyzed for the same parameters as ground water except for HSL volatile organic compounds. Soils in the area consisted primarily of sands and gravels from the surface to the maximum vertical extent of drilling, approximately 100 feet below grade. Measured ground water elevations verified that the ground water gradient is to the southwest. Ground water was encountered between 40 and 77 feet below the land surface.

No evidence of herbicide or herbicide waste migration was found and only trace amounts of other contaminants were detected outside burial zones. There are no potable water wells within one mile downgradient of the site and it appears unlikely that nearby irrigation wells could be adversely affected.

Annual or biannual sampling and laboratory analyses of ground water collected from on-site monitoring wells is recommended as a precaution designed to detect any changes in water quality.

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION . . . . .	1
2.0 INVESTIGATION OBJECTIVES AND TASKS . . . . .	2
2.1 Objectives . . . . .	2
2.2 Tasks . . . . .	2
3.0 SITE HISTORY AND DESCRIPTION . . . . .	5
3.1 Site Location . . . . .	5
3.2 Site History . . . . .	5
3.3 Waste Management Practices . . . . .	8
4.0 ENVIRONMENTAL CHARACTERISTICS . . . . .	13
4.1 Physical Setting . . . . .	13
4.2 Meteorology . . . . .	13
4.3 Regional Geology . . . . .	14
4.4 Hydrology . . . . .	19
4.5 Surface Water . . . . .	23
4.6 Demography . . . . .	23
4.7 Aerial Photography . . . . .	23
5.0 FIELD INVESTIGATION . . . . .	25
5.1 Introduction . . . . .	25
5.2 Detailed Site Investigation . . . . .	25
5.2.1 Surveying/Ground Water Elevation Verification . .	25
5.2.2 Well Drilling and Installation . . . . .	27
5.2.2.1 Soil Boring and Soil Sample Collection .	27
5.2.2.2 Well Installation and Ground Water Sampling . . . . .	30
6.0 RESULTS AND DISCUSSION . . . . .	36
6.1 Introduction . . . . .	36
6.2 Subsurface Soil Lithology . . . . .	36
6.3 Analytical Results for Soils . . . . .	36
6.3.1 Subsurface Soil Gases . . . . .	36
6.3.2 Subsurface Soil Volatile Organics Compounds . . .	39
6.3.3 Subsurface Soil Base/Neutral/Acid (BNA) Compounds . . . . .	39
6.3.4 Subsurface Soil Pesticides and PCBs . . . . .	42
6.3.5 Subsurface Soil Herbicides . . . . .	43
6.3.6 Subsurface Soil Tentatively Identified Compounds (TICs) . . . . .	44
6.3.7 Subsurface Soil Inorganic Results . . . . .	44



6.4	Analytical Results for Ground Water . . . . .	48
6.4.1	Field Measurements of pH, Conductivity, and Temperature . . . . .	48
6.4.2	Volatile Organics Compounds in Ground Water . . .	48
6.4.3	Base/Neutral/Acid (BNAs) Compounds in Ground Water . . . . .	53
6.4.4	Pesticides and PCBs in Ground Water . . . . .	53
6.4.5	Herbicides in Ground Water . . . . .	54
6.4.6	Tentatively Identified Compounds (TICs) in Ground Water . . . . .	54
6.4.7	Inorganic Analyses of Ground Water . . . . .	54
7.0	SUMMARY AND RECOMMENDATIONS . . . . .	62
7.1	Conclusions . . . . .	62
7.2	Recommendations . . . . .	64

#### REFERENCES

APPENDIX A - Aerial Photography

APPENDIX B - Drilling and Sample Logs

APPENDIX C - Sample Documentation Summary

APPENDIX D - Analytical Requirements (EPA Hazardous Substance List)

APPENDIX E - Quality Assurance Memoranda

APPENDIX F - Subsurface Soil Analytical Results

APPENDIX G - Ground Water Analytical Results

#### LIST OF TABLES

<u>Table</u>	<u>Page</u>
3.1 Waste Quantities and Burial Location . . . . .	9
3.2 Composition of Solid Wastes From Herbicide Production . . . . .	11
4.1 Description of Geologic Units . . . . .	16
4.2 Ground Water Levels, December 1982 . . . . .	22
5.1 Subsurface Soil Sample Summary . . . . .	29
5.2 Ground Water Sample Summary . . . . .	33
6.1 Positively Identified Compounds in Subsurface Soil . . . . .	40
6.2 Comparison of Creosote Composition to Soil Data . . . . .	41
6.3 Summary of Tentatively Identified Compounds in Subsurface Soil . . . . .	45
6.4 Statistical Summary of All Results for Subsurface Soil . . . . .	46-47
6.5 Field Measurements of pH, Conductivity, and Temperature . . . . .	49
6.6 Positively Identified Volatile Organic Compounds in Ground Water . . . . .	50

<u>Table</u>	<u>Page</u>
6.7 Summary of Tentatively Identified Compounds in Ground Water .	55
6.8 Statistical Summary of Ground Water Data . . . . .	56
6.9 Inorganic Results of Ground Water Analyses vs. Time . . . . .	61

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
2.1 Investigation Strategy . . . . .	3
3.1 Location Map . . . . .	6
3.2 Vicinity Map . . . . .	7
3.3 Site Map . . . . .	10
4.1 Subsurface Soil Temperatures . . . . .	15
4.2 Geologic Cross-Section Transect Locations . . . . .	17
4.3 Geologic Cross-Sections . . . . .	18
4.4 Ground Water Contours, April 1981 . . . . .	20
4.5 Ground Water Contours, December 1982 . . . . .	21
5.1 Ground Water Contours, July 1985 . . . . .	26
5.2 E&E Monitoring Well Locations . . . . .	28
5.3 E&E Monitoring Well Construction Details . . . . .	32
5.4 Monitoring Well Screen Depths and Water Levels, July/August 1985 . . . . .	34
5.5 Ground Water Contours, December 1985 . . . . .	35
6.1 Ground Surface Contour Map . . . . .	37
6.2 Subsurface Lithology . . . . .	38
6.3 Ground Water Concentrations of Aluminum . . . . .	57
6.4 Ground Water Concentrations of Iron . . . . .	58
6.5 Ground Water Concentrations of Lead . . . . .	59

## DISCLAIMER

This report has been prepared by Ecology and Environment, Inc., under EPA Contract No. 68-01-6692 and reviewed and approved for public release by the U.S. Environmental Protection Agency. Mention of commercial products does not constitute endorsement of the U.S. Government. Editing and technical content of this report are the responsibility of Ecology and Environment, Inc., Seattle, Washington and do not necessarily reflect the views or policies of the EPA.

## 1.0 INTRODUCTION

A Field Investigation (FI) was conducted at the Resource Recovery Corporation Waste Disposal Site in Pasco, Washington during July and August 1985. The FI was conducted by the Ecology and Environment, Inc. (E&E) Seattle Field Investigation Team (FIT) in accordance with the United States Environmental Protection Agency (EPA) Technical Directive Document R10-8410-14.

Resource Recovery Corporation received and disposed of 50,000 drums and several million gallons of liquid industrial wastes in five burial zones at a site in Pasco, Washington between 1972 and 1974. Liquids were evaporated to dryness from both lined and unlined ponds; the remaining sludges were buried beneath layers of soil, polyethylene sheeting, and capped with an additional soil layer. Drums were stacked and buried with a similar liner system. Ecology and Environment, Inc.'s Seattle FIT installed nine monitoring wells and submitted both soil and ground water samples to EPA Contract Laboratories for analyses in an effort to determine if contaminants had migrated out of the burial zones.

Summarized in this report are investigation objectives and tasks, site history, environmental characteristics, sampling techniques and methodology, results of the investigation, analytical data, and conclusions and recommendations relevant to selection of future monitoring and/or cleanup activities.

The primary source of information for this report is data collected during the FI. Other data, primarily those generated during previous E&E site inspections of the facility, are used to complement and supplement the FI data base where appropriate.

## 2.0 INVESTIGATION OBJECTIVES AND TASKS

### 2.1 Objectives

The Field Investigation (FI) of Resource Recovery was designed to:

- 1) determine if wastes disposed of on-site by burial have migrated outside of the burial zones; 2) identify any contaminants found, and if possible, the source or sources; and 3) determine if further investigation of this site is necessary and recommend the form such future work should take based on data generated in this study. The overall investigative strategy is presented in Figure 2.1.

### 2.2 Tasks

To accomplish the above objectives, the FI was divided into five primary tasks. Brief summaries of the objectives of each task and the activities conducted are given below:

#### Task 1 - Project Initiation and Management

The purposes of this task were to solicit input from appropriate EPA, Washington State Department of Ecology (DOE), Franklin County personnel, and E&E project team members to define and initiate preparation of key project plans. Activities included project kickoff meetings, site reconnaissance, and preparation of the project work plan, quality assurance (QA) plan, health and safety plan, and sampling plan.

#### Task 2 - Initial Site Definition

The objective of this task was to obtain information and provide an initial description of the physical conditions at the Resource Recovery disposal site to develop of the detailed field investigation described in Task 3. Specific activities included compilation and review of existing chemical data for the site, preparation of a site map, and preliminary characterization of the site hydrologic features. Information for this




Figure 2.1 Investigation strategy, Resource Recovery Corporation, Pasco, Washington.

task was derived primarily from previous EPA activities at the site and reports prepared for the Department of Ecology by JUB Engineers, Inc. of Kennewick, Washington on the Pasco Sanitary Landfill (PSL), which contains within its boundaries the Resource Recovery disposal areas.

#### Task 3 - Detailed Site Investigations

Objectives of this task were to provide a description of the nature and extent of chemical contamination outside burial zones at the site and to create a data base sufficient for evaluation of potential future monitoring and/or cleanup activities. To accomplish these objectives, three phases of field activities were conducted: 1) soil and ground water characterization of each disposal zone and evaluation of the extent and magnitude of contamination immediately adjacent to each zone; 2) hydrogeologic characterization of ground water beneath the site; and 3) sampling monitoring wells constructed for the Pasco Sanitary Landfill by JUB Engineers, Inc.

#### Task 4 - Site Evaluation

Compilation, summarization, and interpretation of data collected at the site during the FI, and previous EPA (E&E) and JUB investigations were the objectives of this task. Activities included quality assurance (QA) review of the FI data base; compilation of chemical data and interpretation of the distribution and magnitude of contaminants in sediment and ground water; definition of ground water flow direction; and identification of specific sources and receptors of contamination. Emphasis was placed on investigating Resource Recovery burial zones and not landfill activities within the boundaries of the Pasco Sanitary Landfill.

#### Task 5 - Field Investigation Final Report

This report.



### 3.0 SITE HISTORY AND DESCRIPTION

This section summarizes pertinent background information and specific data related to the historical activities of Resource Recovery Corporation. Only those factors that may directly affect the potential for dispersal of buried wastes were considered.

#### 3.1 Site Location

Resource Recovery Corporation's hazardous waste burial zones are within the boundaries of the Pasco Sanitary Landfill, located approximately 1.5 miles northeast of the City of Pasco, Washington. The landfill is in the southwest quarter of Section 15, and the northwest quarter of Section 22, Township 09 North, Range 30 East, Willamette Meridian, Franklin County, Washington (Figures 3.1 and 3.2). The nearest cross streets are Kahlotus Road and Washington State Route 12. The latitude is 46°15'07"N and the longitude is 119°03'13"W (1, 2).

#### 3.2 Site History

Pasco Sanitary Landfill, originally known as the Basin Disposal Company dump site, was owned and operated by John Dietrich as a municipal waste open burning dump from 1956 to 1971. In 1971 all burning was halted and the site was converted into a sanitary landfill. In 1974, Pasco Sanitary Landfill began accepting large quantities of septic wastes for open pit disposal. In 1981, Larry Dietrich took over as owner and operator of Pasco Sanitary Landfill (3). The site is currently operated as an active landfill.

Resource Recovery Corporation (RRC) was formed by a partnership between Basin Disposal Company and Chemical Processors, Inc., of Seattle (Larry Dietrich, Waste Site Operator/Manager). RRC leased a portion of the Pasco Sanitary Landfill (PSL) in 1972 and began operations as a regional





Figure 3.1 Location map, Resource Recovery Corporation, Pasco, Washington.





# LEGEND



Areas of commercial and residential development



U.S. Route



City of Pasco municipal intake

ecology and environment, inc.  
SEATTLE, WA

JOB #: R 10-8410-14

Drawn by: L. Jowise

Date: 3-14-86

Figure 3.2 Vicinity map, Resource Recovery study area, Pasco, Washington.

hazardous waste disposal site under a Washington Department of Ecology Permit No. 5301 issued March 21, 1973 (4). The site accepted potentially hazardous wastes from various sources between early 1972 and December 1974.

### 3.3 Waste Management Practices

According to recent interviews and past records (5, 6, 7), RRC, at least to some degree, segregated wastes into five zones at the disposal site (Table 3.1 and Figure 3.3). A portion of the site, hereafter referred to as Zone A, had been used for disposal of paint wastes prior to the Resource Recovery takeover. Resource Recovery records stated that drums were stacked on end, usually three levels high after their operation began. The space between drums was backfilled with common debris, empty pesticide drums, and small, unidentified amounts of waste. The PSL pit is reported to contain drums of paint wastes, pesticide residues, wood treatment wastes, used etching solutions, metal castings wastes, and laboratory chemicals. No free liquids were discharged into this pit. Maximum burial depth of Zone A is reported to be less than 30 feet below the present surface. The west side of Zone A was utilized for open burning of municipal waste, which was intermittently compacted. The burned area extends approximately 75 feet from the western edge of the zone. A burial area reserved for large disposal items, such as cement walls from building demolition and empty fuel oil tanks, extends for 100 yards from the east side of Zone A.

Zone B is the burial site for over 5,000 herbicide waste drums from Rhodia (Rhône-Poulenc) Chemical Company, Portland, Oregon. The majority of drums contained 2,4-D Bleed, 2,4-DCP Tar, and MCPA waste. The composition of these materials is itemized in Table 3.2.

TABLE 3.1  
WASTE QUANTITIES AND BURIAL LOCATION (3)

Location	Dimensions Lining	Waste Types	Estimated Quantity	Units
Zone A	250' x 150'  bottom unlined top lined	Acids	544	drums
		Aromatic Tars	160-248	drums
		Carcinogenics (unspecified)	9	drums
		Caustics	8,774	drums
		Cadmium	11	drums
		Metal Finishing	244-304	drums
		Oil Sludge	433	drums
		Paint	10,258-24,200	drums
		Pesticides	425	drums
		Pesticide Containers (empty)	791-863	drums
Zone B	85' x 85'  bottom unlined top lined	2,4-D Manufacturing	2,011-5,080	drums
Zone C	110' x 110'  bottom unlined top lined	Acids	7,000	drums
		Acid Metal Cleaning	2,301,560	pounds
		Lime Phenol	684,967	gallons
		Metal Cleaning	185,162	gallons
		Metal Finishing	17,000-35,724	gallons
		Metal Finishing	1,460,602-1,949,652	pounds
Zone D	105' x 105'  bottom unlined top lined	Aromatic Tar	499,270	pounds
		Cutting Oil	76,350-84,300	gallons
		Fertilizer Manufacturing	228,288	pounds
		Oily Sludge	6,000-66,340	gallons
		Paint	72,475-497,418	pounds
		Paint	66,516-95,711	gallons
		Plywood Resin	1,393,380-2,215,440	pounds
		Solvents	12,648	gallons
Zone E	180' x 180'  bottom and top lined	Chlor-Alkali Sludge	10,500-11,582	Tons
Unknown		Acid Sludges	1,000	gallons
		Acid Wash Solution	312,350	pounds
		Benzoic Acid and Tar	176,000	pounds
		Chemistry Lab Reagents	1	drum
		Chrome Rinse Water	700,901	pounds
		OCP Tar	8,790	gallons
		Etching Solution	1,914	barrels
		Lime Sludge	80-160	drums
		MCPA Bleed	104,318-327,000	gallons
		MCPA Tar	2,965-3,037	drums
			939	drums
			2,813	barrels
			680	pails
		Metal Casing Wastes	3,300-5,760	drums
		Misc. Lab Chemicals	29	small containers
		NH <sub>4</sub> <sup>+</sup> and NaOH Chemical Solutions	17,238	gallons
		Oily Sludge	116,680	pounds
		Miscellaneous	435	drums
		Pesticide Containers	1,045	each
		Resin Manufacturing	392,553	gallons
		Solid Caustic Soda	44,550	pounds
		Wood Treatment/Preservative	238	drums plus
		Sludges	294,662	gallons




Figure 3.3 Site map of Resource Recovery burial zones, Pasco, Washington.

TABLE 3.2  
COMPOSITIONS OF SOLID WASTES FROM  
PRODUCTION OF RMODIA HERBICIDES (8)

Waste Name	Composition	%
2,4-D Bleed	2,4-D (as sodium salt), chlorophenols, tars	40 20 40
2,4-DCP Tar	2,4,6-trichlorophenols dichlorophenols para-chlorophenol tars	20-30 25-35 0- 5 35-45
MCP Tar	MCPA acids (as sodium salts) chlorinated cresols and other organics caustic sodium chloride	30 40 15 5

Drums were reportedly stacked at least three tiers high in this zone. However, newspaper photographs show drums stacked four high. Zone B was created by digging into the south side of a small plateau. The earthen surface above this zone is on the same level as the land to the north. Ground level south of the zone is at the same level as the base of the stacked drums.

Records provide conflicting information regarding the area covered by adjoining Zones C and D. Certain records indicate three zones existed in this area. According to Mr. L. Dietrich, only two liquid waste ponds were used. Zone C was an unlined pond used for evaporation of water from lime sludge, ammonia water, metal cleaning acids, and chrome plating wastes. Zone D is listed as an unlined pond used to hold liquid paint, oil, solvent, plywood resin, aromatic tar, pesticide, and fertilizer wastes.

Zone E was a lined chlor-alkali evaporative sludge pond that received approximately 12,000 tons of mercury-contaminated magnesia and barium sulfate liquors. The aqueous component of these wastes was removed by evaporation. No other kinds of wastes or waste materials were added to this pond.

Unsubstantiated reports claim that unsealed and leaking drums were received for disposal by RRC from Rhodia. However, Mr. L. Dietrich has stated that Rhodia drums were all new and in excellent condition.

On closure of the site in 1974, all zones were covered with three feet of soil, four mil polyethylene sheeting, and capped with an additional two feet of soil (9).

#### 4.0 ENVIRONMENTAL CHARACTERISTICS

##### 4.1 Physical Setting

RRC's hazardous waste disposal site is located in a sparsely populated rural area. Approximately 35 people live within a one-mile radius of the site. Pasco Sanitary Landfill covers 250 acres. The surface areas of the five burial zones shown in Figure 3.3 are listed below (10):

<u>Zone</u>	<u>Area</u>
Zone A	36,510 sq. ft. (0.84 acres)
Zone B	6,962 sq. ft. (0.16 acres)
Zone C	11,758 sq. ft. (0.27 acres)
Zone D	10,674 sq. ft. (0.25 acres)
Zone E	32,050 sq. ft. (0.74 acres)

The landfill is surrounded by irrigated agricultural fields and range land. Eighteen wells pump water for irrigation within a one-mile radius.

##### 4.2 Meteorology

The Cascade Mountains west of the Kennewick-Pasco-Richland (Tri-Cities) area obstruct the easterly flow of ocean-moistened air. The Rocky Mountains and ranges in southern British Columbia effectively block severe winter storms which move southward across Canada. The result is that the Tri-Cities area has a very dry climate with mild winters and hot summers (11).

The mean annual precipitation is 6.73 inches with an annual range of 4.05 to 12.90 inches. Maximum precipitation in a 24-hour period was 1.91 inches, recorded in 1957.

The Tri-Cities area has a mean annual snowfall of 14.0 inches, which falls mostly in January. Snowfall in measurable amounts can be expected from November to March.

Evaporation potential is approximately 60 inches per year with 80% of all evaporation occurring from May to October. Temperature extremes range from winter lows of  $-27^{\circ}\text{F}$  to summer highs of  $115^{\circ}\text{F}$ . Normal westerly air patterns produce mean winter low temperatures of  $22^{\circ}\text{F}$  and mean summer high temperatures of  $92^{\circ}\text{F}$ . There are 56 days per year with a maximum temperature greater than  $90^{\circ}\text{F}$  and 117 days per year with a minimum temperature less than  $32^{\circ}\text{F}$ .

Subsurface soil temperatures have been measured at the landfill (7) and are shown in Figure 4.1. Mean winter relative humidity ranges from 58-80% as compared to the summer mean relative humidity of 31-59%.


Winds are predominately from the west-northwest in summer months with a mean windspeed range of 7.5-9.0 mph, and from the northwest in the winter months with a mean windspeed range of 6.0-7.0 mph. Gusts from the southwest and south-southwest of over 70 mph have been recorded, with little variance between summer and winter maximum wind speeds.

#### 4.3 Regional Geology

Well logs and past geological studies have provided information on the regional shallow geology (7, 12, 13, 14). Soils and sediments beneath the Tri-Cities area vary in composition and origin to include: Eolian (wind transported) silts, and lacustrine deposits of silts and clays. These deposits form multiple layers having variable degrees of compaction, cementation, and constituent sizes. Depths to which these deposits extend is unknown.

Underlying these sediments is the Yakima Basalt Formation. It consists of numerous lava flows ranging from a few feet to over 200 feet in





### LEGEND

- Measured soil temperature at 10 feet below ground surface
- Measured soil temperature at 4 feet below ground surface

NOTE: Highest summer air temperature was 110° F.

ecology and environment, inc. SEATTLE, WA	
JOB #: R10-8410-14	
Drawn by: L. Jowise	Date 3-12-86

Figure 4.1 One-year soil temperature test (1971-1972), Resource Recovery Corporation, Pasco, Washington, adapted from DOE files (7).


thickness. It is not certain what formations underly the Yakima Basalt in this area. Table 4.1 presents a generalized summary of the regional geologic units.

TABLE 4.1  
DESCRIPTION OF GEOLOGIC UNITS

Geologic Unit Sub-Unit	Depth (feet)	Description	Permeability (cm/sec)
Eolian Sand & Silt	Surface	Light brown. Very fine sands & silts.	$10^{-3}$ - $10^{-5}$
Touchet Formation	0- 40	Light to medium brown. Very fine to medium grained sands. Occasionally slightly to very silty.	$10^{-3}$ - $10^{-5}$
Pasco Gravels	40- 60	Dark grey. Locally fine to coarse grained sands with occasional gravel	Greater than $10^{-3}$
Ringold Formation Ringold Sands	60-100	Dark grey. Medium to coarse grain with gravel. Gravel increasing and getting coarser with depth.	Greater than $10^{-3}$
Ringold Gravels	100-110	Tan gravel with sand.	Greater than $10^{-3}$
Ringold Clays	110-140	Blue Clay.	Greater than $10^{-3}$
Yakima Basalt	140+	Basalt	$10^{-2}$ - $10^{-5}$

Figure 4.2 shows the geologic cross-section locations and Figure 4.3 the corresponding cross-sections from the RRC disposal area (7).

The surficial soils (approximately 0-5 feet in depth) of the PSL fall into three major categories: Sagehill very fine sandy loam, Kennewick silt loam, and Quincy loamy fine sand.



#### LEGEND



Location and name of geologic cross-section



U.S. Route

15

U.S. Public Land Survey section number


ecology and environment, inc.  
SEATTLE, WA

JOB #: R 10-8410-14

Drawn by D. Pippenger

Date: 10/11/85

Figure 4.2 Locations of geologic cross-sections A-A' and B-B', Resource Recovery Corporation vicinity, Pasco, Washington, from DOE files on Pasco Sanitary Landfill (7).



ecology and environment, Inc. SEATTLE, WA	
JOB #: R 10 - 8410 - 14	
Drawn by: D. Pippenger	Date: 10/21/85

Figure 4.3 Geologic cross-sections A-A' and B-B' in the vicinity of Resource Recovery study area (adapted from DOE files on Pasco Sanitary Landfill). (7)



Sagehill and Kennewick soils are known to have slow to moderate permeabilities and high water capacity. The potential for water and wind erosion of this soil is moderate.

Quincy soil has a high water permeability and low water capacity. This soil type has only a slight risk of water erosion, but potential for wind erosion is severe.

No data on the organic carbon concentration of these surface and subsurface soils at the site is available; in general these types of soils have low organic carbon content.

#### 4.4 Hydrogeology

Ground water flow was estimated in a 1981 study by JUB Engineers, Inc., 2810 W. Clearwater Ave., Kennewick, WA (15), utilizing nine irrigation wells ranging from 1,000 to 5,600 feet from the center of the landfill (Figure 4.4). Wells were sampled April 24 and 25, 1981. Ground water flows were to the southwest with a gradient of 3.7 feet per 1,000 feet.

Subsequent testing of wells installed by JUB Engineers, Inc. specifically for monitoring the PSL site confirm that this flow pattern was unchanged through a period of quarterly and then annual sampling episodes as illustrated in Figure 4.5. Well casings were constructed of two-inch PVC pipe with screw joints below the water table and glued joints above. Bentonite seals were placed just above the water table, at twenty feet below grade, and at the surface. Two screens were set in each well. JUB well construction details are presented in a JUB summary report (14).

Depth to ground water below land surface of the wells constructed by JUB is shown in Table 4.2.




Figure 4.4 Contour map showing elevation of ground water, in feet AMSL, at Resource Recovery study area, on April 24-25, 1981, adapted from JUB report (15).




Figure 4.5 Contour map showing elevation (in feet AMSL) of ground water for December 29-30, 1982, adapted from JUB report (14).

TABLE 4.2  
GROUND WATER LEVELS  
DECEMBER 1982

Well Number	Depth Below Surface (feet)	Surface Elevation (AMSL)*	Ground Water Elevation (AMSL)
JUB 1	64.5	413.9	349.43
JUB 2	56.5	406.2	349.70
JUB 3	68.7	419.1	350.4
JUB 4	38.5	392.75	354.30
JUB Control	49	410.1	360.95

\*AMSL - Above Mean Sea Level

A ground water mound may exist 1,500 feet to the southeast of the site to form the Tomlinson Dairy Pond. Existing wells do not provide sufficient information to estimate the effect of this ground water mound on the direction of flow south of the site.

There are fifteen water and power resource service monitoring wells withing a four mile radius of the site, however, none are downgradient of the site.

Currently, eighteen operational irrigation circles exist within a one mile radius of the PSL which rely on ground water for water supply. Irrigation has had and will continue to have a significant impact on the hydrogeology in this area. Between 1950 and 1974-5 the water table in this area rose approximately ten feet but has dropped about five feet since 1975. Projected irrigation demands have been incorporated into models, the results of which predict a continuing drop in ground water elevation through the year 2000 (15).



#### 4.5 Surface Water

There is no surface water on or adjacent to the Pasco Sanitary Landfill (PSL). The topography of the site could lead to some localized drainage patterns, but the high permeability and climatic conditions of the area sustain vertical drainage patterns.

A dairy pond, approximately 2,000 feet south-southwest of the disposal area, and the Snake and Columbia Rivers, each approximately 15,000 feet southeast and southwest, respectively, of the disposal zones are the surface water bodies closest to the site.

#### 4.6 Demography

RRC is situated in a sparsely populated section of Franklin County. According to 1980 U.S. Census data, approximately 1,900 people reside within one mile of the site, 6,300 people within two miles and 16,000 within four miles.

Approximately twelve domestic and commercial wells, and eighteen irrigation wells exist within a one mile radius of the site. The total population served by the domestic wells is estimated to be 100 people. The closest major population center is the City of Pasco, approximately 1.5 miles southwest of the site. The primary water supply for Pasco residents is the Columbia River. The single most important natural resource in the site vicinity is agricultural land.

#### 4.7 Aerial Photography

Aerial photographs of the RRC site were examined to identify historic areas of activity. Three black and white photographs were obtained from the EPA.

<u>Date</u>	<u>Approximate Scale</u>
August 3, 1970	1" = 250'
May 11, 1973	1" = 335'
April 12, 1978	1" = 185'

Photographic evidence indicates no activity in burial zone areas prior to 1970. Activity is indicated in all zones in the 1973 photo except for identification of only one liquid waste pond at Zone CD. The 1978 photo shows no active RRC burial zones, but indicates ground scarring and fill over each. Photographs are presented in Appendix A.

## 5.0 FIELD INVESTIGATION

### 5.1 Introduction

Tasks 1 and 2 were completed with the preparation of the Proposed Sampling Plan for the RRC FI in June 1985 (16). Task 3 consisted of on-site field work required to define the nature and extent of environmental contamination adjacent to known hazardous waste burial zones. Task 4 consisted of collection and review of data gathered during Task 3 and interpretation of these results, integration with historical data and discussion of the environmental fate of contaminants encountered. Task 5 is complete with publication of this report.

### 5.2 Detailed Site Investigation

Field work began on July 10, 1985 and proceeded through August 8, 1985 and was designed to establish a data base of sufficient quantity and quality to permit detailed evaluation of contaminant dispersal or leaching from burial zones. A series of subtasks were completed during E&E's activities at the site.

#### 5.2.1 Surveying/Ground Water Elevation Verification

Existing monitoring wells were resurveyed using a Pentax theodolite and surveyor's chain to verify locations and elevations. Burial zones were also resurveyed, repeating a 1980 survey by A.D. Stanley and Associates of Pasco, Washington (commissioned by Resource Recovery Corporation) to detail burial zone locations. Ground water levels in the five existing monitoring wells and water supply well (WSW) were measured and plotted (Figure 5.1). This data was used to verify the ground water contours from other investigators. New E&E monitoring well locations, on the downgradient perimeters of each burial zone, were based on results of the E&E survey. An upgradient background well location was also established.




Figure 5.1 Contour map showing elevation of ground water, in feet AMSL, at Resource Recovery study area on July 9-10, 1985.

### 5.2.2 Well Drilling and Installation

The objectives of this sub-task were to: 1) provide a detailed chemical description of the subsurface geological and ground water environment downgradient of each burial zone; and 2) evaluate the magnitude of chemical contamination from each burial zone. Nine monitoring wells were installed to achieve these objectives (Figure 5.2). Monitoring wells 2 through 9 were positioned within 25 feet of surveyed burial zone perimeters. Monitoring well 1 (background) was located 420 feet southeast of the JUB control well and 1,250 northeast of the closest RRC burial zone.

#### 5.2.2.1 Soil Boring and Soil Sample Collection

Each boring was advanced to at least 22 feet below the ground water table using a six-inch inside diameter hollow stem auger fitted with a center plug. The on-site geologist used drill cuttings to classify the lithologic characteristics of the subsurface soil according to the U.S. Soils Classification System. Drilling and sample logs are presented in Appendix B. Drill cuttings were collected in clean 55-gallon drums and stored on-site for later disposal.

As each boring was advanced, a clean stainless steel spatula was used to collect approximately four ounces of soil from the auger flights per linear foot of drilling. A continuous sample was collected from each ten foot section of drilling. Each ten-foot continuous sample was homogenized and stored on ice in coolers until all samples designated for a composite were collected. Sample compositing was designed to provide soil data at depths corresponding to burial depths and at depths from below the maximum burial depth to the maximum depth of the vadose (unsaturated) zone.




Figure 5.2 Monitoring well locations at Resource Recovery site, Pasco, Washington.

Soil compositing is detailed in Table 5.1. Surface soils were not collected in order to avoid interference from wind dispersed sanitary landfill materials and crop spraying materials, and because waste burial practices were expected to prevent upward migration of contaminants.

TABLE 5.1  
SUBSURFACE SOIL SAMPLE SUMMARY

<u>Location</u>	<u>Well No.</u>	<u>Matrix</u>	<u>Type</u>	<u>Depth Below Grade</u>
Background	EE-1	Soil	Composite	10-30'
	EE-1	Soil	Composite	30-58'
Zone A	EE-2	Soil	Composite	10-30'
	EE-2	Soil	Composite	30-68'
	EE-3	Soil	Composite	10-30'
	EE-3	Soil	Composite	30-65'
Zone B	EE-4	Soil	Continuous	10-20'
	EE-4	Soil	Composite	20-43'
	EE-5	Soil	Continuous	10-20'
	EE-5	Soil	Composite	20-52'
Zone CD	EE-6	Soil	Composite	10-30'
	EE-6	Soil	Composite	30-70'
	EE-7	Soil	Composite	10-30'
	EE-7	Soil	Composite	30-73'
Zone E	EE-8	Soil	Composite	10-30'
	EE-8	Soil	Composite	30-77'
	EE-9	Soil	Composite	10-30'
	EE-9	Soil	Composite	30-73'

Composite samples were generated by adding equal volumes of soil from continuous samples to a stainless steel container and thoroughly homogenizing the mixture.

Augers and associated drilling and sampling tools were routinely decontaminated between borings to minimize cross-contamination. Routine decontamination included:

- o high pressure hot soap and water wash
- o high pressure hot water rinse
- o nanograde acetone rinse
- o nanograde methanol rinse
- o final rinse with deionized, carbon-free water

Samples and composites were submitted to assigned Contract Laboratory Program (CLP) labs for Inorganic and Organic analyses, and to the EPA Region X Laboratory for herbicide analysis. Details of soil sample documentation, packaging and shipping are summarized in Appendix C. Analytical requirements are summarized in Appendix D.

Quality Assurance reviews are presented in Appendix E. The QA reviews were performed by E&E senior chemists for those samples analyzed through the CLP and by EPA personnel for those samples analyzed at the EPA Region X Laboratory. The data were, in general, judged to be acceptable, except where flagged with qualifiers which modified the usefulness of individual values.

#### 5.2.2.2 Well Installation and Ground Water Sampling

All nine E&E monitoring wells were constructed of two-inch inside diameter (I.D.) stainless steel casing with a twenty foot length of wire-wound stainless steel well screen having a slot size of 0.010 inches. Wells were set inside the hollow stem auger and the annular space was filled as the augers were withdrawn. The lower annular space of each well was backfilled with coarse sand to at least two feet above the screen. A fine-grained sand cap of one to three feet was placed over the coarse sand pack. The annular space from the sand cap to approximately ten feet below ground surface was pressure grouted from the bottom up with a bentonite




slurry. The remaining ten feet were sealed with cement grout. A six-inch outside diameter (O.D.) protective steel casing with locking cover set at least three feet into the cement and extending two feet above ground level was placed over each well for protection (Figure 5.3).

Well development was accomplished by purging and backflushing each well four times using approximately 15 gallons of well water each time. At the end of this process, the water was clear and free of sand. Well completion diagrams and construction details are presented in Appendix B.

After development, each well was allowed to equilibrate at least 24 hours prior to collection of a ground water sample. The static water level in each well was measured and four times the standing water volume was purged from each well. After appropriate purging, sample collection was accomplished with a clean stainless steel top loading bailer. pH, conductivity, and water temperature were measured at this time.

Existing JUB monitoring wells at the PSL were also purged and sampled in the same manner as the E&E wells. Development, purge, and decontamination waters were collected in clean 55-gallon drums and stored on-site for later disposal. Ground water sampling is summarized in Table 5.2. Figure 5.4 illustrates monitoring well screen and ground water depth measured below ground surface at the time of sample collection. Ground water elevations were measured December 20-21, 1985; ground water contours based on this sampling episode are shown in Figure 5.5.



Not to scale.

ecology and environment, inc. SEATTLE, WA	
JOB #: R10-8410-14	
Drawn by: L. Jowise	Date: 3-14-86

Figure 5.3 General well construction diagram of Ecology and Environment, Inc. monitoring wells at Resource Recovery study area, Pasco, Washington.

TABLE 5.2  
GROUND WATER SAMPLE SUMMARY


<u>Location</u>	<u>Well No.</u>	<u>Matrix</u>	<u>Type</u>
Background	EE-1	Water	Grab
Zone A	EE-2	Water	Grab
	EE-3	Water	Grab
Zone B	EE-4	Water	Grab
	EE-5	Water	Grab
Zone CD	EE-6	Water	Grab
	EE-7	Water	Grab
Zone E	EE-8	Water	Grab
	EE-9	Water	Grab
PSL	JUB-1	Water	Grab
	JUB-2	Water	Grab
	JUB-3	Water	Grab
	JUB-4	Water	Grab
	JUB Control	Water	Grab
	WSW	Water	Grab

Aqueous samples were submitted to assigned CLP laboratories for Inorganic and Organic analyses, and to the EPA Region X Laboratory for herbicide analyses. Details of aqueous sample documentation, packaging and shipping are summarized in Appendix C. Analytical requirements are summarized in Appendix D.

Quality Assurance reviews are presented in Appendix E. The QA reviews were performed by E&E senior chemists for those samples analyzed through the CLP and by EPA personnel for those samples analyzed at the EPA Region X Laboratory. The data were, in general, judged to be acceptable, except where flagged with qualifiers which modified the usefulness of individual values.



# MONITORING WELLS



## LEGEND

Location of well screens

Depth of ground water

CW Control well

WSW Water supply well

ecology and environment, inc.  
SEATTLE, WA

JOB #: R10-8410-14

Drawn by L. Jowise

Date 3-26-86

Figure 5.4 Monitoring well screen depths and ground water levels, July-August, 1985, Resource Recovery study area, Pasco, Washington.




Figure 5.5 Contour map showing elevation of ground water, in feet AMSL, at Resource Recovery study area on December 20-21, 1985.

## 6.0 RESULTS AND DISCUSSION

### 6.1 Introduction

Presentation and interpretation of the geological and chemical data generated during Task 3 was the goal of Task 4. The reduced data is presented and discussed in the following sections.

### 6.2 Subsurface Soil Lithology

The upper one to two feet of soils at the site are loamy to very fine-grained sandy soils. Wind erosion and excavation has removed all or part of this layer exposing the plastic liner in places. From zero to ten feet below ground surface are silty sands. This is followed by a fine- to coarse-grained sand unit at 25 to 55 feet below ground surface. The sand is composed of clear to frosted quartz grains and brown, possibly basaltic, grains. In places the sand is cemented into thin layers. Occurring below the sand unit to the bottom of each borehole are clean gravels to gravelly sands with interbedded, unconsolidated sands.

The three major lithological units described above are found at varying depths in each borehole, indicating lateral continuity of the units across the site. Ground water was encountered between 43 and 77 feet below ground surface (Figure 6.1). Subsurface lithologies are summarized in Figure 6.2.

### 6.3 Analytical Results For Soils

#### 6.3.1 Subsurface Soil Gases

An HNU Model PI-101 was used for ambient air monitoring of organic vapors during drilling. Levels above background were encountered only at monitoring wells EE-2 and EE-3. Boring at EE-3 penetrated a strata of municipal trash which included: wood, aluminum cans, and plastic material between three and seventeen feet below ground surface. Readings of 500 ppm














Figure 6.1 Contours showing ground surface elevations, in feet AMSL, at Resource Recovery study area, Pasco, Washington.



# **LEGEND**

-  Silty Sand
-  Sand
-  Gravelly Sand
-  Gravel
-  Sandy Gravel
-  Gravelly Sand with Pebbles
-  Ground Water Level

ecology and environment, inc. SEATTLE, WA	
JOB #: R 10 - 8410 - 14	
Drawn by: D. Pippenger	Date: 1/15/86

Figure 6.2 Comparison of lithology of monitoring wells at Resource Recovery study area, Pasco, Washington.



at the borehole exit were probably due to methane-like gases normally associated with decomposition of organic materials in landfills. The maximum reading at EE-2 was 7 ppm and probably resulted from migration of soil gases from the old municipal waste burial zone which surrounds Resource Recovery burial Zone A.

#### 6.3.2 Subsurface Soil Volatile Organic Compounds

The combination of drilling techniques, ambient weather conditions, sample collection methodology, and subsurface lithology presented an unacceptably high probability of sample alteration, primarily through volatilization and loss of contaminants in the soil, prior to analysis by a laboratory. Therefore, no soil samples were submitted for volatile organic analysis.

#### 6.3.3 Subsurface Soil Base/Neutral/Acid (BNA) Organic Compounds

Low levels of Benzo (a) pyrene were found in the shallow and deep soil samples at EE-7 and in the deep soil sample from EE-3. Phenol was found in the EE-3 deep soil sample. Several compounds were indentified in the shallow soil sample from EE3. No BNAs were detected in any of the other soil samples.

Table 6.1 is a summary of all BNA data where compounds were detected and identified. Data from all BNA soil analyses are presented in Appendix F.

Many of the compounds listed in Table 6.1 are polycyclic aromatic hydrocarbons (PAHs), the major components of creosote (17). Creosote is one of the materials reported to have been disposed of in the vicinity of Zone A prior to use of the area by Resource Recovery Corporation. Table 6.2 presents pure creosote component concentrations normalized to

TABLE 6.1  
POSITIVELY IDENTIFIED BASE/NEUTRAL/ACID COMPOUNDS  
IN SUBSURFACE SOILS  
(ug/kg)

COMPOUNDS	Sample Number	EE-3 (10-30')	EE-3 (30'-GW)	EE-7 (10-30')	EE-7 (30'-GW)
PHENOL			1900J		
NAPHTHALENE		1700J			
2-METHYLNAPHTHALENE		1200J			
ACENAPHTHENE		370J			
DIBENZOFURAN		190J			
FLUORENE		270J			
PHENANTHRENE		1300J			
ANTHRACENE		200J			
DI-N-BUTYL PHTHALATE		2000J			
FLUORANTHENE		960J			
PYRENE		1400J			
BUTYL BENZYL PHTHALATE		430J			
BENZO (A) ANTHRACENE		320J			
CHRYSENE		220J			
DI-N-OCTYL PHTHALATE		1900J			
BENZO (A) PYRENE			150J	170J	160J

J = ESTIMATED CONCENTRATION (ANALYTICAL QUALITY CONTROL CRITERIA NOT COMPLETELY ACCEPTABLE)

GW = Ground Water

TABLE 6.2  
COMPARISON OF CREOSOTE COMPOSITION RATIOS  
TO SHALLOW SOIL DATA FROM EE-3

COMPOUND	IN CREOSOTE	EE3 10-30FT.
PHENOL	--	--
NAPHTHALENE	.14	.81
2-METHYLNAPHTHALENE	.06	.57
ACENAPHTHENE	.43	.29
DIBENZOFURAN	.24	.15
FLUORENE	.48	.21
PHENANTHRENE	1.0	1.0
ANTHRACENE	.10	.15
FLUORANTHENE	.48	.74
PYRENE	.41	1.1
BENZO (a) ANTHRACENE	TRACE	.25
CHRYSENE	.14	.17
BENZO (a) PYRENE	TRACE	NOT DETECTED

phenanthrene concentration and compares them to ratios found in shallow soil sample EE-3. Weathering of each component of creosote proceeds at different environmental rates. Data from other landfills also exhibits similar variations from unweathered ratios (18). Increased levels of naphthalenes may be due to coal tar, which is often mixed with creosote in wood preservatives.

Phenol (carbolic acid), a common creosote additive, was identified in EE-3 soil. Phenol is extremely soluble in water as compared to the components of creosote and coal tar and has a much lower log Poct (octanol/water partition coefficient) value indicating a lower affinity towards soil adsorption (19). Migration downward as surface rain water percolates through the soil is expected.

Three phthalates were also identified. Phthalates are used and formulated in plastizing agents, plastic manufacturing, recycling, and processing. They are ubiquitous in the environment and nearly always encountered in landfills (20). Phthalates are highly lipophilic and exhibit low aqueous solubility; they are similar to creosote in this respect.

Benzo (a) pyrene, a high molecular weight PAH, is a combustion by-product of open air refuse burning (21). Because it was detected at low levels in only three samples, it is not expected to present a hazard despite its published toxicity.

Phenol, PAHs, and phthalates exhibit toxicity through ingestion and in aquatic organism testing. However, it is inappropriate to extrapolate this toxicity data to subsurface soil values.

#### 6.3.4 Subsurface Soil Pesticide and PCBs

Only two contaminants were positively identified, both in shallow soil at EE-3:

<u>PCB</u>	<u>CONCENTRATION</u>
Aroclor 1242	3100 ug/kg
Aroclor 1254	1400 ug/kg

Both values are estimates, as laboratory quality control did not meet EPA criteria. It is probable that because both Aroclors are mixtures of chlorinated biphenyls, concentrations reported are overestimates of "true" levels. PCBs are extremely lipophilic and virtually insoluble in water. They were used primarily in electrical transformers and capacitors, but many waste oils are contaminated with PCBs (22). Pesticide and PCB data are presented in detail in Appendix F.

PCBs are readily absorbed from aqueous solution onto any solid particles and do not easily leach from soil (23, 24). The rate of PCB movement in saturated soil has been found to be between one-tenth and one one-hundredth the rate of ground water movement (25). Rates of PCB mobility in soil vary, however, with the most heavily chlorinated PCBs being the least mobile. Therefore, migration is not expected to be significant (26).

The toxicity of PCBs has been documented (20) but extrapolation of this hazard to soil data is not possible. The levels are far less than 50,000 ug/kg, which marks the lowest level at which an oil is considered contaminated.

#### 6.3.5 Subsurface Soil Herbicides

No measurable amounts of 2,4-D; 2,4,5 T; 2,4,5-TP (Silvex); or MCPA were detected in any of the subsurface soil samples. Neither were any of the reported components of 2,4-D Bleed; 2,4-DCP Tar; or MCPA Tar solid wastes from herbicide production identified. Herbicide analysis data is presented in Appendix F.

#### 6.3.6 Subsurface Soil Tentatively Identified Compounds

A limited number of compounds , Table 6.3, were detected which are not on the Hazardous Substance List (HSL). Positive identification of all of these compounds was not possible and quantities are estimates only. Analytes appear to be chiefly hydrocarbons of unknown origin. Nineteen compounds were detected in the shallow soil sample from EE-3. This sample was collected in the former open-burning and municipal waste disposal area. Again, the presence of this class of compounds is consistent with historical waste disposal practices. A complete summary of this data is presented in Appendix F.

#### 6.3.7 Subsurface Soil Inorganic Results

Results have been statistically summarized in Table 6.4. Appendix F contains a complete list of inorganic soil analyses.

Minimum and maximum concentrations of each element are presented with corresponding sample location number to display the range of values measured for each analyte. The median is the middle value of a set of data points. All shallow subsurface soil data has been combined and statistically reduced to yield: average concentration, standard deviation, and skew. Similar data is presented for the deep soil samples. The Student's t-test was employed to determine if significant differences exist between composition of shallow versus deep soil samples. Critical (calculated) t values greater than tabled, indicate a significant difference exists between the two soil populations at the 90% confidence interval.

Aluminium, calcium, chromium, magnesium, manganese, and potassium concentrations in shallow soils are statistically greater than in deep soil samples. The highest soil concentrations of mercury, barium, and sodium were detected in EE-9 soils. These elements have been identified as compo-

TABLE 6.3  
SUMMARY OF TENTATIVELY IDENTIFIED ORGANIC COMPOUNDS  
SUBSURFACE SOILS  
(ug/kg)

COMPOUND	SAMPLE LOCATIONS AND DEPTH			
	EE-3 10-30'	EE-3 20'-GW	EE-5 10-30'	EE-5 20'-GW
<hr/>				
UNKNOWN	4200J			
DIMETHYL BENZENE ISOMER	1700J			
DIMETHYL BENZENE ISOMER	1200J			
UNKNOWN	4600J			
1-ETHYL-2-METHYL BENZENE	860J			
TRIMETHYL BENZENE	1300J			
DECANE	1800U			
P-PHOSPHORIC ACID, TRIBUTYL ESTER	1700J			
UNKNOWN	5900J			
UNKNOWN	2000J			
UNKNOWN	4200J			
UNKNOWN	7700J			
UNKNOWN HYDROCARBON	2900J			
UNKNOWN	5000J			
UNKNOWN	1800J			
UNKNOWN	9400J			
UNKNOWN	2300J			
UNKNOWN	2400J			
UNKNOWN	300J			
2-BUTOXY ETHANOL		520J		
UNKNOWN		260J		
UNKNOWN			200J	
UNKNOWN				220J

J: ESTIMATED CONCENTRATION ONLY  
GW: GROUND WATER

TABLE 6.4  
RESOURCE RECOVERY CORP., PASCO, WA.  
STATISTICAL SUMMARY OF INORGANIC RESULTS FOR SOIL  
(mg/kg)

PARAMETER	ALL SOIL DATA					SHALLOW SUBSURFACE SOIL SAMPLES			DEEP SUBSURFACE SOIL SAMPLES			CRITICAL T	TABLED T	SIGNIFICANT DIFFERENCE
	MINIMUM CONC.	SAMPLE LOCATION	MAXIMUM CONC.	SAMPLE LOCATION	MEDIAN	AVERAGE	STANDARD DEVIATION	SKEW	AVERAGE	STANDARD DEVIATION	SKEW			
ALUMINIUM	4671.00	EES 20'-GW	8934.00	EES 10-20'	7066.50	7868.44	831.73	0.13675	5762.11	960.12	0.37751	4.97	1.75	YES
ANTIMONY	4.00	EE6 10-30'	10.00	EE1 30'-GW	6.50	6.56	1.24	-0.76624	6.78	1.39	1.58768	-0.36	1.75	NO
ARSENIC	3.20	EE1 30'-GW	7.10	EES 10-20'	3.30	3.69	1.94	-0.04869	3.26	0.05	-0.22361	0.67	1.75	NO
BARIUM	79.00	EES 20'-GW	652.00	EE9 10-30'	105.00	169.33	181.15	2.46688	96.33	12.10	-0.14216	1.21	1.75	NO
BERYLLIUM	0.30	EE3 10-30'	0.60	EE6 30'-GW	0.50	0.50	0.09	-1.22474	0.41	0.11	0.45560	#	1.75	#
CAOMIUM	1.00	EE1 10-30'	1.40	EE3 10-30'	1.00	1.18	0.34	1.82571	1.04	0.10	2.06732	1.13	1.75	NO
CALCIUM	7616.00	EES 20'-GW	15703.00	EES 10-20'	11169.00	11946.00	1888.94	0.44513	10223.78	1889.17	0.68412	1.93	1.75	YES
CHROMIUM	4.00	EE4 20'-GW	28.00	EE3 10-30'	10.50	13.44	5.53	2.35936	7.67	1.94	-0.48686	2.96	1.75	YES
COBALT	11.00	EE2 10-30'	15.00	EE6 30'-GW	13.00	12.44	1.01	-0.22307	12.44	1.33	0.46128	*	1.75	NO
COPPER	10.00	EES 20'-GW	19.00	EE3 10-30'	12.00	13.00	2.96	1.22938	11.67	1.22	0.67358	1.25	1.75	NO
IRON	20000.00	EE2 10-30'	27462.00	EE4 10-20'	22890.00	23348.44	2483.46	0.25723	22570.56	1684.74	1.18219	0.78	1.75	NO
LEAD	2.90	EES 20'-GW	100.00	EE3 10-30'	5.45	16.82	31.23	2.46327	4.16	0.96	0.82732	1.22	1.75	NO
MAGNESIUM	4523.00	EES 20'-GW	8363.00	EES 10-20'	6187.50	6796.56	755.59	0.79536	5310.00	712.32	-0.06348	4.29	1.75	YES
MANGANESE	313.00	EES 20'-GW	486.00	EES 10-20'	416.50	435.56	36.22	0.20935	390.11	46.19	-0.09057	2.32	1.75	YES



TABLE 6.4 (CONT.)

STATISTICAL SUMMARY OF INORGANIC RESULTS FOR SOIL  
(mg/kg)

PARAMETER	ALL SOIL DATA					SHALLOW SUBSURFACE SOIL SAMPLES			DEEP SUBSURFACE SOIL SAMPLES			CRITICAL T	TABLED T	SIGNIFICANT DIFFERENCE
	MINIMUM CONC.	SAMPLE LOCATION	MAXIMUM CONC.	SAMPLE LOCATION	MEDIAN	AVERAGE	STANDARD DEVIATION	SKEW	AVERAGE	STANDARD DEVIATION	SKEW			
MERCURY	0.10	EE1 10-30'	0.60	EE9 10-30'	0.10	0.18	0.16	2.17238	0.11	0.03	2.47487	1.19	1.75	NO
NICKEL	8.00	EE1 10-30'	14.00	EES 10-20'	9.00	9.78	1.79	1.60545	8.67	0.50	-0.70711	#	1.75	#
POTASSIUM	1508.00	EE2 30'-GW	2942.00	EE4 10-20'	2519.00	2592.22	166.35	0.37228	2105.00	365.50	-0.28827	4.39	1.75	YES
SELENIUM	1.80	EE1 10-30'	9.50	EE7 10-30'	1.90	3.00	2.53	2.17271	2.66	2.38	2.47289	0.30	1.75	NO
SILVER	1.70	EE4 20'-GW	3.50	EE8 10-30'	2.60	2.62	0.56	0.04378	2.44	0.60	0.37146	0.65	1.75	NO
SODIUM	522.00	EE2 10-30'	1406.00	EE9 10-30'	605.00	736.33	270.82	1.85132	587.78	41.30	0.34826	1.63	1.75	NO
THALLIUM	2.00	EE1 10-30'	5.00	EE6 10-30'	2.00	2.44	1.01	2.06732	2.00	*	*	1.32	1.75	NO
TIN	9.00	EE1 10-30'	11.00	EE4 10-20'	10.00	10.00	0.50	*	9.78	0.44	-1.33631	1.00	1.75	NO
VANADIUM	35.70	EE7 30'-GW	61.30	EE4 10-20'	44.45	45.92	6.77	1.31200	44.33	5.76	0.85666	0.54	1.75	NO
ZINC	40.00	EES 20'-GW	218.00	EE7 10-30'	53.50	76.00	53.98	2.35143	47.67	6.36	0.66529	1.56	1.75	NO

NOTE: STATISTICAL ANALYSES INCLUDE VALUES FLAGGED U AND J

STUDENTS T-TEST ASSUMES DATA ARE NORMALLY DISTRIBUTED

\* DENOTES PARAMETER WAS NOT ANALYZED FOR OR CONTROL SAMPLES WERE NOT IDENTIFIED

R DENOTES PARAMETER WAS REJECTED

# THE STUDENT'S T-TEST STATISTIC IS NOT APPLICABLE BECAUSE ALL BERYLLIUM AND NICKEL DATA ARE LESS THAN A FACTOR OF 2 ABOVE THE DETECTION LIMIT.

nents of chlor-alkali wastes in the adjacent burial Zone E. Cadmium, copper, chromium and lead values were highest in soils at EE-3, the former municipal waste disposal area. Zinc and several other metals were measured above the statistical average soil levels at EE-7, adjacent to the former open pit which received liquid metal cleaning and finishing wastes. No data point was significantly different from average at the 99% confidence interval.

#### 6.4 Analytical Results For Ground Water

##### 6.4.1 Field Measurements of pH, Conductivity, and Temperature

Three parameters (pH, conductivity, and temperature) were measured in water with portable instruments in the field, Table 6.5.

Specific conductivity is an indirect measure of total dissolved solids in water, however, no direct relation exists because conductivity is a function of electrolytic species present. pH is used to measure the acidity or basicity of dilute aqueous solutions. Neither conductivity nor pH exceed Federal Drinking Water Standards.

##### 6.4.2 Volatile Organic Compounds Detected in Ground Water

Table 6.6 lists volatile organic compounds detected in wells at the site. Federal Drinking Water Guideline Recommended Highest Safe Levels (27) for each compound are also included in Table 6.6. Neither methylene chloride nor acetone are included in the table because levels measured are indicative of laboratory generated contamination.

Volatile organics (VOAs) were detected in groundwater from only three monitoring wells: EE-2, EE-3, and JUB-2. Monitoring well EE-3 is located beneath an area formerly used for open burning and municipal waste

TABLE 6.5  
FIELD MEASUREMENTS TAKEN AUGUST 8, 1985

MONITORING WELL	CONDUCTIVITY UMHOS	TEMPERATURE °C	pH
EE1	490	18	7.7
EE2	710	17	7.2
EE3	570	18	6.8
EE4	600	18	*
EE5	700	18	*
EE6	475	18	*
EE7	491	18	*
EE8	490	17	*
EE9	550	18	*

\* : NO DATA

TABLE 6.6  
POSITIVELY IDENTIFIED VOLATILE ORGANIC COMPOUNDS IN GROUND WATER  
(ug/l)

COMPOUND	FEDERAL DRINKING WATER GUIDELINES HIGHEST SAFE LEVEL	SAMPLE LOCATION		
		EE-2	EE-3	JUB-2
1,1-DICHLOROETHYLENE	400	5.0	50.0U	13.0
1,1-DICHLOROETHANE	-	15.0	64.0	35.0
TRANS-1, 2-DICHLOROETHYLENE	270	9.0	50.0U	15.0
CHLOROFORM	100	3.0	50.0U	17.0
1,1,1-TRICHLOROETHANE	1000	70.0	420.0	168.0
TRICHLOROETHYLENE	4.5	65.0	480.0	164.0
TETRACHLOROETHYLENE	3.5	32.0	5.0U	5.0U
TOLUENE	-	5.0U	230.0	5.0U
TOTAL XYLENE	620	5.0U	63.0	5.0U

disposal. Wells EE-2 and JUB-2 are both down gradient of ground water flow through this area. All three are on the perimeter of burial Zone A, Figure 5.2.

Interpretation of the data is complicated by elevated detection limits for the sample from well EE-3. Materials may have been present at EE-3 but below laboratory reported detection limits.

The seven chlorinated volatiles listed in Table 6.6 detected have numerous uses as solvents, degreasers, paint and varnish intermediates, paint removers, dry cleaning fluids, plastics manufacturing, organic synthesis, etc. The presence of these compounds in ground water below the former municipal waste disposal and burning area is not unusual. These compounds are ubiquitous in the drinking water of industrialized areas (28).

All the compounds in Table 6.6 have high vapor pressures and a low potential for bioaccumulation. Removal of these compounds is almost exclusively through volatilization from the aqueous system and degassing out of the vadose zone followed by rapid oxidation in the atmosphere by hydroxyl radicals. Movement of these contaminants in ground water will be controlled in part by the following factors: density of the detected contaminants will cause downward vertical migration while volatility would lead to upward movement; high soil/water partition coefficients may result in adsorption onto soils retarding migration; bacteria may decrease contaminant concentrations through biodegradation; dispersion caused by diffusion may be assumed to be negligible; recharge and the soil matrix will control horizontal and vertical ground water advection.

Assuming a geometric progression for contaminant concentration gradients in ground water and using the data from EE-3 and either EE-2 or JUB-2, aqueous volatile organic concentrations could decrease to below 5

ug/l (the standard EPA/CLP detection limit for these compounds) less than 800 feet down gradient from monitoring well EE3. Since the dates of active site use are known, a migration rate has been estimated (based on this geometric decrease) to be very roughly 40-80 feet per year. The closest irrigation well is 1600 feet down gradient from well EE3, therefore, horizontal migration is not expected to be a significant problem. Irrigation wells are usually screened deeper in an aquifer than monitoring wells since a constant water supply for high volume pumping is required. Irrigation supply water may be vertically displaced away from potentially contaminated shallow zones of ground water. Studies of aquifer decontamination and water reclamation based on ambient air spray head aeration (29) have demonstrated a 90% removal of chlorinated volatile organics. Irrigation should produce an effect equivalent to aeration especially if volatilization from the wetted surface of soil is taken into account. Further, since irrigation water which percolates down through the vadose zone soil to ground water would be significantly less contaminated with these compounds than the ground water, dilution of ambient ground water contaminants by cleaner water will result.

Two aromatic volatile organics, toluene and xylene, were detected in ground water from monitoring well EE-3. The principal source of these compounds may be coal tar as noted in Section 6.3.3, although they are both major constituents of gasoline and are used in numerous paint and lacquer manufacturing processes (19).

High log Poet values for toluene and xylene mean adsorption may be significant. However, both toluene and xylene possess high vapor pressures and may biodegrade to methylated catechols (28). The principle mechanism

for removal is volatilization and subsequent airborne photodecomposition. Environmental fate and movement should be similar to the chlorinated volatiles.

#### 6.4.3 Base/Neutral/Acid (BNA) Organic Compounds Detected in Ground Water

4-methyl phenol was detected at 6 ug/l in water from monitoring well EE-3. Bis (2-ethylhexyl) phthalate (BehP) was detected in: EE-2 at 6 ug/l, EE-4 at 39 ug/l, and EE-5 at 7.8 ug/l. No other BNAs were detected in any of the other wells sampled by E&E. Appendix G contains complete tables of BNA data from aqueous analyses.

4-methylphenol (p-cresol) is a water soluble component of coal tar and further supports the record that this material was buried in the municipal waste disposal area above EE3. No drinking water quality guideline limits are reported for cresol.

BehP is in the same chemical family of compounds as the three phthalates identified in the BNA soil results from EE3. However, it is the least soluble of the four phthalates found, and its presence may be the result of laboratory induced contamination of the sample. No drinking water standards are reported for phthalates. BehP is not volatile and is likely to be absorbed onto soils rather than solubilize into water (28).

None of the PAHs found in soils at EE3 were detected in the ground water.

#### 6.4.4 Pesticides and PCBs Detected in Ground Water

No pesticides or PCBs were reported in any of the sampled wells above laboratory detection limits. PCBs were not found in the ground water at EE-3, where both Aroclor-1242 and Aroclor-1254 were measured in the shallow soil sample. A complete data list is in Appendix G.

#### 6.4.5 Herbicides Detected in Ground Water

No herbicides, herbicide production wastes or by-products were detected in any of the ground water samples collected during this investigation. Appendix G contains a complete listing of aqueous herbicide results.

#### 6.4.6 Tentatively Identified Organic Compounds (TICs) in Ground Water

The largest number and highest amount of TICs detected was in water from monitoring well EE-3 (Table 6.7). Substituted benzene compounds predominate and may be components of coal tar, gasoline, or paint wastes. Anthropogenic origins for all TICs cannot be established. See Appendix G for a complete list of TIC data.

#### 6.4.7 Inorganic Analyses of Ground Water

Table 6.8 summarizes the inorganic ground water results, however, no t-test statistics were computed. Lithologic data and inorganic soil analyses show uniform distribution of metals over the site. Ground water analysis results are extremely heterogeneous over very short distances. Elemental concentration bar graphs, projected onto a site map, are presented in Figures 6.3, 6.4, and 6.5 for three metals. The spatial variations in concentrations across the site shown in these figures do not reflect the expected levels based on ground water flow.

Significant variations in concentrations were found in adjacent wells throughout the site. The two upgradient background monitoring wells, EE-1 and JUB-Control are approximately 420 feet apart in similar lithologies and at the same ground water elevation. Concentrations at EE-1 are the lowest values measured while JUB-Control has the highest values for eighteen out of twenty-four analytes. Data from well sets EE-5/EE-4, JUB-3/WSW, and EE-2/EE-3/JUB-2 also show widely variable data for nearly all analytes. Of



TABLE 6.7  
 RESOURCE RECOVERY CORP., PASCO, WA.  
 SUMMARY OF TENTATIVELY IDENTIFIED BASE/NEUTRAL/ACID COMPOUNDS FOR  
 GROUNDWATER SAMPLES COLLECTED JULY/AUGUST 1985  
 (ug/l)

LOCATION:	EE1	EE2	EE3	EE4	EE5	EE6	EE7	EE8	EE9	JUB CNTR	JUB1	JUB2	JUB3	JUB4	WSW
COMPOUND															
ALCOHOL	190J														
ALCOHOL	20J														
ALKENE	600J	16J				62J									
HYDROCARBON	22J														
CARBOXYLIC ACID	12J														
CARBOXYLIC ACID	94J														
UNKNOWN	26J	3J	4J		15J	68J	12J								
SATURATED HYDROCARBON		22J													
UNKKNOWN		6J													
DIMETHYL BENZENE			696J												
DIMETHYL BENZENE			364J												
ALKYL BENZENE			12J												
SUBSTITUTED BENZENE			26J												
ALKYL BENZENE			120J												
TRIMETHYL BENZENE			42J												
METHYL KETONE			6J												
ALKYL BENZENE			40J												
ALKYL BENZENE			84J												
ALKYL BENZENE			20J												
ALKYL BENZENE			6J												
SUBSTITUTED ALKANE			16J												
SUBSTITUTED ALKANE			8J												
KETONE			1CJ												
KETONE						160J									
UNKNOWN						12J									
SUBSTITUTED CARBOXYLIC ACID							158J								
UNKNOWN								14J							
UNKNOWN								6J							
PHTHALATE								6J							
UNKNOWN									18J						
UNKNOWN									8J						
UNKNOWN									4J						
UNKNOWN															
HYDROCARBON				6.7J											
UNKNOWN				11J											
UNKNOWN				27J											
HEXADECANOIC ACID				18J											
UNKNOWN				22J											
UNKNOWN				25J											
CARBOXYLIC ACID										7.6J	6.2J		4.8J	5.6J	
C-3 SUBSTITUTED BENZENE											6.2J		4.8J	7.2J	
C-2 SUBSTITUTED BENZENE												13J			

J: Estimated Concentration

TABLE 6.8  
STATISTICAL SUMMARY OF INORGANIC RESULTS FOR ALL GROUND WATER  
(ug/l)

PARAMETER	MINIMUM CONC.	SAMPLE LOCATION	MAXIMUM CONC.	SAMPLE LOCATION	MEDIAN	AVERAGE TEST SAMPLES	STANDARD DEVIATION TEST	SKEW TEST SAMPLES
ALUMINIUM	61.00	WSW	129800.00	JUB CNTR.	22560.00	32366.93	33734.22	1.68778
ANTIMONY	12.00	EE1/WSW	19.00	EE2	12.00	12.73	2.02	2.48679
ARSENIC	10.00	EE1/WSW	40.00	JUB WELL 4	10.00	14.04	10.00	2.15411
BARIUM	63.00	WSW	2148.00	EES	526.00	746.80	668.19	0.99745
BERYLLIUM	0.50	EEQ	10.40	JUB CNTR.	2.10	2.65	2.55	1.91232
CADMIUM	1.90	EE1/WSW	3.50	EE4	1.90	2.21	0.51	1.34235
CALCIUM	57180.00	WSW	332200.00	JUB CNTR.	94780.00	110555.33	70881.10	2.24792
CHROMIUM	11.00	WSW	176.00	JUB CNTR.	60.00	63.47	43.37	1.29584
COBALT	3.90	EE1/WSW	184.00	JUB CNTR.	32.00	47.45	48.86	1.54527
COPPER	1.70	WSW	254.00	JUB CNTR.	62.00	77.38	70.49	1.21140
IRON	24.00	WSW	268300.00	JUB CNTR.	52150.00	73957.53	72112.50	-
LEAD	5.00	WSW	180.00	JUB CNTR.	36.95	45.99	33.70	-0.69075
MAGNESIUM	20600.00	WSW	99060.00	JUB CNTR.	29930.00	37886.67	20654.54	1.92679
MANGANESE	3.00	WSW	5281.00	JUB CNTR.	1394.00	1742.80	1468.37	0.89281
MERCURY	0.13	EE1	1.00	JUB CNTR.	0.20	0.32	0.24	1.82907
NICKEL	16.00	WSW	138.00	JUB CNTR.	46.00	53.27	39.19	1.08324
POTASSIUM	7315.00	WSW	26000.00	JUB CNTR.	11690.00	12289.53	5052.73	1.60305
SELENIUM	5.00	WSW	25.00	JUB CNTR.	25.00	23.67	5.16	-3.47440
SILVER	3.30	EE1	19.10	JUB CNTR.	6.80	7.25	4.17	1.49099
SODIUM	31920.00	EE3	47580.00	EE2	35780.00	36338.67	4054.41	1.53454
THALLIUM	10.00	EE1/WSW	10.00	JUB CNTR.	10.00	10.00	*	*
TIN	18.00	EE1	88.00	JUB WELL 2	18.00	25.13	19.46	2.64291
VANADIUM	15.90	EE1	493.70	JUB CNTR.	111.30	136.81	123.82	1.67899
ZINC	8.00	WSW	673.00	JUB CNTR.	289.00	277.80	168.18	0.55741

NOTE: STATISTICAL ANALYSES INCLUDE VALUES FLAGGED U AND J  
STUDENTS T-TEST ASSUMES DATA ARE NORMALLY DISTRIBUTED  
\* DENOTES PARAMETER WAS NOT ANALYZED FOR OR CONTROL SAMPLES WERE NOT IDENTIFIED  
R DENOTES PARAMETER WAS REJECTED




Figure 6.3 Concentration of aluminum, in micrograms per liter, measured in ground water at monitoring wells. Resource Recovery study area, Pasco, Washington.




Figure 6.4 Concentration of iron, in micrograms per liter; measured in ground water at monitoring wells, Resource Recovery study area, Pasco, Washington.




Figure 6.5 Concentration of lead, in micrograms per liter, measured in ground water at monitoring wells, Resource Recovery study area, Pasco, Washington.

the analytes with detectable quantities, only sodium demonstrates uniformity between wells. A concentration gradient based on dilution is not apparent because relative amounts of individual elements in each monitoring well are independent. The limited amount of conductivity and pH data provide no explanation of data variability.

Data collected from JUB monitoring wells over several years is presented in Table 6.9 along with the primary and secondary drinking water standards. In every case, concentrations increased between 1982 and 1985.

Rigorous Quality Assurance reviews of both field and analytical quality controls indicate that these anomalous data are not the result of field or lab errors. Variations in well construction probably do not account for the results.

Suspension of fine clay particles appears unlikely because the elemental distribution in groundwater does not match the expected elemental distribution in either Montmorillonitic or Illitic clays (30).

Possible explanations for ground water anomalies include:

1. Unknown point sources of contaminants
2. Micro-acidic environments promoting dissolution
3. Highly channelized flow regime
4. High levels of non-electrolytic soluble species and/or dissolved solids
5. Unsuspected field or lab quality control problems

TABLE 6.9  
RESOURCE RECOVERY, PASCO, WA.  
RESULTS OF INORGANIC ANALYSES OF GROUND WATER VS. TIME a  
(ug/l)

ELEMENTS	PRIMARY AND SECONDARY DRINKING WATER STANDARDS	JUB 1		JUB 2		JUB 3		JUB 4		JUB CONTROL			
		FEB. 1982	JULY/AUG. 1985	FEB. 1982	JULY/AUG. 1985	FEB. 1982	SEPT. 1984	JULY/AUG. 1985	DEC. 1982	JULY/AUG. 1985	FEB. 1982	SEPT. 1984	JULY/AUG. 1985
ALUMINIUM		*	37210	*	46670	*	41500	17030	*	40180	*	102000	129800
ANTIMONY		*	12U	*	12U	*	20U	12U	*	12U	*	20U	12U
ARSENIC	50	10.0U	10.0U	10U	12.0	10.0U	28J	10.0U	10U	40.0	10U	39J	37.2
BARIUM	1000	100U	896	100U	834	100U	785	350	500U	838	100U	[1631]	[1656]
BERYLLIUM		*	3.1	*	3.6	*	5U	1.7	*	3.0	*	7	10.4
CADMIUM	10	1U	2.8	1U	1.9U	1U	1U	1.9U	1U	1.9U	1U	1.9	1.9U
CALCIUM		*	101100	*	116100	*	*	77740	*	100700	*	*	332200
CHROMIUM	50	5	[60]	5U	[71]	5U	42	31	5U	[51]	5U	[106]	[176]
COBALT		*	67	*	87	*	50U	23	*	4	*	*	184
COPPER	1000	10U	103	10U	109	10U	120J	33	10U	77	10U	280J	254
IRON	300	[1600]	[89890]	[610]	[105400]	[350]	[97450]	[41430]	[700]	[95460]	[490]	[199900]	[268300]
LEAD	50	50	[70]	5U	[56]	50	[70]	13.2	5U	15.3	5U	[160]	[180]
MAGNESIUM		*	38990	*	41490	*	*	29140	*	39840	*	*	99060
MANGANESE	50	[110]	[2695]	[70]	[2232]	10U	[1694]	[733]	20	[1394]	40	[4380]	[5281]
MERCURY	2	0.50	0.6	0.5U	0.2	0.5U	0.2U	0.6	0.5U	0.2	0.5U	0.2U	1.0
NICKEL		*	61	*	50	*	63J	16U	*	23	*	162J	138
POTASSIUM		*	12410J	*	13420J	*	*	9598J	*	12290J	*	*	26000J
SELENIUM	10	50	25UJ	5U	25UJ	5U	2	25UJ	5U	250J	5U	2	25UJ
SILVER	50	50	9.8	5U	11.1	5U	10U	8.0	5U	9.3	5U	10U	19.1
SODIUM		*	35960	*	39370	*	*	35140	*	36120	*	*	41800
THALLIUM		*	10UJ	*	10UJ	*	10U	10UJ	*	10UJ	*	10U	10UJ
TIN		*	.18U	*	88	*	20U	18U	*	52	*	20U	18U
VANADIUM		*	164.5	*	195.8	*	200U	79.4	*	150.0	*	302	493.7
ZINC	5000	500	262	500	354	5U	207	132	50U	211	50U	514	673
CYANIDE		*	*	*	*	*	10U	*	*	*	*	10U	*

a - FEB. AND DEC. 1982 OATA - FROM JUB REPORT (12)  
SEPT. 1984 DATA - E & E SITE INSPECTION (1)  
JULY/AUGUST 1985 DATA - THIS STUDY  
\* - NOT ANALYZED  
[ ] VALUE EXCEEDS DRINKING WATER STANDARDS

## 7.0 SUMMARY AND RECOMMENDATIONS

Resource Recovery Corporation received and disposed of several million gallons of liquid industrial wastes and 50,000 drums of material for disposal between 1972 and 1974. Liquids were evaporated to dryness from two lined and one unlined ponds and subsequently covered with layers of soil, polyethylene sheeting, and capped with an additional soil layer. Drums were stacked and buried in two unlined pits capped with a similar surface liner system. Ecology and Environment, Inc. installed nine monitoring wells and submitted both soil and ground water samples to EPA contract labs for standard HSL organic and inorganic analyses and herbicides in order to document any migration or contamination from these burial zones.

### 7.1 Conclusions

The following points summarize E&E's conclusions reached in the investigation of Resource Recovery Corporation disposal site during 1985.

- o Ground water contours confirm the flow of ground water is towards the southwest.
- o Organic contamination in the soil was found almost exclusively in the shallow (10-30 feet) soil sample collected from the former municipal waste disposal and burn area.

The low level organic contaminants identified in the soil are indicative of:

- wood preservatives, e.g., creosote, coal tar, and phenol
- plasticizers, e.g., phthalates
- soil gas from organic decomposition, e.g., methane
- transformer and capacitor fluid, e.g., PCBs
- no herbicide or herbicide waste products were identified



- hydrocarbons of unknown origin, possibly the carrier for wood preservatives or diesel and lubricating oils.
- only the soil gases are expected to exhibit substantial migration.
- o Inorganic soil constituents were uniformly distributed throughout the site with only these minor variations in concentrations:
  - slightly elevated barium, mercury, and sodium levels were associated with the shallow (10-30 feet) soil samples near the former chloroalkali waste pond.
  - zinc was slightly elevated in the shallow (10-30 feet) soil sample taken outside the former metal finishings waste pond.
- o Ground water contamination by organics occurred only beneath or adjacent to the former municipal disposal and burn area:
  - volatile organics may be leaching from several source materials, including plastics, solvents, paints, gasoline, and coal tar
  - only trichloroethylene and tetrachloroethylene concentrations exceeded recommended drinking water levels
  - only 4-methylphenol was detected in the BNA fraction and may be due to coal tar
  - only trace amounts of phthalate were found
  - no PCBs or pesticides were found
  - no herbicides or herbicide waste products were identified
  - tentatively identified compounds are similar to those found in sediment samples
  - the potential effects on irrigation do not appear to be significant based on the expected horizontal contaminant gradients, vertical irrigation well depths, volatilization of contaminants

during spraying, ground surface volatilization, and subsequent ground water dilution effects.

- o Inorganic ground water data displayed unexplainably wide variations in concentration across the site and between adjacent monitoring wells:
  - barium, chromium, iron, lead, and manganese exceeded primary and secondary drinking water standards
  - a significant increase in nearly all inorganic species occurred between 1982 and 1985 at monitoring wells across the entire site
- o No special additional analyses for dioxin were required because potentially dioxin contaminated materials or precursors were not identified.
- o No exposure routes or significant hazards were identified as a result of disposal practices or sample analyses.
- o Migration rates for trichloroethylene and tetrachloroethylene have been estimated to be on the order of 40 to 80 feet per year.
- o In summary, the results indicate that trace amounts of contaminants may have migrated outside of Resource Recovery Corporation's burial Zones A, CD, and E as described above. No evidence of contaminant migration from Zone B (the herbicide waste drum burial zone) was found. Some of the contaminants identified near Zone A may have leached from the area around the zone which had been used as an industrial burial and municipal waste open-burning area prior to development by Resource Recovery Corporation.

## 7.2 Recommendations

- o Areas where erosion or site activities have exposed plastic liner should be recovered with soil to preserve liner integrity.

- o Drill cuttings and water drummed during field operations may be disposed on-site.
- o Resampling and re-analysis of samples from each of the on-site monitoring wells and several of the surrounding irrigation wells will be necessary in order to explain the inorganic ground water data.
- o Continue monitoring ground water with annual or bi-annual sampling and analyses to detect any onset of migration from a burial zone.
- o A recent EPA study at Alkali Lake, Oregon (31), where similar Rhodia herbicide wastes were emptied from drums and buried, found parts per trillion levels of polychlorinated dibenzo-p-dioxins and polychlorinated dibenzofurans in the surface sediment. If herbicide or herbicide waste materials are detected by future monitoring around Zone B, the potential for dioxin contamination exists. However, as dioxins and furans have high partition coefficients (are readily and almost irreversibly adsorbed onto solids), their appearance in ground water is extremely unlikely.

## REFERENCES

1. U.S.G.S. Quadrangle Map, Glade, Washington; 1:24,000, 1979.
2. U.S.G.S. Quadrangle Map, Pasco, Washington; 1:24,000, 1964; photo revised 1973.
3. Preliminary Site Inspection Report of Resource Recovery Corporation, Pasco, WA. Prepared by Ecology and Environment, Inc. (E&E), January 8, 1985.
4. EPA Files on Resource Recovery Corporation (RRC). Monthly Activity Reports Sent by RRC to WDOE.
5. EPA Files on RRC, Memos from Rhodia to various agencies documenting waste composition.
6. Personal communication with Larry Dietrich, January 29, 1985.
7. Resource Recovery Corporation, Industrial Waste Site Disposal Site Evaluation. Prepared by WDOE, December 1973.
8. Composition of Wastes at Alkali Lake, Memo - Gitschlag to Beverly Hall, August 17, 1973. EPA File on Rhone-Poulenc Chemical Plant, Portland, OR.
9. EPA Files on RRC, Resource Recovery, Inc., Pasco Disposal Facility Requirements for Facility Closedown and Site Monitoring.
10. EPA Files on RRC, Map of Survey for Resource Recovery, Inc., A.D. Stanley, Wash. Reg. No. 7890, Franklin County Fee No. 402472.
11. U.S. Weather Bureau. Local Climatological Summary: Tri-City Area, Kennewick-Pasco-Richland, WA. National Climatic Data Center, Asheville, NC.
12. EPA Files on RRC, Well Logs.
13. Basalt Waste Isolation Project, Annual Report - Fiscal Year 1980, RHO-BW1-80-100, document prepared for U.S. Department of Energy under contract DE-Ac06-77RL01030 by Rockwell International.
14. Summary Report - Groundwater Quality in the Vicinity of the Pasco Landfill, J-U-B Engineers, Kennewick, WA, July 1983.
15. Evaluation of the Pasco Sanitary Landfill Waste Disposal Practices, J-U-B Engineers, Kennewick, WA, June 1981.
16. Proposed Sampling Plan for Resource Recovery Corporation, Pasco, Washington. Prepared by Ecology and Environment, Inc., 1985.

17. Lorenz, L.F. and L.R. Gjorik, "Analyzing Creosote by Gas Chromatography: Relationship to Creosote Specifications," AWWA Proceedings, pp. 32-39, 1972.
18. Final Report for St. John's Landfill, Portland, OR. Prepared by E&E, 1986.
19. Verschueren, K. Handbook of Environmental Data on Organic Compounds, Van Nostrand Reinhold Co., NY, 1983.
20. Connell, D.W. and G.J. Miller, Chemistry and Ecotoxicology of Pollution, John Wiley & Sons, NY, 1984.
21. Grimmer, G., Environmental Carcinogens: Polycyclic Aromatic Hydrocarbons, CRC Press, Boca Raton, LA, 1983.
22. Hutzinger, O., et al., The Chemistry of PCBs, Krieger Publishing Co., Malabar, 1983.
23. Hague, R., D.W. Schmedding, & V.H. Freed. Aqueous Solubility Adsorption, and Vapor Behavior of Polychlorinated Biphenyl (Aroclor 1254): Environmental Sciences and Technology, V. 8, pp. 139-142, 1974.
24. Tucker, E.S., W.J. Litschgi, & W.M. Mees. Migration of Polychlorinated Biphenyls in Soil Induced by Percolating Water: Bulletin of Environmental Contamination and Toxicology, V. 13, pp. 86-93, 1975.
25. Leis, W.M., et al., Migration of PCBs by Groundwater Transport - A Case Study of Twelve Landfills and Dredge Disposal Sites in the Upper Hudson Valley, New York: Conference of Applied Research and Practice on Municipal and Industrial Waste, Box 5571, Madison, WI 53705, pp. 539-548, September 10-13, 1978.
26. Hague, R. and D.W. Schmedding, Studies on the Adsorption of Selected Polychlorinated Biphenyl Isomers on Several Surfaces: Journal of Environmental Sciences and Health, B11, pp. 129-137, 1976.
27. Guidance on Feasibility Studies Under CERCLA, EPA/540/G-85/003, June 1985.
28. Callahan, M., et al., Water-Related Environmental Fate of 129 Priority Pollutants, Vol. II, EPA-440/4-79-0296, 1979.
29. Wood, P.R., R.F. Lang, and J.L. Payan, Anaerobic Transformation, Transport and Removal of Volatile Chlorinated Organics in Groundwater, Drinking Water Research Center, Florida International University, Miami, Florida, 1981.
30. Riley, J.P. and G. Skirrow, Chemical Oceanography 2, Academic Press, NY, 1965.

31. Final Report for Alkali Lake Chemical Disposal Site, Alkali Lake, OR,  
Prepared by E&E, 1986.

APPENDIX A

AERIAL PHOTOGRAPHY






TITLE: Resource Recovery  
Pasco, Washington  
Aerial Photograph

JOB #: R10-8410-14

ecology and environment, inc.  
SEATTLE, WA

Date August 3, 1970 Scale: 1"=250'





**TITLE:**

Resource Recovery  
Pasco, Washington  
Aerial Photograph

**JOB #:** R10-8410-14

**ecology and environment, Inc.**  
SEATTLE, WA

**Date** May 11, 1973

**Scale:** 1"=335'





TITLE: Resource Recovery  
Pasco, Washington  
Aerial Photograph

JOB #: R10-8410-14

ecology and environment, inc.  
SEATTLE, WA

Date April 12, 1978 Scale: 1"=185'

NOTE: SITE OUTLINE APPROXIMATE



APPENDIX B  
DRILLING AND SAMPLE LOGS

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: R. Holtz  
 Date Completed: 8/02/85

Job No: TDD R10-841G-14 Boring No: EE-1  
 Location: 75' 11" SE of JUB control well  
 Surface Elev: 418.9 ft. Datum: AMSL  
 Casing Elev: 421.1 ft. Datum: AMSL  
 Total Depth: 88 ft. Datum: Below TOC  
 Groundwater: 363.6 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT		-- 0--	SM	SAND WITH SILT - fine- to fine-grained, well sorted, subrounded, light gray and frosted, trace surface loam, very dry. Eolian origin		
		4--	SW	SAND - Sand, 100% fine- to medium-grained, well sorted, subangular to subrounded, light to dark brown and clear to frosted. Quartz mica, feldspar, hornblende or basalt. Semi-dry.		
	2" SS CASING	-- 10--	SW	SAND - Sand, 100%, fine- to medium-grained, well to moderately well sorted, subangular to subrounded, light olive brown and clear to frosted. Semi-dry. Hard cemented sand layer 19-20'.	85310396 JA544 MJA210	Soil Composite
		20--	SW	SAND - Sand, 100%, fine- to medium-grained, well to moderately well sorted, pale to dark yellowish brown. Feldspar, hornblende mica. Semi-dry.		
	BEN- TONITE SLURRY	35--	SW	SAND - Sand, 100%, fine- top very fine-grained clear to light olive gray. Trace silt, trace pebbles (3-10mm) scattered throughout.	85310397 JA545 MJA211	Soil Composite
		40--	SW	SAND - Sand, 100%, medium- to fine-grained, moderately well to well sorted, subrounded to subangular, frosted and dark yellowish brown. Trace pebbles. Quartz mica, hornblende or basalt, feldspar.		
		-- 46				
FINE SAND CAP		-- 49				
GRAVEL		-- 50--				

Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-1

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
GRAVEL PACK	2" SS CASING	50--	SP	SAND - Sand, 100%, medium- to coarse-grained, poorly sorted, angular, frosted to moderate olive brown, moist.	85320877 JA554 MJA221	Aqueous Grab
		55--	SP	GRAVELLY SAND - Sand, 70%, medium- to very coarse-grained, poorly sorted, subrounded, dark gray to black and frosted, some mica, moist.		
		60--	SW	SAND - Sand, 100%, medium- to coarse-grained, dark olive brown to dark gray.		
	2" SS .010 SLOT SCREEN	-- 66--	GP	SANDY GRAVEL - Gravel, 60%, coarse-grained, poorly sorted, subrounded, gray to black. Sand, 40%, medium- to very coarse-grained, poorly sorted, subrounded, dark gray to black, frosted. Feldspar, mica, quartz. Large cobbles in lower part.		
		-- 86				
	2" SS SUMP	-- 88--		TOTAL DEPTH - 88 ft.		

Job No:	TDD R10-8410-14	Boring No:	EE-2
Location:	30' SE of Area A		
Surface Elev:	416.8 ft.	Datum:	AMSL
Casing Elev:	419.2 ft.	Datum:	AMSL
Total Depth:	88 ft.	Datum:	Below TOC
Groundwater:	348.8 ft.		AMSL

B-3

Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-2

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
BEN- TONITE SLURRY	2" SS CASING	-- 50--				
		-- 60--	SP	GRAVELLY SAND. Gravel - poorly sorted, angular, mostly dark gray to black, some frosted. Water at 65'.		
FINE SAND			SP			
		-- 66--				
COARSE AND NATURAL SAND	2 " SS (0.010) SLOT SCREEN					
		-- 86--				
	2" SS SUMP	-- 88--				
				BOTTOM OF BORING - 88 ft.	85320885 JA572 MJA249	Aqueous grab

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: R. Hpltz  
 Date Completed: 8/04/85

Job No: TDD R10-8410-14 Boring No: EE-3  
 Location: 30' West of Area A  
 Surface Elev: 415.1 ft. Datum: AMSL  
 Casing Elev: 417.2 ft. Datum: AMSL  
 Total Depth: 87 ft. Datum: Below TOC  
 Groundwater: 353.1 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT	2" SS CASING	-- 0--	SM	SILTY SAND. Sand, 80%, fine-grained, well sorted, subrounded to subangular, light gray and opaque, mica granules. Silt, 20%, light gray, dry.	85320875 JA560 MJA228	Soil Composite
		2--	SM	SAND WITH SILT. Sand, 90%, fine-grained, well sorted, subangular to subrounded, frosted and light to dark brown. Silt, 10%, semi-dry, large amounts of garbage (wood, cans, plastic, etc.) from 3'-17'.		
-- 10--		SW	SAND - Sand, 100%, fine- to medium-grained, moderately well sorted, subangular to angular, dusky yellowish brown and frosted, mica flakes, semi-dry.			
-- 15		SW	SAND - Sand, 100%, medium-grained, moderately well sorted, subangular to subrounded, dark olive brown. Trace fine pebbles (4-10mm) at 25' and 38'.			
17--						
BEN- TONITE PELLET						
BEN- TONITE SLURRY					85320876 JA561 MJA229	Soil Composite
		40--	SP	GRAVELLY SAND - poorly sorted, angular to sub-angular, dark gray, and frosted, a salt and pepper appearance.		
		-- 50--				



Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-3


WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
BEN- TONITE SLURRY	2" SS CASING	-- 50--	SP	GRAVELLY SAND - Coarse, poorly sorted, sub- rounded to subangular, dark gray to black, and frosted. Gravel approximately 3mm size, small pebbles (10-15mm) at 57', flowing sands at 64'.		
FINE SAND		-- 59				
		-- 64				
COARSE SAND AND NATURAL GRAVEL	2" SS (0.010) SLOT SCREEN					
	2" SS SUMP	-- 85		TOTAL DEPTH - 87 ft.	85320881 JA573 MJA248	Aqueous grab
		-- 87--				

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: R. Holtz  
 Date Completed: 7/17/85

Job No: T00 R10-8410-14 Boring No: EE-4  
 Location: 30' SE of Area B  
 Surface Elev: 397.6 ft. Datum: AMSL  
 Casing Elev: 396.4 ft. Datum: AMSL  
 Total Depth: 72 ft. Datum: Below TOC  
 Groundwater: 353.4 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT		-- 0--	SM	SILTY SAND. Sand, 80%, very fine-grained, well sorted, subangular to subrounded, light gray, frosted, and clear. Very dry.	85290825 JA562 MJA231	Soil Composite
		-- 2--	SW	SAND - Sand, 100%, fine- to medium-grained, moderately well sorted, subangular, frosted and dark yellowish brown. Feldspar, mica, horblende, or basalt. Cemented sand 13'-14', increasingly coarser below 14'.		
BEN- TONITE SLURRY	2" SS CASING	-- 18--	SP	SAND - Sand, 100%, coarse, poorly sorted, subangular, medium olive gray, frosted, trace gravel and 5-8mm pebbles.	85290826 JA563 MJA230	Soil Composite
		20--	SP	SAND WITH GRAVEL. Sand, 90%, medium- to coarse-grained, moderately poorly to poorly sorted, angular to subangular, dark yellowish brown and frosted. Gravel, 10%, coarse-grained, dark gray or black. Gravel found between 26'-30'.		
		30--	GP	SANDY GRAVEL - moderately poorly to poorly sorted, angular to subrounded, semi-dry, light to moderate brown, and frosted. Gravel found between 26'-30'.		
		35--	SP	GRAVELLY SAND. Sand - poorly sorted, angular to subangular, olive gray to dark gray, and frosted. Gravel - coarse, subangular, olive gray to dark gray.		
		-- 43				
FINE SAND		45--				
		-- 46	GP	GRAVEL - Gravel, 100%, coarse to very coarse, poorly sorted, flowing, dark gray to black and frosted. Trace sand. Trace pebbles and small cobbles at 60'.		
COARSE SAND & NATURAL GRAVEL	2" SS 0.010 SLOT SCREEN	-- 50--				

Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-4

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
COARSE SAND & NATURAL GRAVEL		-- 50--	 GP	GRAVEL - cont'd		
	2" SS 0.010 SLOT SCREEN					
	2" SS SUMP	-- 70--				
		-- 72--		TOTAL DEPTH - 72 ft.	85281029 JA569 MJA234	Aqueous grab

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: R. Holtz  
 Date Completed: 7/20/85

Job No: TDD R10-8410-14 Boring No: EE-5  
 Location: 30' West of Area B  
 Surface Elev: 405.5 ft. Datum: AMSL  
 Casing Elev: 407.9 ft. Datum: AMSL  
 Total Depth: 72 ft. Datum: Below TOC  
 Groundwater: 350.9 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT		-- 0--	SM	SILTY SAND. Sand - 80%, very fine-grained, well sorted, light to medium gray, clear, and frosted. Silt - 20%, light to medium gray, some surface loam.	85290827 JA565 MJA232	Soil Composite
		2--	SW	SAND - Sand, 100%, very fine- to medium-grained, well to moderately well sorted, subrounded to subangular, frosted and light to dark brown.		
BEN- TONITE		10--	SW	SAND - Sand, 100%, fine- to coarse-grained, well to moderately well sorted, subrounded to angular, frosty and clear, also dark olive brown, semi-dry.		
		-- 12.5				
		-- 14				
	2" SS CASING	20--	SP	SAND - Sand, 100%, fine- to coarse-grained, poorly to moderately poorly sorted, subangular, dark olive gray, becomes coarser and olive gray below 35'. Granules and small pebbles (6-16mm) at 38', semi-dry.	85290828 JA566 MJA233	Soil Composite
BEN- TONITE SLURRY						
		-- 40--				
FINE SAND		-- 42--	GP	GRAVEL - Gravel, 100%, coarse, poorly sorted, angular to subangular, dark gray to black, and frosted.		
COARSE SAND AND NATURAL PACK		-- 50--				

Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-5

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
COARSE SAND AND GRAVEL PACK		-- 50--	GP	SAND AND GRAVEL - coarse to very coarse, angular to subangular, dark gray to black, and frosted.		
	2" SS					
	0.010	57--	GP	GRAVEL WITH SAND. Gravel - 90%, very coarse, poorly sorted, angular. Sand, 10%, coarse-grained, subrounded. Trace pebbles and cobbles. Saturated.		
	SLOT					
	SCREEN					
		-- 69				
	2" SS					
	SUMP	-- 72			85281030 JA570 MJA238 (MJA235)	Aqueous grab
		-- 75		TOTAL DEPTH - 75 ft.		

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: Randy Holtz/Jim Braddock  
 Date Completed: 7/31/85

Job No: TDD R10-8410-14 Boring No: EE-6  
 Location: 30' Southwest of Area C-D  
 Surface Elev: 424.9 ft. Datum: AMSL  
 Casing Elev: 427.0 ft. Datum: AMSL  
 Total Depth: 102 ft. Datum: Below TOC  
 Groundwater: 352.4 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT		-- 0--	SM	SILTY SAND - Well sorted, light to medium gray, frosted, and transparent. Mostly quartz, dry. SAND with SILT. Sand, fine- to very fine-grained, well sorted, light to medium brown. Most silt found 2'-5'.		
		2--	SW			
		10--	SW	SAND - Sand, 100%, fine- to coarse-grained, well to moderately well sorted, subrounded to subangular, frosted, to dark yellowish to olive brown; occasional layers, 4-6 mm pebbles in lower part.	85290827 JA565 MJA232	Soil Composite
BEN- TONITE		-- 12				
		-- 14				
	2" SS CASING					
BEN- TONITE						
		40--	SP	SAND - Sand, 100%, coarse- to medium-grained, moderately poorly to poorly sorted, subangular to angular, frosted to dark olive gray; moist.	85310395 JA553 MJA219	Soil Composite
		-- 50--				

Project: Resource RecoveryJob No: R10-8410-14Boring No: EE6

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE		
BEN- TONITE SLURRY	2"SS CASING	-- 50--	GC	SANDY GRAVEL with CLAY - Gravel, coarse to very coarse, subangular, dark gray to black. Sand, coarse, poorly sorted, subangular to subrounded, frosted and dark olive gray. Clay, silty clay in occasional seams, small granules and pebbles at 58'. GRAVELLY SAND with PEBBLES - Sand, coarse-grained, poorly sorted, subangular to angular dark gray to black, and frosted. Pebbles - 10-20mm.				
		57--	SP					
		-- 70		GRAVEL with SAND - Sand, very coarse-grained, very poorly sorted, angular, dark gray to black, and frosted, salt and pepper appearance.				
		-- 72						
75--	GP							
-- 80								
FINE SAND								
COARSE SAND AND GRAVEL TO 102'	2"SS 0.010 SLOT SCREEN							
	2" SS SUMP	-- 100			85320878 JA575 MJA227	Aqueous grab		
	-- 102--		TOTAL DEPTH - 102 ft.					

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: Randy Holtz/Jim Braddock  
 Date Completed: 7/29/85

Job No: TDD R10-8410-14 Boring No: EE-7  
 Location: 30' West of Area C  
 Surface Elev: 423.8 ft. Datum: AMSL  
 Casing Elev: 425.6 ft. Datum: AMSL  
 Total Depth: 100 ft. Datum: Below TOC  
 Groundwater: 351.9 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT		-- 0--	SM	SILTY SAND - Sand, well sorted, subrounded, light gray, frosted and clear; surficial loam and debris present.		
		2--	SM	SILTY SAND - Sand, fine- to very fine-grained, well to moderately well sorted, subangular, light to medium brown, and frosted. Fill material (old car parts, glass, wood, etc.) between 6'-9'.		
BEN- TONITE	2" SS CASING	-- 10--	SW	SAND - Sand, 100%, fine- to medium-grained, moderately well sorted, subangular to subrounded, mostly frosted quartz, some dark to moderate olive brown, 1-2mm granules at 14', micaceous flakes at 16'.	85310392 JA557 MJA224	Soil Composite
		-- 1--				
BEN- TONITE SLURRY		20--	SW	SAND - Sand, 100%, medium- to fine-grained, moderately well sorted, subangular to subrounded. Mostly frosted, some dark to moderate olive brown.	85310393 JA558 MJA225	Soil Composite
		40--	GP	SANDY GRAVEL - Sand, medium- to coarse-grained, poorly sorted, subangular to subrounded, cloudy, and grayish olive brown.		
		-- 50--				



Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-7

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
BEN- TONITE SLURRY	2" SS CASING	-- 50--	GP	SANDY GRAVEL (continued)		
FINE SAND		-- 70--	SP	GRAVELLY SAND - Sand, poorly sorted, subangu- lar to subrounded, dark gray to black, and frosted quartz. Salt and pepper appearance. Pebbles and cobbles at 66', flowing sands at 76'.		
		-- 72--				
		-- 78				
COARSE SAND AND NATURAL GRAVEL						
	2" SS					
	0.010					
	SLOT SCREEN					
		-- 98				
	2" SS SUMP	-- 100--		TOTAL DEPTH - 100 ft.	85320879 JA576 MJA237	Aqueous grab

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: Randy Holtz/Jim Braddock  
 Date Completed: 7/23/85

Job No: TDD R10-8410-14 Boring No: EE-8  
 Location: 30' Southeast of Area E  
 Surface Elev: 426.5 ft. Datum: AMSL  
 Casing Elev: 428.4 ft. Datum: AMSL  
 Total Depth: 100 ft. Datum: Below TOC  
 Groundwater: 351.8 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
CEMENT		-- 0--	SM	SILTY SAND - Sand, very fine-grained, well sorted, light to medium gray, and frosted. Dry, mica flakes, some surficial loam mixed in. SAND with SILT. Sand - fine-grained, well to moderately well sorted, subrounded to subrounded to subangular, frosted and moderate olive brown. Small pebbles at 7'.	85300850 JA548 MJA214	Soil Composite
		2--	SW			
		10--	SW	SAND - Sand, 100%, fine- to medium-grained, well to moderately well sorted, subangular to subrounded, frosted to moderate olive brown. Becomes more coarse below 18'.		
BEN- TONITE	2" SS CASING	-- 13			85300851 JA549 MJA215	Soil Composite
		-- 15				
BEN- TONITE SLURRY		20--	SW	SAND - Sand, 100%, fine- to medium-grained, well to moderately well sorted, angular to subangular, frosted to olive brown. Occasional 1'-2' lenses of cemented sand; small pebble layers at 35', 47' and 50'. Becomes coarser at 49'.		
		-- 50--				

Project: Resource RecoveryJob No: R10-8410-14Boring No: EE-8

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE
BEN- TONITE SLURRY		-- 50--	GP	SANDY GRAVEL - Gravel, poorly sorted, subangular to subrounded, dark grayish brown to black frosted. Pebbles (10-20mm) at 54'.		
FINE SAND		-- 54				
		-- 57				
COARSE SAND	2" SS CASING	70--	SP	GRAVELLY SAND - Sand, poorly sorted, subangular to angular gravel and subrounded sand, dusky yellowish brown to grayish black.		
		-- 78				
	2" SS 0.010 SLOT SCREEN					
		-- 98				
	2" SS SUMP	-- 100--		TOTAL DEPTH - 100 ft.	853 10391 JA574 MJA223	Aqueous grab

Project: Resource Recovery  
 Boring Contr.: Boyles Bros.  
 Boring Method: Hollow Stem Auger  
 Logged by: Randy Holtz/Jim Braddock  
 Date Completed: 7/25/85

Job No: TDD R10-8410-14 Boring No: EE-9  
 Location: 30' Southeast of Area E  
 Surface Elev: 426.2 ft. Datum: AMSL  
 Casing Elev: 424.8 ft. Datum: AMSL  
 Total Depth: 97 ft. Datum: Below TOC  
 Groundwater: 352.7 ft. AMSL

WELL DETAILS		DEPTH (FEET)	SYMBOL	LITHOLOGICAL DESCRIPTION	SAMPLE NO.	SAMPLE TYPE	
CEMENT	2" SS CASING	-- 0--	SM	SILTY SAND - Sand, fine- to very fine-grained, well sorted, subrounded to subangular, light to medium gray, clear and frosted.	85300852 JA550 MJA216	Soil Composite	
		2--	SW	SAND - Sand, 100%, fine- to medium-grained, well to moderately well sorted, subangular to angular, light to dark brown. Large pebbles and fill material 8'-10'.			
-- 10--		SW	SAND - Sand, 100%, fine- to medium-grained, moderately well to well sorted, subangular to subrounded, mostly frosted, also dark to moderate olive brown. Large mica flakes; pebbles (4-10mm) at 18'. Occasional cemented sand.				
-- 12							
BEN- TONITE PELLET							
BEN- TONITE SLURRY							
			30--	SP	SAND - Sand, 100%, medium-grained, poorly sorted, frosted to moderate olive brown. Extensive cemented sand at 35' and 44'.	85310853 JA551 MJA217	Soil Composite
			-- 50--				

Boring No: EE-9

B-18

ecology and environment, inc.

DRILLING  
WEEKLY PROGRESS REPORT

Work Site: Resource Recovery Corp. E & E Job No.: R-20-8410-14 <sup>YDU#</sup> Ending: 8/6/85  
Drillers: W. Franklin Driller's Helper: K. Jones/A. Aronson Geologists: R. Holtz  
Number of Drill Holes Drilled and Completed: 11 days = 951 feet Average Feet/Days: 86.4/day

Drill Hole Information:

1. Hole Designation: EE-1-A Total Depth: 23' Static Water Level: N/A  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem  
augers.

7/16/85

Was Hole Cased? N Type and Amount of Casing Used: N/A Screened Interval: N/A  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size

Amount of Sand, Gravel or Cement Used: N/A

Was Hole Developed? No

Problems Encountered: Large cobbles and boulders encountered causing augers  
to bind. Hole was abandoned.

2. Hole Designation: EE-1-B Total Depth: 43' Static Water Level: N/A  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem  
augers.

7/16/85

Was Hole Cased? N Type and Amount of Casing Used: N/A Screened Interval: N/A  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size.

Amount of Sand, Gravel or Cement Used: N/A

Was Hole Developed? No

Problems Encountered: Large Cobles and boulders encountered, hole abandoned,  
move to Area B.

3. Hole Designation: EE-4 Total Depth: 72' Static Water Level: 43.5'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

Was Hole Cased? Y Type and Amount of Casing Used: S.S. 52' Screened Interval: 48-70'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size

7/17/85

Amount of Sand, Gravel or Cement Used: 30' coarse sand, fine 25' bentonite, 17 cement

Was Hole Developed? Y, 30 gallons purged out on 7/21/85

Problems Encountered: Flowing sands causing problems with installation of casing.

Randall S. O'Leary 8/30/85  
Signature/Date

\*11 days actual drilling - other days spend decontamination

ecology and environment, inc.

DRILLING  
WEEKLY PROGRESS REPORT

Work Sites: Resource Recovery Corp. E & E Job No.: R-20-8410-14 <sup>100%</sup> ~~Week~~ Endings: 8/6/85  
Drillers: W. Franklin Driller's Helpers: K. Jones/A. Aronson Geologists: R. Holtz  
Number of Drill Holes Drilled and Completed: 11 days = 951' Average feet/Day: 86.4'/day

Drill Hole Informations:

1. Hole Designations: EE-5-A Total Depths: 78' Static Water Levels: 52.25'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

7/19/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 58' Screened Interval: 56.25'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size  
Amount of Sand, Gravel or Cement Used: 30' coarse & fine sand. 2' bentonite pellets  
Was Hole Developed? No  
Problems Encountered: Sand had flowed up inside the augers and when pellets were introduced they seized the casing to the augers. Hole abandoned.

2. Hole Designation: EE-5-B Total Depths: 72' Static Water Levels: 51'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

7/20/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 52' Screened Interval: 50-72'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size.  
Amount of Sand, Gravel or Cement Used: 32' coarse, fine sand 28' bentonite 12' grout.  
Was Hole Developed? Yes on 7/21 - 30 gallons purged out.  
Problems Encountered: Flowing sands causing some minor problems with casing installation

3. Hole Designation: EE-8 Total Depths: 103' Static Water Levels: 77.4'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

7/23/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 80' Screened Interval: 78-100'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size  
Amount of Sand, Gravel or Cement Used: 50' sand (coarse, fine) 38' bentonite, 12' grout  
Was Hole Developed? Yes. 24.8 gallons purged on 7/24/85.  
Problems Encountered: Casing rose about 3' at beginning of auger withdrawal, but after sand pack was in, no more rose up.

Randall S. May 8/30/85  
Signature/Date

ecology and environment, inc.

DRILLING  
WEEKLY PROGRESS REPORT

Work Site: Resource Recovery Corp. E & E Job No.: R-20-8410-14 <sup>100%</sup> Week Ending: 8/6/85  
Driller: W. Franklin Driller's Helper: K. Jones/A. Aronson Geologist: R. Holtz  
Number of Drill Holes Drilled and Completed: 11 days = 951 feet Average Feet/Day: 86.4/day

Drill Hole Information:

1. Hole Designation: EE-9 Total Depth: 97' Static Water Level: 75'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

7/25/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 75' Screened Interval: 75-97'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size  
Amount of Sand, Gravel or Cement Used: 33' coarse & fine sand, 54' bentonite, 10' grout  
Was Hole Developed? Yes. 24.5 gallons purged on 7/30/85  
Problems Encountered: Flowing sand causing some problems with casing installation.

2. Hole Designation: EE-7 Total Depth: 100' Static Water Level: 73.2'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

7/29/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 80' Screened Interval: 78-100'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size.  
Amount of Sand, Gravel or Cement Used: 30' sand coarse & fine, 60' bentonite, 10' grout  
Was Hole Developed? Yes. 30 gallons purged 7/30/85  
Problems Encountered: Some debris at beginning of hole but no major difficulties encountered

3. Hole Designation: EE-6 Total Depth: 100' Static Water Level: 70.3  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

7/31/85 Was Hole Cased?        Type and Amount of Casing Used: S.S. 80' Screened Interval: 77.5 to 99.5'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size  
Amount of Sand, Gravel or Cement Used: 30' coarse and fine sand, 58' bentonite, 12' grout  
Was Hole Developed? Yes. 24.5 gallons purged on 8/2/85  
Problems Encountered: Flowing sands caused casing to be set at 99.5 instead of 102'.

Daniel J. [Signature] 8/30/85  
Signature/Date



ecology and environment, inc.

DRILLING  
WEEKLY PROGRESS REPORT

Work Site: Resource Recovery Corp. E & E Job No.: R-20-8410-14 <sup>100#</sup> ~~Week~~ Endings: 8/6/85  
Driller: W. Franklin Driller's Helper: K. Jones/A. Aronson Geologist: R. Holtz  
Number of Drill Holes Drilled and Completed: 11 days = 951 feet Average Feet/Day: 86.4/day

Drill Hole Information:

1. Hole Designations: EE-1 Total Depth: 88' Static Water Level: 59.2'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

8/2/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 69' Screened Interval: 66-88'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size  
Amount of Sand, Gravel or Cement Used: 43' sand (coarse & fine), 35' bentonite, 10' grout  
Was Hole Developed? Yes. 28 gallons purged on 8/3/85  
Problems Encountered: No problems at all

2. Hole Designations: EE-3 Total Depth: 87' Static Water Level: 62'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

8/4/85 Was Hole Cased? Y Type and Amount of Casing Used: S.S. 67' Screened Interval: 65-87'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size.  
Amount of Sand, Gravel or Cement Used: 27' coarse & fine sand. 48' bentonite, 12' grout  
Was Hole Developed? Yes. 28 gallons purged out on 8/6/85  
Problems Encountered: High Hou readings caused us to wear PAPRs throughout the entire hole.

3. Hole Designations: EE-2 Total Depth: 86' Static Water Level: 68.5'  
How Hole was Drilled and Equipment Used: Mobile B-80 rig with 4" hollow stem augers.

8/6/85 Was Hole Cased? Y Type and Amount of Casing Used: 66' Screened Interval: 64-86'  
Type and Size of Well Screens: Johnson Stainless Steel .01 slot size  
Amount of Sand, Gravel or Cement Used: 26' sand (coarse & fine) 50' bentonite, 10' grout  
Was Hole Developed? Yes. 28.2 gallons purged on 8/6/85  
Problems Encountered: No problems at all.

Randall S. May 8/30/85  
Signature/Date

APPENDIX C  
SAMPLE DOCUMENTATION SUMMARY

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4679

TOO NO. : R10-8410-i4  
PROJECT CODE: ICE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 1 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
W1	85281002	7/10/85	Aqueous Grab	0.2 ppb	463973090	7/10/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
W1	JA536	7/10/85	Aqueous Grab	Varies	463973086	7/10/85 1600	2 40-ml vials 4 1-liter amber	Rock Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
W1	MJA203	7/10/85	Aqueous Grab	Varies	463973016	7/10/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
W2	85281003	7/10/85	Same	0.2 ppb	463973090	7/10/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
W2	JA538	7/10/85	Same	Varies	463973086	7/10/85 1600	2 40-ml vials 4 1-liter amber	Rocky Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
W2	MJA205	7/10/85	Same	Varies	463973042	7/10/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
W3	85281001	7/09/85	Same	0.2 ppb	463973101	7/09/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
W3	JA533	7/09/85	Same	Varies	463973123	7/09/85 1600	2 40-ml vials 4 1-liter amber	Rocky Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
W3	MJA202	7/09/85	Same	Varies	463973112	7/09/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
W4	85281004	7/11/85	Aqueous Grab	0.2 ppb	463973031	7/11/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
W4	JA539	7/11/85	Aqueous Grab	Varies	463973042	7/11/85 1600	2 40-ml vials 4 1-liter amber	Rocky Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
W4	MJA206	7/11/85	Aqueous Grab	Varies	463973053	7/11/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4679

TOD NO. : R1G-B410-14  
PROJECT CODE: ICE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 2 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
W5	85281005	7/11/85 1155	Aqueous Grab	0.2 ppb	463973031	7/11/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
W5	JA540	7/11/85 1155	Same	Varies	463973042	7/11/85 1600	2 40-ml vials 4 1-liter amber	Rocky Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
W5	MJA207	7/11/85 1155	Same	Varies	463973053	7/11/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
DWW	85281006	7/11/85 1116	Same	0.2 ppb	463973031	7/11/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
DWW	JA541	7/11/85 1166	Same	Varies	463973042	7/11/85 1600	2 40-ml vials 4 1-liter amber	Rocky Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
DWW	MJA208	7/11/85 1116	Same	Varies	463973053	7/11/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
BRS-01	85281000	7/09/85 0800	Same	0.2 ppb	463973101	7/09/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
BRS-01	JA534	7/09/85 0800	Same	Varies	463973123	7/09/85 1600	2 40-ml vials 4 1-liter amber	Rocky Mountain/ Organic	Vial Lot #24292122 Amber Lot #85172222
BRS-01	MJA201	7/09/85 0800	Same	Varies	463973112	7/09/85 1600	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
TP-01	JA534	7/09/85 0845	Aqueous	Varies	46373123	7/09/85 1600	2 40-ml vials	Rocky Mountain/ VOA	Lot #24292122
TP-02	JA537	7/10/85 1425	Aqueous	Varies	463973086	7/10/85 1600	2 40-ml vials	Rocky Mountain/ VOA	Lot #24292122
TP-03	JA542	7/11/85 1430	Aqueous	Varies	463973042	7/11/85 1600	2 40-ml vials	Rocky Mountain/ VOA	Lot #24292122

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TDD NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 3 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
TP-04	JA578	7/22/85 1350	Aqueous	Varies	129006684	7/22/85 1600	2 40-ml vials	Rocky Mountain/ VOA	Lot #24292122
TP-05	JA568	8/01/85 1400	Aqueous	Varies	129006754	8/01/85 1600	2 40-ml vials	A.T.I./VOA	Lot #24292122
TP-06	JA338	8/05/85 1400	Aqueous	Varies	129006625	8/05/85 1530	2 40-ml vials	Rocky Mountain/ VOA	Lot #24292122
TP-07	JA302	8/07/85 0900	Aqueous	Varies	155009260	8/07/85 1500	2 40-ml vials	A.T.I./VOA	Lot #24292122
Auger Rinsate	85320884	8/07/85 1230	Aqueous	0.2 ppb	463973974	8/07/85 1500	2 1-liter amber	EPA Lab/Pesticides	Lot #85175162
Auger Rinsate	JA303	8/07/85 1230	Aqueous	Varies	155009260	8/07/85 1500	4 1-liter amber 2 40-ml vials	A.T.I./Organic	Vial Lot #24292122 Amber Lot #85175162
Auger Rinsate	MJA236	8/07/85 1230	Aqueous	Varies	463973020	8/07/85 1500	1 1-liter poly	California Analytical/ Inorganic	Lot #35157312
Transfer Blank for lot #05175102	85320880	8/07/85 0900	Aqueous	0.2 ppb	463973974	8/07/85 1500	2 1-liter amber	EPA Lab/Pesticides	Lot #85175162
Transfer Blank	JA301	8/07/85 1300	Aqueous	Varies	155009260	8/07/85 1500	4 1-liter amber	A.T.I./Organics	Lot #85175162
EE-1	85320877	8/05/85 1040	Aqueous Grab	0.2 ppb	129006636	8/05/85 1530	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
EE-1	JA554	8/05/85 1040	Aqueous Grab	Varies	129006625	8/05/85 1530	2 40-ml vials 4 1-liter amber	A.T.I./Organics	Vial Lot #25292122
EE-1	MJA221	8/05/85 1040	Aqueous Grab	Varies	129006640	8/05/85 1530	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TOO NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PU22

Page 4 of 10

C-4

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-2	85320885	8/07/85 0930	Aqueous Grab	0.2 ppb	463973974	8/07/85 1500	2 1-liter amber	EPA Lab/Pesticides	
EE-2	JAS72	8/07/85 0930	Aqueous Grab	Varies	155009260	8/07/85 1500	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Lot #85172222
EE-2	MJA249	8/07/85 0930	Aqueous Grab	Varies	463973020	8/07/05 1500	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312
EE-3	85320881	0/07/85 1000	Aqueous Grab	0.2 ppb	85320881	0/07/05 1500	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
EE-3	JAS73	8/07/85 1000	Aqueous Grab	Varies	155009260	8/07/85 1500	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Amber Lot #05172222
EE-3	MJA240	8/07/85 1000	Aqueous Grab	Varies	463973020	8/07/85 1500	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312
EE-4	85281029	7/22/85 1415	Aqueous Grab	0.2 ppb	129006732	7/22/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #05172222
EE-4	JAS69	7/22/05 1415	Aqueous Grab	Varies	129006684	7/22/85 1600	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Amber Lot #85172222
EE-4	MJA234	7/22/05 1415	Aqueous Grab	Varies	129006743	7/22/05 1600	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312
EE-5	05281030	7/22/85 1500	Aqueous Grab	0.2 ppb	129006732	7/22/85 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #05172222
EE-5	JAS70	7/22/05 1500	Aqueous Grab	Varies	129006684	7/22/85 1600	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Amber Lot #85172222
EE-5	MJA238 (MJA235)	7/22/85 1500	Aqueous Grab	Varies	129006743	7/22/85 1600	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TDD NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 5 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-6	85320870	8/05/85 0930	Aqueous Grab	0.2 ppb	129006636	8/05/85 1530	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
EE-6	JA575	8/05/85 0930	Aqueous Grab	Varies	129006625	8/05/85 1530	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Amber Lot #85172222
EE-6	MJA227	8/05/85 0930	Aqueous Grab	Varies	129006640	8/05/85 1530	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312
EE-7	05320079	0/05/85 0030	Same	0.2 ppb	129006636	0/05/85 1530	2 1-liter amber	EPA Lab/Pesticides	Lot #05172222
EE-7	JA576	8/05/85 0830	Same	Varies	129006625	8/05/85 1530	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Amber Lot #85172222
C-5 EE-7	MJA237	8/05/85 0830	Same	Varies	129006640	8/05/85 1530	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312
EE-8	05310391	8/01/05 1130	Same	0.2 ppb	129006695	0/01/05 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #85172222
EE-0	JA574	8/01/85 1130	Same	Varies	129006754	8/01/85 1600	2 40-ml vials	EPA Lab/Pesticides	Vial Lot #24292122
EE-0	MJA223	0/01/05 1130	Same	Varies	129006706	8/01/85 1600	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312
EE-9	05310390	0/01/85 1400	Aqueous Grab	0.2 ppb	129006695	0/01/05 1600	2 1-liter amber	EPA Lab/Pesticides	Lot #05172222
EE-9	JA571	0/01/05 1400	Aqueous Grab	Varies	129006754	0/01/05 1600	2 40-ml vials 4 1-liter amber	A.I.I./Organics	Vial Lot #24292122 Amber Lot #85172222
EE-9	MJA222	8/01/85 1400	Aqueous Grab	Varies	129006706	8/01/85 1600	1 1-liter poly	California Analytical/ Inorganics	Lot #35157312

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TDD NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 6 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-1 10-30 ft.	85310396	8/02/85 0810	Soil Composite	0.2 ppb	129006603	8/02/85 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-1 10-30 ft.	JA544	8/02/85 0810	Soil Composite	Varies	12900651	8/05/85 1600	8 oz. glass jar	EAL/Organics	
EE-1 10-30 ft.	MJA210	8/02/85 0810	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-1 30-gw	85310397	8/02/85 1030	Soil Composite	0.2 ppb	129006603	8/02/85 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-1 30-gw	JA545	8/02/05 1030	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-1 30-gw	MJA211	8/02/85 1030	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-2 10-30 ft.	85320882	8/06/05 0000	Soil Composite	0.2 ppb	463973974	8/07/85 1500	8 oz. glass jar	EPA Lab/Pesticides	
EE-2 10-30 ft.	JA546	8/06/05 0800	Soil Composite	Varies	155009271	8/07/05 1500	8 oz. glass jar	EAL/Organics	
EE-2 10-30 ft.	MJA212	8/06/85 0800	Soil Composite	Varies	463973020	8/07/85 1500	8 oz. glass jar	California Analytical/ Inorganics	
EE-2 30-gw	85320003	8/06/85 1015	Soil Composite	0.2 ppb	463973974	8/07/05 1500	8 oz. glass jar	EPA Lab/Pesticides	
EE-2 30-gw	JA547	8/06/85 1015	Soil Composite	Varies	155009271	8/07/85 1500	8 oz. glass jar	EAL/Organics	
EE-2 30-gw	MJA213	8/06/85 1015	Soil Composite	Varies	463973020	8/07/05 1500	8 oz. glass jar	California Analytical/ Inorganics	

C-6



SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TDD NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 7 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-3 10-30 ft.		8/07/05 0930	Soil Composite	0.2 ppb			8 oz. glass jar	EPA Lab/Pesticides	
EE-3 10-30 ft.	JA560	0/07/05 0930	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-3 10-30 ft.	MJA228	8/07/85 0930	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-3 30-gw		8/07/85 1030	Soil Composite	0.2 ppb			8 oz. glass jar	EPA Lab/Pesticides	
EE-3 30-gw	JA561	8/07/85 1030	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-3 30-gw	MJA229	8/07/05 1030	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-4 10-20 ft.	85290825	7/17/85 1340	Soil Composite	0.2 ppb	129006603	8/02/85 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-4 10-20 ft.	JA562	7/17/85 1340	Soil Composite	Varies	129006651	0/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-4 10-20 ft.	MJA231	7/17/85 1340	Soil Composite	Varies	129006640	0/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-4 20-gw	85290826	7/17/85 1615	Soil Composite	0.2 ppb	129006603	8/02/85 1600	0 oz. glass jar	EPA Lab/Pesticides	
EE-4 20-gw	JA563	7/17/85 1615	Soil Composite	Varies	129006651	8/05/85 1530	0 oz. glass jar	EAL/Organics	
EE-4 20-gw	MJA230	7/17/85 1615	Soil Composite	Varies	129006640	8/85/85 1530	0 oz. glass jar	California Analytical/ Inorganics	

C-7

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TDD NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 8 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-5 10-20 ft.	85290827	7/19/85 1340	Soil Composite	0.2 ppb	129006603	8/02/85 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-5 10-20 ft.	JA565	7/19/85 1340	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-5 10-20 ft.	MJA232	7/19/85 1340	Soil Composite	Varies	129006640	0/05/05 1530	0 oz. glass jar	California Analytical/ Inorganics	
EE-5 20-gw	05290828	7/19/05 1615	Soil Composite	0.2 ppb	129006603	0/02/05 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-5 20-gw	JA566	7/19/05 1615	Soil Composite	Varies	129006651	0/05/05 1530	8 oz. glass jar	EAL/Organics	
EE-5 20-gw	MJA233	7/19/05 1615	Soil Composite	Varies	129006640	8/05/05 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-6 10-30 ft.	05310394	7/31/05 0920	Soil Composite	0.2 ppb	129006603	8/02/85 1600	0 oz. glass jar	EPA Lab/Pesticides	
EE-6 10-30 ft.	JA552	7/31/05 0920	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-6 10-30 ft.	MJA210	7/31/05 0920	Soil Composite	Varies	129006640	0/05/05 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-6 30-gw	85310395	7/31/85 1145	Soil Composite	0.2 ppb	129006603	8/02/85 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-6 30-gw	JA553	7/31/85 1145	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-6 30-gw	MJA219	7/31/85 1145	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	

C-100

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TDD NO. : R10-8410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 9 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-7 10-30 ft.	85310392	7/29/85 0935	Soil Composite	0.2 ppb	129006603	8/02/85 1600	0 oz. glass jar	EPA Lab/Pesticides	
EE-7 10-30 ft.	JA557	7/29/85 0935	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-7 10-30 ft.	MJA224	7/29/05 0935	Soil Composite	Varies	129006640	0/05/05 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-7 30-gw	85310393	7/29/85 1150	Soil Composite	0.2 ppb	129006603	0/02/05 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-7 30-gw	JA558	7/29/05 1150	Soil Composite	Varies	129006651	0/05/05 1530	8 oz. glass jar	EAL/Organics	
EE-7 30-gw	MJA225	7/29/05 1150	Soil Composite	Varies	129006640	0/05/05 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-8 10-30 ft.	05300050	7/23/05 1045	Soil Composite	0.2 ppb	129006603	0/02/05 1600	8 oz. glass jar	EPA Lab/Pesticides	
EE-8 10-30 ft.	JA548	7/23/05 1045	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-8 10-30 ft.	MJA214	7/23/85 1045	Soil Composite	Varies	129006640	0/05/05 1530	0 oz. glass jar	California Analytical/ Inorganics	
EE-8 30-gw	85300851	7/23/05 1230	Soil Composite	0.2 ppb	129006603	0/02/05 1600	0 oz. glass jar	EPA Lab/Pesticides	
EE-8 30-gw	JA549	7/23/05 1230	Soil Composite	Varies	129006651	0/05/05 1530	8 oz. glass jar	EAL/Organics	
EE-8 30-gw	MJA215	7/23/85 1230	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	

SITE NAME: RESOURCE RECOVERY  
CASE NO. 4768

TOO NO. : R10-B410-14  
PROJECT CODE: TCE-2394  
ACCOUNT NO. : TGB-10-PUZZ

Page 10 of 10

Location Number (RRC-)	Sample Number	Date/Time Collected	Matrix/Grab or Composite	Detection Limit	Federal Express Air Bill Number	Date/Time Shipped	Sample Containers	Destination/ Analysis	Remarks
EE-9 10-30 ft.	85300852	7/25/85 0845	Soil Composite	0.2 ppb	129006603	0/02/05 1600	0 oz. glass jar	EPA Lab/Pesticides	
EE-9 10-30 ft.	JA550	7/25/05 0845	Soil Composite	Varies	129006651	0/05/05 1530	8 oz. glass jar	EAL/Organics	
EE-9 10-30 ft.	MJA216	8/25/85 0845	Soil Composite	Varies	129006640	8/05/85 1530	8 oz. glass jar	California Analytical/ Inorganics	
EE-9 30-gw	85310853	7/25/85 1100	Soil Composite	0.2 ppb	129006603	8/02/05 1600	0 oz. glass jar	EPA Lab/Pesticides	
EE-9 30-gw	JA551	7/25/85 1100	Soil Composite	Varies	129006651	8/05/85 1530	8 oz. glass jar	EAL/Organics	
EE-9 30-gw	MJA217	7/25/05 1100	Soil Composite	Varies	129006640	8/05/05 1530	8 oz. glass jar	California Analytical/ Inorganics	

0-10

APPENDIX D

ANALYTICAL REQUIREMENTS  
EPA HAZARDOUS SUBSTANCE LIST

## ANALYTICAL REQUIREMENTS

Analytical methods and data quality from contract laboratories is described in detail in IFB WA 84-A266, Chemical Analytical Services for Organics, and IFB WA 84-J091, Chemical Analytical Services for Inorganics. All contract laboratories were required to conform to these standards. Herbicide analyses were conducted using EPA approved extraction, analytical and quality assurance techniques, e.g. Standard Methods for the Examination of Water and Wastewater, 15th Edition, Method 509B (Chlorinated Phenoxy Acid Herbicides). Identification and quantification of herbicides was to be confirmed using two different chromatography columns.

TABLE D-1  
ORGANICS ANALYSES  
Hazardous Substance List (HSL) and  
Contract Required Detection Limits (CRDL) \*

Compound	Detection Limits	
	Low Water <sup>a</sup> (ug/l)	Low Soil/Sediment <sup>b</sup> (ug/kg)
VOLATILES		
1. Chloromethane	10	10
2. Bromomethane	10	10
3. Vinyl Chloride	10	10
4. Chloroethane	10	10
5. Methylene Chloride	5	5
6. Acetone	10	10
7. Carbon Disulfide	5	5
8. 1,1-Dichloroethene	5	5
9. 1,1-Dichloroethane	5	5
10. trans-1,2-Dichloroethene	5	5
11. Chloroform	5	5
12. 1,2-Dichloroethane	5	5
13. 2-Butanone	10	10
14. 1,1,1-Trichloroethane	5	5
15. Carbon Tetrachloride	5	5
16. Vinyl Acetate	10	10
17. Bromodichloromethane	5	5
18. 1,1,2,2-Tetrachloroethane	5	5
19. 1,2-Dichloropropane	5	5
20. trans-1,3-Dichloropropene	5	5
21. Trichloroethene	5	5
22. Dibromochloromethane	5	5
23. 1,1,2-Trichloroethane	5	5
24. Benzene	5	5
25. cis-1,3-Dichloropropene	5	5
26. 2-Chloroethyl Vinyl Ether	10	10
27. Bromoform	5	5
28. 2-Hexanone	10	10
29. 4-Methyl-2-pentanone	10	10
30. Tetrachloroethene	5	5
31. Toluene	5	5
32. Chlorobenzene	5	5
33. Ethyl Benzene	5	5
34. Styrene	5	5
35. Total Xylenes	5	5

TABLE D-1 (CONT.)

Compound	Detection Limits	
	Low Water <sup>c</sup> (ug/l)	Low Soil/Sediment <sup>d</sup> (ug/kg)
EXTRACTABLE ORGANICS		
1. N-Nitrosodimethylamine	10	330
2. Phenol	10	330
3. Aniline	10	330
4. bis(2-Chloroethyl) Ether	10	330
5. 2-Chlorophenol	10	330
6. 1,3-Dichlorobenzene	10	330
7. 1,4-Dichlorobenzene	10	330
8. Benzyl Alcohol	10	330
9. 1,2-Dichlorobenzene	10	330
10. 2-Methylphenol	10	330
11. bis(2-Chloroisopropyl) Ether	10	330
12. 4-Methylphenol	10	330
13. N-Nitroso-dipropylamine	10	330
14. Hexachloroethane	10	330
15. Nitrobenzene	10	330
16. Isophorone	10	330
17. 2-Nitrophenol	10	330
18. 2,4-Dimethylphenol	10	330
19. Benzoic Acid	50	330
20. bis(2-Chloroethoxy)methane	10	1600
21. 2,4-Dichlorophenol	10	330
22. 1,2,4-Trichlorobenzene	10	330
23. Naphthalene	10	330
24. 4-Chloroaniline	10	330
25. Hexachlorobutadiene	10	330
26. 4-Chloro-3-methylphenol (para-chloro-meta-cresol)	10	330
27. 2-Methylnaphthalene	10	330
28. Hexachlorocyclopentadiene	10	330
29. 2,4,6-Trichlorophenol	10	330
30. 2,4,5-Trichlorophenol	50	1600
31. 2-Chloronaphthalene	10	330
32. 2-Nitroaniline	50	1600
33. Dimethyl Phthalate	10	330
34. Acenaphthylene	10	330
35. 3-Nitroaniline	50	1600



TABLE D-1 (CONT.)

Compound	Detection Limits	
	Low Water <sup>c</sup> (ug/l)	Low Soil/Sediment <sup>d</sup> (ug/kg)
EXTRACTABLE ORGANICS (cont.)		
36. Acenaphthene	10	330
37. 2,4-Dinitrophenol	50	1600
38. 4-Nitrophenol	50	1600
39. Dibenzofuran	10	330
40. 2,4-Dinitrotoluene	10	330
41. 2,6-Dinitrotoluene	10	330
42. Diethylphthalate	10	330
43. 4-Chlorophenyl Phenyl Ether	10	330
44. Fluorene	10	330
45. 4-Nitroaniline	50	1600
46. 4,6-Dinitro-2-methylphenol	50	1600
47. N-nitrosodiphenylamine	10	330
48. 4-Bromophenyl Phenyl Ether	10	330
49. Hexachlorobenzene	10	330
50. Pentachlorophenol	50	1600
51. Phenathrene	10	330
52. Anthracene	10	330
53. Di-n-butylphthalate	10	330
54. Fluoranthene	10	330
55. Benzidine	50	1600
56. Pyrene	10	330
57. Butyl Benzyl Phthalate	10	330
58. 3,3'-Dichlorobenzidine	20	660
59. Benzo(a)anthracene	10	330
60. bis(2-Ethylhexyl)phthalate	10	330
61. Chrysene	10	330
62. Di-n-octyl Phthalate	10	330
63. Benzo(b)fluoranthene	10	330
64. Benzo(k)fluoranthene	10	330
65. Benzo(a)pyrene	10	330
66. Indeno(1,2,3-cd)pyrene	10	330
67. Dibenz(a,h)anthracene	10	330
68. Benzo(g,h,i)perylene	10	330

TABLE D-1 (CONT.)

Compound	Detection Limits	
	Low Water <sup>e</sup> (ug/l)	Low Soil/Sediment <sup>f</sup> (ug/kg)
PESTICIDES		
1. alpha-BHC	.05	2
2. beta-BHC	.05	2
3. delta-BHC	.05	2
4. gamma-BHC (Lindane)	.05	2
5. Heptachlor	.05	2
6. Aldrin	.05	2
7. Heptachlor Epoxide	.05	2
8. Endosulfan I	.05	2
9. Dieldrin	.1	4
10. 4,4'-DDE	.1	4
11. Endrin	.1	4
12. Endosulfan II	.1	4
13. 4,4'-DDD	.1	4
14. Endrin Aldehyde	.1	4
15. Endosulfan Sulfate	.1	4
16. 4,4'-DDT	.1	4
17. Endrin Ketone	.1	4
18. Methoxychlor	.5	20
19. Chlordane	.5	20
20. Toxaphene	1.0	40
21. AROCHLOR 1016	.5	20
22. AROCHLOR 1221	.5	20
23. AROCHLOR 1232	.5	20
24. AROCHLOR 1242	.5	20
25. AROCHLOR 1248	.5	20
26. AROCHLOR 1254	1.0	40
27. AROCHLOR 1260	1.0	40

\* Specific detection limits are highly matrix dependent. The detection limits listed herein are provided for guidance and may not always be achievable.

a Medium Water Contract Required Detection Limits (CRDL) for Volatile HSL Compounds are 100 times the individual Low Water CRDL.

b Medium Soil/Sediment Contract Required Detection Limits (CRDL) for Volatile HSL Compounds are 100 times the individual Low Soil/Sediment CRDL.

TABLE D-1 (CONT.)

- c Medium Water Contract Required Detection Limits (CRDL) for Semi-Volatile HSL Compounds are 100 times the individual Low Water (CRDL).
- d Medium Soil/Sediment Contract Required Detection Limits (CRDL) for Semi-Volatile HSL Compounds are 60 times the individual Low Soil/Sediment (CRDL).
- e Medium Water Contract Required Detection Limits (CRDL) for Pesticide HSL Compounds are 100 times the individual Low Water (CRDL).
- f Medium Soil/Sediment Contract Required Detection Limits (CRDL) for Pesticide HSL Compounds are 60 times the individual Low Soil/Sediment (CRDL).

TABLE D-2  
INORGANIC ANALYSES

Element	Contract Required Detection Limits Water (ug/l)
Aluminum	200
Antimony	60
Arsenic	10
Barium	200
Beryllium	5
Cadmium	5
Calcium	5000
Chromium	10
Cobalt	50
Copper	25
Iron	100
Lead	5
Magnesium	5000
Manganese	15
Mercury	0.2
Nickel	40
Potassium	5000
Selenium	5
Silver	10
Sodium	5000
Thallium	10
Tin	40
Vanadium	50
Zinc	20
Cyanide	10

TABLE D-3  
PHENOXY HERBICIDE ANALYSES

Compound	Detection Limits	
	Water (ug/l)	Soil/Sediment (ug/kg)
HERBICIDES		
1. 2,4-Dichlorophenoxyacetic acid (2,4-D)	0.05	0.2
2. 2,4,5-Trichlorophenoxyacetic acid (2,4,5-T)	0.05	0.2
3. Silvex/2,4,5-Trichlorophenoxy- propionic acid (2,4,5-TP)	0.05	0.2
4. 2-Methyl-4 chlorophenoxyacetic acid (MCPA)	0.05	0.2

TABLE D-4  
ADDITIONAL ANALYSES

If the soil analyses indicate the presence of 2,4-D; 2,4,5-T; Silvex; or MCPA, archived soil samples will be submitted for dioxin analysis.

Laboratory analysis and contaminant quantification in soil samples will be conducted for:

- o 2,3,7,8-Tetrachlorodibenzo-p-dioxin (2,3,7,8-TCDD)
- o 2,3,7,8-Tetrachlorodibenzofuran (2,3,7,8-TCDF)
- o  $\Sigma$  all 22 tetrachlorodibenzo-p-dioxin isomers (TCDDs)
- o  $\Sigma$  all 38 tetrachlorodibenzofuran isomers (TCDFs)
- o  $\Sigma$  all 14 pentachlorodibenzo-p-dioxin isomers (PsCDDs)
- o  $\Sigma$  all 28 pentachlorodibenzofuran isomers (PeCDFs)
- o  $\Sigma$  all 10 hexachlorodibenzo-p-dioxin isomers (HxCDDs)
- o  $\Sigma$  all 16 hexachlorodibenzofuran isomers (HxCDFs)

APPENDIX E

QUALITY ASSURANCE MEMORANDA



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## MEMORANDUM

DATE: February 6, 1986

TO: John Osborn, FIT RPO, USEPA, Seattle

FROM: Roger McGinnis, Chemist, E&E, Seattle *rm*  
Andrew Hafferty, Senior Chemist, E&E, Seattle *AH*

THRU: D.A. Buecker, FIT RPM, E&E, Seattle *DB*

SUBJ: QA of Case 4679 (Inorganics)  
Resource Recovery WA 0280

CC: Gerald Muth, DPO, USEPA, Region X  
Harold Takenaka, DPO, USEPA, Region IX  
Jack Sceva, USEPA, Seattle  
Bill Ritthaler, E&E, Seattle

The Quality Assurance review of seven samples, Case 4679, collected at Resource Recovery has been completed. The seven water samples were analyzed at low level for inorganics by California Analytical Laboratories of West Sacramento, California. The samples were numbered:

MJA201	MJA206
MJA202	MJA207
MJA203	MJA208
MJA205	

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control Specifications outlined in IFB WA84J-091.

- 1) Timeliness - Acceptable
- 2) Initial Calibration - Acceptable
- 3) Continuing Calibration - Acceptable
- 4) Blanks - Acceptable
- 5) Instrument Detection Limits - Acceptable



Case 4679  
Page Two

- 6) ICP Interference Check - Acceptable
- 7) Laboratory Control Sample - Acceptable
- 8) Duplicate Sample Analysis - Acceptable
- 9) Spiked Sample Analysis

Two out of 24 spike % recoveries were out of control.

<u>Element</u>	<u>% Recovery</u>	<u>QC Limit</u>
Selenium	42%	75-125%
Thallium	58%	75-125%

- 10) Furnace AA - Acceptable
- 11) ICP Serial Dilutions

One out of 24 elements was out of control.

<u>Element</u>	<u>% Difference</u>	<u>QC Limit</u>
Potassium	13.9%	< 10%

- 12) Mercury Analysis - Acceptable
- 13) Samples

Selenium and thallium results are flagged as estimated (J) based on low spike recoveries. Interferences were noted in selenium analyses of samples MJA202, 203, 205, 206, and 207. Potassium results are flagged as estimated (J) due to differences between the serial dilution and sample analyses. Reported antimony detection limits were slightly higher than contract required limits.

#### Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses" (R-582-5-5-01).

Upon consideration of the data qualifications noted above, the data are ACCEPTABLE for use except where flagged with data qualifiers which modify the usefulness of individual values.

Case 4679  
Page Three

Data Qualifiers

- U - The material was analyzed for, but was not detected. The associated numerical value is estimated sample quantitation limit.
- J - The associated numerical value is an estimated quantity because quality control criteria were not met.
- R - Quality Control indicates that data unusable (compound may or may not be present). Resampling and reanalysis is necessary for verification.
- Q - No analytical result.
- N - Presumptive evidence of presence of material (tentative identification).
- S - Indicates a value determined by method of standard addition.

RM:dlk



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## MEMORANDUM

DATE: September 6, 1985

TO: John Osborn, FIT RPO, USEPA, Region X

FROM: Roger McGinnis, Chemist, E&E, Seattle *RM*  
Andrew Hafferty, Senior Chemist, E&E, Seattle *990*

SUBJ: QA of Case 4679  
Resource Recovery WA 0280

THRU: Dave Buecker, FIT RPM, E&E, Seattle *DB*

REF: TDD-R10-8507-01

CC: Gerald Muth, EPA, Manchester  
Jack Sceva, EPA, Seattle  
Harold Takenaka, DPO, EPA, Region IX  
Bill Ritthaler, E&E, Seattle

The Quality Assurance review of two samples. Case 4679, collected at Resource Recovery has been completed. Two water samples were analyzed at low level for inorganics by California Analytical Laboratories of West Sacramento, California. The samples were numbered:

MJA234  
MJA238

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control Specifications outlined in IFB WA 84J091.

- 1) Timeliness - Acceptable
- 2) Calibration Verification - Acceptable
- 3) Blanks - Acceptable

Beryllium, chromium, iron, and vanadium were present in the laboratory blank but at levels less than the CRDL.

Case 4679  
Page Two

- 4) Instrument Detection Limits - Acceptable
- 5) ICP Interference Check - Acceptable
- 6) Laboratory Control Sample - Acceptable
- 7) Duplicate Sample Analysis - Acceptable
- 8) Spike Recoveries

One out of 24 elements was out of control.

<u>Element</u>	<u>% Recovery</u>	<u>QC Limit</u>
Mercury	70%	75-125%

- 9) Furnace AA - Acceptable
- 10) Mercury Analysis - Acceptable
- 11) Samples

Mercury results were flagged as estimated (J) based on low spike recovery.

#### Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses (R-582-5-5-01)."

The data are ACCEPTABLE for use except where flagged with data qualifiers which modify the usefulness of the individual values.

#### Data Qualifiers

- U - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit.
- J - The associated numerical value is an estimated quantity because quality control criteria were not met.
- R - Quality control indicates that data are unusable (compound may or may not be present). Resampling and analysis is necessary for verification.
- Q - No analytical result.
- N - Presumptive evidence of presence of material (tentative identification).



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## MEMORANDUM

DATE: September 13, 1985

TO: John Osborn, FIT RPO, USEPA, Region X

FROM: Roger McGinnis, Chemist, E&E, Seattle *rm*  
Andrew Hafferty, Senior Chemist, E&E, Seattle *998*

THRU: David Buecker, FIT RPM, E&E, Seattle *DB*

SUBJ: QA of Case 4768 (Inorganics)  
Resource Recovery WA 0280

REF: TDD R10-8507-01

CC: Gerald Muth, EPA, Manchester  
Harold Takenaka, DPO, EPA, Region IX  
Bill Ritthaler, E&E, Seattle

The Quality Assurance review of 26 samples. Case 4768, collected at Resource Recovery has been completed. The eight water samples and 18 soil samples were analyzed at low level for inorganics by California Analytical Laboratories, Inc. of West Sacramento, California. The samples were numbered:

MJA222	MJA216	MJA231
MJA223	MJA217	MJA232
MJA221	MJA218	MJA233
MJA227	MJA219	MJA212
MJA237	MJA224	MJA213
MJA210	MJA225	MJA236
MJA211	MJA228	MJA248
MJA214	MJA229	MJA249
MJA215	MJA230	

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control Specifications outlined in IFB WA84A-266.

- 1) Timeliness - Acceptable
- 2) Initial Calibration - Acceptable

- 3) Continuing Calibration - Acceptable
- 4) Blanks - Acceptable
- 5) Instrument Detection Limits - Acceptable
- 6) ICP Interference Check - Acceptable
- 7) Laboratory Control Sample - Acceptable
- 8) Duplicate Sample Analysis

Two out of 24 of the water matrix sample % RPDs were out of control.

<u>Element</u>	<u>% RPD</u>	<u>QC Limit</u>
Lead	34%	<20%
Vanadium	21%	<20%

- 9) Spiked Sample Analysis

Two out of 18 soil matrix sample % recoveries were out of control.

<u>Element</u>	<u>% Recovery</u>	<u>QC Limit</u>
Antimony	58%	75-125%
Selenium	30%	75-125%

Four out of 24 water matrix sample % recoveries were out of control.

<u>Element</u>	<u>% Recovery</u>	<u>QC Limit</u>
Antimony	56%	75-125%
Arsenic	65%	75-125%
Lead	15%	75-125%
Thallium	68%	75-125%

- 10) ICP Serial Dilution

No serial dilution was done for a soil matrix sample.

- 11) Furnace AA - Acceptable
- 12) Mercury Analysis - Acceptable

### 13) Samples

Results are reported on a dry weight basis for soil matrix samples. Antimony and selenium results for soil samples are flagged as estimated (J) based on low spike recoveries.

Vanadium results for water matrix samples are flagged as estimated (J) due to low duplicate analysis RPDs. Antimony, arsenic, and thallium results for water samples are flagged as estimated (J) based on low spike recoveries. Lead results for water samples are rejected (R) due to excessively low spike recovery.

### Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses" (R-582-5-5-01).

The data are ACCEPTABLE for use except where flagged with data qualifiers which modify the usefulness of the individual values.

Lead data for water samples are NOT usable.

### Data Qualifiers

- U - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit.
- J - The associated numerical value is an estimated quantity because quality control criteria were not met.
- R - Quality Control indicates that data are unusable (compound may or may not be present). Resampling and reanalysis is necessary for verification.
- Q - No analytical result.
- N - Presumptive evidence of presence of material (tentative identification).
- E - The detection limit was elevated as a result of matrix interference.

RH: dk



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## MEMORANDUM

DATE: September 13, 1985

TO: John Osborn, FIT RPO, USEPA, Region X

FROM: Roger McGinnis, Chemist, E&E, Seattle *RM*  
Andrew Hafferty, Senior Chemist, E&E, Seattle *AH*

THRU: Dave Buecker, FIT RPM, E&E, Seattle *DB*

SUBJ: QA of Case 4768 (HSL Organics)  
Resource Recovery, WA 0280

REF: TDD R10-8507-01

CC: Gerald Muth, EPA, Manchester  
Jack Sceva, EPA, Seattle  
Harold Takenaka, DPO, EPA, Region IX  
Bill Ritthaler, E&E, Seattle

The Quality Assurance review of 12 samples. Case 4768, collected at Resource Recovery Landfill has been completed. The 12 water samples were analyzed at low level by Analytical Technologies, Inc. of National City, California for full HSL organics. The samples were numbered:

JA301	JA554	JA573
JA302	JA568	JA574
JA303	JA571	JA575
JA338	JA572	JA576

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control Specifications outlined in IFB WA84A-266.

#### I. Volatiles and Semi-Volatile Compounds

- 1) Timeliness - Acceptable
- 2) GC/MS Instrument Tuning - Acceptable
- 3) Initial Calibration - Acceptable
- 4) Continuing Calibration - Acceptable
- 5) Instrument Detection Limits - Acceptable



6) Blanks

The VOA fraction blanks all contained several contaminants but all were present at levels less than the CRDL.

The semi-volatile fraction blanks contained several contaminants present at levels less than the CRDL. The BNA blank prepared on 8/08/85 contained 84 ug/l of di-n-octylphthalate which is greater than 5 times the CRDL.

7) Surrogate Recoveries

Twelve out of 96 semi-volatiles % Recoveries were out of control.

<u>Sample</u>	<u>Compound</u>	<u>% Recovery</u>	<u>QC Limit</u>
JA568	d <sub>5</sub> -nitrobenzene	33%	41-120%
JA571	d <sub>5</sub> -nitrobenzene	12%	41-120%
JA573	d <sub>5</sub> -phenol	10%	15-96 %
	2-fluoropheol	4%	23-107%
	2,4,6-tribromophenol	7%	20-105%
JA575	d <sub>5</sub> -nitrobenzene	27%	41-120%
JA576	d <sub>5</sub> -nitrobenzene	3%	41-120%
	2-flurobiphenyl	27%	44-119%
JA301	d <sub>5</sub> -nitrobenzene	0%	41-120%
	2-flurobiphenyl	1%	44-119%
JA303RE	2-flurobiphenyl	33%	44-119%
Blank (8/13/85)	2-flurobiphenyl	39%	44-119%

Samples JA568, JA571, JA573, JA575, JA576, and JA301 were not re-extracted as required, due to insufficient sample volume.

8) Matrix Spike and Matrix Spike Duplicates

Two out of 20 VOA % Recoveries were out of control.

<u>Sample</u>	<u>Compound</u>	<u>% Recovery</u>	<u>QC Limit</u>
JA554 MS	1,1-dichloroethene	150%	61-145%
JA554 MSD	1,1-dichloroethene	150%	61-145%

Six out of 48 semi-volatile % Recoveries were out of control.

<u>Sample</u>	<u>Compound</u>	<u>% Recovery</u>	<u>QC Limit</u>
JA572 MSD	1,2,4-Trichlorobenzene	35%	39-98 %
JA572 MS	di-n-butylphthalate	10%	11-117%

<u>Sample</u>	<u>Compound</u>	<u>% Recovery</u>	<u>QC Limit</u>
JA572 MS	2-chlorophenol	138%	27-123%
JA572 MSD	2-chlorophenol	148%	27-123%
JA572 MS	2-chloro-3-methylphenol	141%	23-97 %
JA572 MSD	2-chloro-3-methylphenol	141%	23-97 %

9) Laboratory Contact

The laboratory was contacted on September 19, 1985. See attached telephone log.

10) Samples

The results for the base/neutral fraction of samples JA301 and JA576 were rejected (R) for compounds not detected and were flagged as estimated (J) for compounds which were detected, as required when surrogate % Recoveries are less than 10%.

The results for the acid fraction of sample JA573 were rejected (R) for compounds not detected and were flagged as estimated (J) for compounds which were detected, as required when surrogate % Recoveries were less than 10%.

II. Pesticides/PCBs

- 1) Timeliness - Acceptable
- 2) Instrument Performance - Acceptable
- 3) Calibration

The laboratory reported the linearity standard deviation rather than the % RSD on 8/07/85. The % RSD for Endrin was 13% (QA Limit < 10%).

- 4) Blanks - Acceptable
- 5) Surrogate Recoveries

Four dibutylchloroendate surrogate % Recoveries were outside the advisory limits.

- 6) Matrix Spike and Matrix Spike Duplicates - Acceptable

7) Samples

Results for Endrin were flagged as estimated (J) based on a high % RSD.

Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Organic Analyses" (R-582-5-5-01).

The data are ACCEPTABLE for use except where flagged with data qualifiers which modify the use of the individual values.

Data Qualifiers

- U - The material was analyzed for, but was not detected. The associated numerical value is estimated sample quantitation limit.
- J - The associated numerical value is an estimated quantity because quality control criteria were not met.
- R - Quality Control indicates that data are unusable (compound may or may not be present). Resampling and reanalysis is necessary for verification.
- Q - No analytical result.
- N - Presumptive evidence of presence of material (tentative identification).

RM:jkb

In Reference to Case No(s):  
4768

Contract Laboratory Program  
REGIONAL/LABORATORY COMMUNICATION SYSTEM

Telephone Record Log

Date of Call: 6 September 85  
Laboratory Name: Analytical Technologies Inc  
Lab Contact: Mike Hiatt  
Region: 10  
Regional Contact: Andrew Hafferty  
Call Initiated By:      Laboratory X Region

In reference to data for the following sample number(s):

\_\_\_\_\_

\_\_\_\_\_


\_\_\_\_\_

Summary of Questions/Issues Discussed:

1. VOA LLDs for CS<sub>2</sub>, 1,1,1-trichloroethane, 2,2,2-trichloroethane
2. Benzidine LLD varies
3. JA 554 RE why no PCP hit reported
4. JA 575 why no trans 1,2-dichloroethane hit reported

Summary of Resolution:

1530 call by AH to ATI - M. Ke. Hiatt unavailable will call back  
19 Sept contact with Mike Hiatt - missed conversations several times previously  
1 & 2 normal LLD work close enough to required LLD - lab made aware of the discrepancy  
#3 PCP hit is real we will edit data and initial  
#4 - not a real hit

  
Signature

19 September 85  
Date

Distribution: (1) Lab Copy, (2) Region Copy, (3) SMO Copy



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## MEMORANDUM

DATE: September 6, 1985

TO: John Osborn, FIT RPO, USEPA, Region X

FROM: John Ryding, Chemist, E&E, Seattle *JmR*  
Andrew Hafferty, Senior Chemist, E&E, Seattle *9907*

SUBJ: QA of Case 4679 (Organics)  
Resource Recovery WA 0280

THRU: Dave Buecker, FIT RPM, E&E, Seattle *db*

REF: TDD-R10-8507-01

CC: Gerald Muth, EPA, Manchester  
John Tilstra, DPO, EPA, Region VIII  
Andrew Hafferty, E&E, Seattle

The Quality Assurance review of fourteen samples, Case 4579, collected at Resource Recovery has been completed. Fourteen water samples were analyzed at low level by Rocky Mountain Analytical Lab of Arvada, Colorado. Four samples were analyzed for volatiles, nine samples were analyzed for full HSL organics and one sample was analyzed for extractables. The samples were numbered:

<u>Sample</u>	<u>Analysis</u>	<u>Sample</u>	<u>Analysis</u>
JA533	HSL	JA540	HSL
JA534	VOA	JA541	HSL
JA535	HSL	JA542	VOA
JA536	HSL	JA569	HSL
JA537	VOA	JA570	HSL
JA538	HSL	JA578	VOA
JA539	HSL	JA579	Extractables

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control Specifications outlined in IFB WA84A-265.

Case 4679  
Page Two

1) Timeliness

The pesticide fraction extraction of samples JA533, JA535, JA536, JA538, JA539, JA540 and JA541 took place eight days after sample receipt. The QC limit is five days.

2) Instrument Tuning - Acceptable

3) Initial Calibration - Acceptable

4) Continuing Calibration

Two SPCC compounds were out of control.

<u>Compound</u>	<u>Date</u>	<u>Fraction</u>	<u>RF</u>	<u>QC Limit</u>
1,1,2,2-Tetrachloroethane	7/13	VOA	0.286	>0.300
2,4-Dinitrophenol	7/31	BNA	0.030	>0.050

One CCC compound was out of control.

<u>Compound</u>	<u>Date</u>	<u>Fraction</u>	<u>%D</u>	<u>QC Limit</u>
4-Chloro-3-methylphenol	8/17	BNA	43	25%

5) Detection Limits - Acceptable

6) Pesticide Standards

a. Linearity - The following compounds exceeded QC Limits.

<u>Compound</u>	<u>Date</u>	<u>Column</u>	<u>% RSD</u>	<u>QC Limit</u>
4,4'-DDT	7/25/85	3% OV-1	13	<10%
Aldrin	7/29/85	1.5% OV-17/1.95% QF-1	12.1	<10%

b. 4,4' DDT/Endrin Breakdown - Acceptable

c. Dibutylchloroendate Retention Time Shift

<u>Sample</u>	<u>Date</u>	<u>Column</u>	<u>% D</u>	<u>QC Limit</u>
JA533	7/25	3% OV-1	3.3	<2%
JA569	7/31	3% OV-1	3.7	<2%
JA570	7/31	3% OV-1	2.6	<2%
JA569	7/29	1.5% OV-17/1.95% QF-1	2.4	<2%

d. Standards Summary

The following compounds were out of control.

<u>Compound</u>	<u>Date</u>	<u>Column</u>	<u>% D</u>	<u>QC Limit</u>
4,4'-DDT	7/26	3% OV-1	24	<20%
Methoxychlor	8/1	3% OV-1	37	<20%

- 7) Blanks - Methylene Chloride, 2-Hexanone and 4-Methyl-2-Pentanone were reported in the blank.
- 8) Surrogates - Acceptable
- 9) Matrix Spike and Matrix Spike Duplicate

The following compounds exceeded % Recovery QC limits in samples JA533 (BNA) and JA535 (Pest.).

<u>Compound</u>		<u>Fraction</u>	<u>% Recovery</u>	<u>QC Limits</u>
1,2,4-Trichlorobenzene	(MS)	B/N	104%	39-98 %
1,2,4-Trichlorobenzene	(MSD)	B/N	118%	39-98 %
Pyrene	(MS)	B/N	128%	26-127%
Pentachlorophenol	(MS)	Acid	130%	09-103%
Pentachlorophenol	(MSD)	Acid	140%	09-103%
Lindane	(MS)	Pest.	130%	56-123%
Lindane	(MSD)	Pest.	135%	56-123%
Heptachlor	(MS)	Pest.	140%	40-131%
Heptachlor	(MSD)	Pest.	135%	40-131%
Aldrin	(MS)	Pest.	130%	40-120%
Aldrin	(MSD)	Pest.	125%	40-120%
Dieldrin	(MS)	Pest.	140%	52-126%
Dieldrin	(MSD)	Pest.	142%	52-126%
Endrin	(MS)	Pest.	142%	56-121%
Endrin	(MSD)	Pest.	134%	56-121%
4,4'-DDT	(MS)	Pest.	150%	38-127%
4,4'-DDT	(MSD)	Pest.	144%	38-127%

One compound in the B/N fraction of JA579 MSD was out of control for RPD.

<u>Compound</u>	<u>RPD</u>	<u>QC Limit</u>
Di-n-Butylphthalate	69.7	<40

- 10) Samples - TICs found in certain samples were also detected at equivalent levels in the blank. These compounds were deleted from the data sheets.

#### Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Organic Analyses (R-582-5-5-01)."

The data is ACCEPTABLE for use except where data qualifiers modify the usefulness of individual values.

#### Data Qualifiers

- U - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit.
- J - The associated numerical value is an estimated quantity because quality control criteria were not met.
- R - Quality Control indicates that data are unusable (compound may or may not be present).
- Q - No analytical result.
- N - Presumptive evidence of presence of material (tentative identification).





# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## MEMORANDUM

DATE: October 16, 1985

TO: John Osborn, FIT RPO, EPA, Seattle

FROM: John Ryding, Chemist, E&E, Seattle  
Andrew Hafferty, Senior Chemist, E&E, Seattle

THRU: D.A. Buecker, FIT RPM, E&E, Seattle

SUBJ: QA of Case 4768 (Organics)  
Resource Recovery WA 0280

REF: TDD R10-8510-01

CC: Gerald Muth, DPO, EPA, Region X  
Harold Takenaka, DPO, EPA, Region IX  
Bill Ritthaler, E&E, Seattle

The Quality Assurance review of 17 samples with one duplicate, Case 4768, collected at Resource Recovery has been completed. One soil sample was analyzed at low level for HSL volatiles only by EAL Corporation of Richmond, California. Sixteen soil samples and one duplicate were analyzed at low levels for HSL semi-volatiles and pesticides only. The samples were numbered:

JA339 (VOA)	JA551	JA561
JA544	JA552	JA562
JA545	JA553	JA563
JA548	JA557	JA563 (dup)
JA549	JA558	JA565
JA550	JA560	JA566

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control specifications outlined in IFB WA84A-266.

#### 1) Timeliness

The laboratory extracted and analyzed all samples within QC time limits. However, the following samples were held in the field for more than two days prior to shipment to the lab:

<u>Sample No</u>	<u>Holding Time in the Field</u>
JA548	13 days
JA549	13
JA550	11
JA551	11
JA552	6
JA553	6
JA557	6
JA558	6
JA563	19
JA565	17
JA566	17

- 2) Instrument Tuning - Acceptable
- 3) Initial and Continuing Calibrations - Acceptable
- 4) Detection Limits

In some instances, the detection limits for the multi-component pesticides and PCBs were above the CRDL.

5) Pesticide Standards

a) Linearity

On column SP-2250/SP-2401 (quantitation). This is a questionable choice as a confirmation column.

<u>Date</u>	<u>Instrument</u>	<u>Compound</u>	<u>% RSD</u>	<u>QC Limit</u>
9/9/85	2	Aldrin	14%	10%
9/9/85	2	4,4'-DDT	16%	10%
9/12/85	1	4,4'-DDT	16%	10%
9/12/85	2	Aldrin	14%	10%
9/12/85	2	4,4'-DDT	21%	10%

On column SE-30/SP-2401 (confirmation)

<u>Date</u>	<u>Instrument</u>	<u>Compound</u>	<u>% RSD</u>	<u>QC Limit</u>
9/9/85	2	4,4'-DDT	11%	10%
9/12/85	2	4,4'-DDT	16%	10%

- b) 4,4'-DDT/Endrin Breakdown - Acceptable
- c) Dibutylchloredate Retention Time Shift - Acceptable

d) Standards Summary

On the quantitation column

<u>Instrument</u>	<u>Compound</u>	<u>% D</u>	<u>QC Limit</u>
1	Endosulfan Sulfate	35%	15%

6) Blanks

Methylene chloride and bis(2-ethylhexyl)phthalate were found in the VOA and BNA blanks. The pesticide blank is not acceptable, the laboratory should take immediate action to eliminate an ongoing pesticide blank problem noted by the reviewers. Only one blank was run with two sets of samples run on different days.

7) Surrogates

Acceptable as reported; however, most of the surrogate recoveries could not be reproduced from the raw data.

8) Matrix Spike and Matrix Spike Duplicate

The following compounds exceeded QC limits for % recovery:

<u>Compound</u>	<u>% Recovery</u>	<u>QC Limit</u>
1,2,4-Trichlorobenzene (MSD)	34	38-107%
Pyrene (MS)	32	35-142%
Pyrene (MSD)	24	35-142%
Lindane (MS)	328	46-127%
Lindane (MSD)	364	46-127%
Heptachlor (MS)	24	35-130%
Heptachlor (MSD)	197	35-130%
Aldrin (MS)	373	34-132%
Aldrin (MSD)	392	34-132%
Endrin (MSD)	153	42-139%
4,4'-DDT (MS)	149	23-134%
4,4'-DDT (MSD)	163	23-134%

The % recoveries could not be reproduced from the raw data.

The following compounds exceed QC limits for RPD:

<u>Compound</u>	<u>RPD</u>	<u>QC Limit</u>
Acenaphthene	41	<19
1,4-Dichlorobenzene	28	<27
Phenol	68	<35
4-Nitrophenol	55	<50
Heptachlor	157	<31

9) Samples

The volatile fraction data of JA339 was flagged "J" due to the surrogate recoveries and contaminant concentrations being non-reproducible. The BNA data for samples JA550-JA560 was flagged "J" due to the non-reproducibility of the contaminant concentrations and surrogate recoveries. With a few exceptions all positive hits in the pesticide fraction were flagged "R" due to severe contamination in the blank. These exceptions are: JA557 4,4-DDD flagged "N," JA560 endosulfan sulfate and methoxychlor flagged "N," PCB data in JA560 acceptable (with "J"), and JA561 Aroclor 1242 flagged "N." All pesticide data has been flagged "J" due to poor linearity.

10) Tentatively Identified Compounds

4-Hydroxy-4-methyl-2-pentanone (diacetone alcohol) was detected and in some cases identified on the TIC data sheets in nearly every sample. This compound was detected in the blank but at significantly lower levels than in the samples. However, this compound is an aldol condensation product of an acetone reaction which has been noted in several other EAL data packages, e.g., E&E, QA memo dated October 3, 1985; Case 4680 from R. McGinnis and A. Hafferty to J. Osborn, RPO, USEPA, Region X. The data is not reliable and has been deleted from the data sheets in this report.

Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Organic Analyses (R-582-5-5-01)."

Considering the above mentioned factors, the data is useful for LIMITED PURPOSES ONLY.

Pesticide/PCB data indicating positive results, except where specifically mentioned, is unusable.

Data Qualifiers

U - The material was analyzed for, but was not detected. The associated numerical value is estimated sample quantitation limit.

J - The associated numerical value is an estimated quantity because quality control criteria were not met.

R - Quality Control indicates that data are unusable (compound may or may not be present). Resampling and reanalysis is necessary for verification.

Case 4768  
Page Five

Q - No analytical result.

N - Presumptive evidence of presence of material (tentative identification).

JR:dlk



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists In the Environmental Sciences

## MEMORANDUM

DATE: October 16, 1985

TO: John Osborn, FIT RPO, EPA, Seattle

FROM: John Ryding, Chemist, E&E, Seattle  
Andrew Hafferty, Senior Chemist, E&E, Seattle

THRU: D.A. Buecker, FIT RPM, E&E, Seattle

SUBJ: QA of Case 4768 (Organics)  
Resource Recovery WA 0280

REF: TDD R10-8510-01

CC: Gerald Muth, DPO, EPA, Region X  
Harold Takenaka, DPO, EPA, Region IX  
Bill Ritthaler, E&E, Seattle

The Quality Assurance review of two samples. Case 4768, collected at Resource Recovery has been completed. Two soil samples were analyzed at low level for semi-volatiles and pesticides/PCBs by EAL Corporation of Richmond, California. The samples were numbered:

JA546

JA547

### Data Qualifications

The following comments refer to the laboratory performance in meeting the Quality Control specifications outlined in IFB WA84A-265.

- 1) Timeliness - Acceptable
- 2) Instrument Tuning - Acceptable
- 3) Initial and Continuing Calibration - Acceptable
- 4) Detection Limits

Limits for multi-component pesticides and PCBs were above the CRDL.

5) Pesticide Standards

a) Linearity

On column SP-2250/SP-2401 (quantitation)

<u>Compound</u>	<u>% RSD</u>	<u>QC Limit</u>
Aldrin	15%	10%
Endrin	12%	10%
4,4'-DDT	21%	10%

On column SE-30/SP-2401 (confirmation). This is a questionable choice as a confirmation column.

<u>Compound</u>	<u>% RSD</u>	<u>QC Limit</u>
4,4'-DDT	16%	10%

b) 4,4'-DDT/Endrin Breakdown - Acceptable

c) Dibutylchlorendate Retention Time Shift - Acceptable

d) Standards Summary - Acceptable

6) Blanks

Bis(2-ethylhexyl)phthalate was found in the BNA blank. The pesticide blank is not acceptable. The laboratory should take immediate action to eliminate an ongoing pesticide blank problem noted by the reviewers.

7) Surrogates

Acceptable as reported; however, most of the surrogate recoveries could not be reproduced from the raw data.

8) Matrix Spike and Matrix Spike Duplicate

The following compounds exceeded QC limits for % recovery:

<u>Compound</u>	<u>% Recovery</u>	<u>QC Limit</u>
1,2,4-Trichlorobenzene (MSD)	34	38-107%
Pyrene (MS)	32	35-142%
Pyrene (MSD)	24	35-142%
Lindane (MS)	328	46-127%
Lindane (MSD)	364	46-127%
Heptachlor (MS)	24	35-130%

Heptachlor (MSD)	197	35-130%
Aldrin (MS)	373	34-132%
Aldrin (MSD)	392	34-132%
Endrin (MSD)	153	42-139%
4,4'-DDT (MS)	149	23-134%
4,4'-DDT (MSD)	163	23-134%

The % recoveries could not be reproduced from the raw data.

The following compounds exceed QC limits for RPD:

<u>Compound</u>	<u>RPD</u>	<u>QC Limit</u>
Acenaphthene	41	<19
1,4-Dichlorobenzene	28	<27
Phenol	68	<35
4-Nitrophenol	55	<50
Heptachlor	157	<31

9) Samples

The BNA fraction data was flagged "J" due to the non-reproducibility of the contaminant concentrations and surrogate recoveries. All positive hits of the pesticide fraction were flagged "R" due to severe contamination of the blank. All pesticide data was flagged "J" due to poor linearity.

10) Tentatively Identified Compounds

4-Hydroxy-4-methyl-2-pentanone (diacetone alcohol) was detected and identified on the TIC data sheets in nearly every sample. This compound was detected in the blank but at significantly lower levels than in the samples. However, this compound is an aldol condensation product of an acetone reaction which has been noted in several other EAL data packages, e.g., E&E, QA memo data October 3, 1985; Case 4680 from R. McGinnis and A. Hafferty to J. Osborn, RPO, USEPA, Region X. The data is not reliable and has been deleted from the data sheets in this report.

Data Use

The usefulness of the data is based on the criteria outlined in the "Laboratory Data Validation Functional Guidelines for Evaluating Organic Analyses (R-582-5-5-01)."

Considering the above mentioned factors, the data is useful for LIMITED PURPOSES ONLY.

Pesticide/PCB data is suspect.



Data Qualifiers

- U - The material was analyzed for, but was not detected. The associated numerical value is estimated sample quantitation limit.
- J - The associated numerical value is an estimated quantity because quality control criteria were not met.
- R - Quality Control indicates that data are unusable (compound may or may not be present). Resampling and reanalysis is necessary for verification.
- Q - No analytical result.
- N - Presumptive evidence of presence of material (tentative identification).

JR:dlk

APPENDIX F

SUBSURFACE SOIL ANALYTICAL RESULTS

Explanation of data modifiers:

U: undetected at specified level  
J: estimated concentration only  
R: value rejected during Quality Assurance review  
\*: not analyzed for  
GW: depth at which ground water was encountered  
SCAN: Relative Retention Time Indicator

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF BASE/NEUTRAL/ACID COMPOUND RESULTS  
FOR SUBSURFACE SEDIMENT SAMPLES COLLECTED JULY/AUGUST 1985  
(ug/kg) DRY WEIGHT

LOCATION	N-NITROSO DIMETHYLAMINE	PHENOL	ANILINE	BIS(2-CHLORO ETHYL)ETHER	2-CHLORO- PHENOL	1,3-DICHLORO BENZENE	1,4-DICHLORO BENZENE	BENZYL ALCOHOL
EE1 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE1 30'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE2 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE2 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 10-30'	350.00 U	260.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 30'-GW	350.00 U	1900.00 J	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE4 10-20'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE4 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE5 10-20'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE5 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE6 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE6 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE7 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE7 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE8 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE8 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE9 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE9 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U

LOCATION	1,2-DICHLORO BENZENE	2-METHYLPHENOL	BIS(2CHLOROISO PROPYL)ETHER	4-METHYL PHENOL	N-NITROSO DIPROPYLAMINE	HEXACHLORO ETHANE	NITROBENZENE	ISOPHORONE
EE1 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE1 30'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE2 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE2 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE4 10-20'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE4 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE5 10-20'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE5 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE6 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE6 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE7 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE7 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE8 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE8 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE9 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE9 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U

LOCATION	2-NITROPHENOL	2,4-DIMETHYL PHENOL	BENZOIC ACID	BIS(2-CHLORO ETHOXY)METHANE	2,4 DICHLORO PHENOL	1,2,4 - TRI CHLOROBENZENE	NAPHTHALENE
EE1 10-30'	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE1 30'-GW	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE2 10-30'	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE2 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 10-30'	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 J
EE3 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE4 10-20'	340.00 U	340.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE4 20'-GW	340.00 U	340.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE5 10-20'	360.00 U	360.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE5 20'-GW	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE6 10-30'	360.00 U	360.00 U	1700.00 U	1700.00 U	1700.00 U	1700.00 U	1700.00 U
EE6 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE7 10-30'	340.00 U	340.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE7 30'-GW	350.00 U	350.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE5 10-30'	350.00 U	350.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE8 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE9 10-30'	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE9 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U

LOCATION	4-CHLORO ANILINE	HEXACHLORO BUTADIENE	4-CHLORO- 3-METHYLPHENOL	2-METHYL NAPHTHALENE	HEXACHLOROXY CLOPENTADIENE	2,4,6-TRI CHLOROPHENOL	2,4,5-TRI CHLOROPHENOL
EE1 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	1700.00 U
EE1 30'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	1700.00 U
EE2 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE2 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE3 10-30'	350.00 U	350.00 U	350.00 U	1200.00 J	350.00 U	350.00 U	1700.00 U
EE3 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE4 10-20'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE4 20'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE5 10-20'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	1700.00 U
EE5 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	1700.00 U
EE6 10-30'	1700.00 U	1700.00 U	1700.00 U	1700.00 U	1700.00 U	1700.00 U	1700.00 U
EE6 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE7 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	1700.00 U
EE7 30'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	1700.00 U
EE8 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	1700.00 U
EE8 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U
EE9 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	1700.00 U
EE9 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	1700.00 U

LOCATION	2-CHLORO NAPHTHALENE	2-NITROANILINE	DIMETHYL PHTHALATE	ACENAPHTHYLENE	3-NITROANILINE	ACENAPHTHENE
EE1 10-30'	340.00 U	1700.00 U	340.00 U	340.00 U	1700.00 U	340.00 U
EE1 30'-GW	340.00 U	1700.00 U	340.00 U	340.00 U	1700.00 U	340.00 U
EE2 10-30'	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	350.00 U
EE2 30'-GW	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	350.00 U
EE3 10-30'	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	370.00 J
EE3 30'-GW	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	350.00 U
EE4 10-20'	340.00 U	1700.00 U	340.00 U	340.00 U	700.00 U	340.00 U
EE4 20'-GW	340.00 U	1700.00 U	340.00 U	340.00 U	1700.00 U	340.00 U
EE5 10-20'	340.00 U	1700.00 U	340.00 U	340.00 U	700.00 U	360.00 U
EE5 20'-GW	340.00 U	1700.00 U	340.00 U	340.00 U	1700.00 U	340.00 U
EE6 10-30'	360.00 U	1700.00 U	360.00 U	360.00 U	1700.00 U	360.00 U
EE6 30'-GW	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	350.00 U
EE7 10-30'	340.00 U	1700.00 U	340.00 U	340.00 U	1700.00 U	340.00 U
EE7 30'-GW	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	340.00 U
EE8 10-30'	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	350.00 U
EE8 30'-GW	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	350.00 U
EE9 10-30'	360.00 U	1700.00 U	360.00 U	360.00 U	1700.00 U	360.00 U
EE9 30'-GW	350.00 U	1700.00 U	350.00 U	350.00 U	1700.00 U	360.00 U



LOCATION	2,4-DINITRO PHENOL	4-NITROPHENOL	DIBENZOFURAN	2,4-DINITRO TOLUENE	2,6-DINITRO TOLUENE	DIETHYL PHTHALATE	4-CHLORO- PHENYL/PHENYL ETHER	FLUORENE
EE1 10-30'	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE1 30'-GW	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE2 10-30'	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE2 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 10-30'	1700.00 U	1700.00 U	190.00 J	350.00 U	350.00 U	350.00 U	350.00 U	270.00 J
EE3 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE4 10-20'	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE4 20'-GW	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE5 10-20'	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE5 20'-GW	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE6 10-30'	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE6 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE7 10-30'	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE7 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE8 10-30'	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE8 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE9 10-30'	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE9 30'-GW	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U

LOCATION	4-NITROANILINE	4,6-DINITRO-2 METHYLPHENOL	N-NITROSODI PHENYLAMINE	4-BROMOPHENYL PHENYL ETHER	HEXACHLORO BENZENE	PENTACHLORO PHENOL	PHENANTHRENE	ANTHRACENE
EE1 10-30'	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U
EE1 30'-GW	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U
EE2 10-30'	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE2 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE3 10-30'	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	1300.00 J	200.00 J
EE3 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE4 10-20'	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U
EE4 20'-GW	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U
EE5 10-20'	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U
EE5 20'-GW	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U
EE6 10-30'	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U
EE6 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE7 10-30'	1700.00 U	1700.00 U	340.00 U	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U
EE7 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE8 10-30'	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE8 30'-GW	1700.00 U	1700.00 U	350.00 U	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U
EE9 10-30'	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U
EE9 30'-GW	1700.00 U	1700.00 U	360.00 U	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U

LOCATION	DI-N-BUTYL PHTHALATE	FLUORANTHENE	BENZIDINE	PYRENE	BUTYL BENZYL PHTHALATE	3,3'-DICHLORO BENZIDINE	BENZO(A) ANTHRACENE	BIS(2-ETHYL HEXYL)PHTHALATE
EE1 10-30'	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	680.00 U	340.00 U	340.00 U
EE1 30'-GW	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	680.00 U	340.00 U	340.00 U
EE2 10-30'	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	386.00 U
EE2 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	350.00 U
EE3 10-30'	2000.00 J	960.00 J	1700.00 U	1400.00 J	430.00 J	700.00 U	320.00 J	1400.00 U
EE3 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	390.00 U
EE4 10-20'	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	680.00 U	340.00 U	340.00 U
EE4 20'-GW	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	690.00 U	340.00 U	340.00 U
EE6 10-20'	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U	710.00 U	360.00 U	360.00 U
EE6 20'-GW	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	680.00 U	340.00 U	340.00 U
EE6 10-30'	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U	720.00 U	360.00 U	360.00 U
EE6 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	350.00 U
EE7 10-30'	340.00 U	340.00 U	1700.00 U	340.00 U	340.00 U	170.00 U	340.00 U	340.00 U
EE7 30'- GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	350.00 U
EE6 10-30'	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	350.00 U
EE6 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	350.00 U
EE9 10-30'	360.00 U	360.00 U	1700.00 U	360.00 U	360.00 U	720.00 U	360.00 U	360.00 U
EE9 30'-GW	350.00 U	350.00 U	1700.00 U	350.00 U	350.00 U	700.00 U	350.00 U	350.00 U

LOCATION	CHRYSENE	DI-N-OCTYL PHTHALATE	BENZO(B) FLUORANTHENE	BENZO(K) FLUORANTHENE	BENZO(A) PYRENE	INDENO(1,2,3-CD) PYRENE	DIBENZ(A,H) ANTHRACENE
EE1 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE1 30'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE2 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	450.00 R	350.00 U	350.00 U
EE2 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	365.00 R	350.00 U	350.00 U
EE3 10-30'	220.00 J	1900.00 J	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE3 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	150.00 J	350.00 U	350.00 U
EE4 10-20'	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE4 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE5 10-20'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE5 20'-GW	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U	340.00 U
EE6 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE6 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE7 10-30'	340.00 U	340.00 U	340.00 U	340.00 U	170.00 J	340.00 U	340.00 U
EE7 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	160.00 J	350.00 U	350.00 U
EE5 10-30'	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE5 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U
EE9 10-30'	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U	360.00 U
EE9 30'-GW	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U	350.00 U

LOCATION	BENZO(G,H,I) PERYLENE
-----	
EE1 10-30'	340.00 U
EE1 30'-GW	340.00 U
EE2 10-30'	350.00 U
EE2 30'-GW	350.00 U
EE3 10-30'	350.00 U
EE3 30'-GW	350.00 U
EE4 10-20'	340.00 U
EE4 20'-GW	340.00 U
EE6 10-20'	360.00 U
EE6 20'-GW	340.00 U
EE6 10-30'	360.00 U
EE6 30'-GW	350.00 U
EE7 10-30'	340.00 U
EE7 30'-GW	350.00 U
EE6 10-30'	350.00 U
EE8 30'-GW	350.00 U
EE9 10-30'	360.00 U
EE9 30'-GW	350.00 U

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF PESTICIDE AND PCB RESULTS  
FOR SUBSURFACE SEDIMENT SAMPLES COLLECTED JULY/AUGUST 1985  
ug/kg DRY WEIGHT

SAMPLE LOCATION	ALPHA-BHC	BETA-BHC	GAMMA-BHC (LINDANE)	HEPTACHLOR	ALDRIN	HEPTACHLOR EPOXIDE	ENDOSULFAN I	DIELDRIN	4,4'-DDE	DELTA-BHC
EE1 10-30'	2.00 U	6.50 R	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	2.00 U
EE1 30'-GW	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	2.00 U
EE2 10-30'	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	9.80 R	2.00 U	4.00 U	4.00 U	2.00 R
EE2 30'-GW	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	12.00 R	2.00 U	4.00 U	4.00 U	3.20 R
EE3 10-30'	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	8.00 U	8.00 U	4.00 U
EE3 30'-GW	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	5.00 R	11.00 R	4.00 U
EE4 10-20'	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	8.80 R	2.00 U	4.00 U	4.60 R	2.00 U
EE4 20'-GW	2.60 R	2.00 U	2.00 U	2.00 U	2.00 U	10.00 R	2.00 U	4.00 U	5.30 R	2.20 R
EES 10-20'	2.50 R	2.00 U	2.00 U	2.00 U	2.00 U	12.00 R	2.00 U	4.00 U	5.50 R	2.20 R
EES 20'-GW	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	5.10 R	2.00 U	4.00 U	4.00 U	2.00 U
EE6 10-30'	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	4.00 R
EE6 30'-GW	2.00 U	2.00 U	2.00 R	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	4.50 R
EE7 10-30'	2.00 U	100.00 R	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	5.50 R
EE7 30'-GW	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	2.00 U
EES 10-30'	2.00 U	7.20 R	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.00 U	4.00 U	2.00 U
EE8 30'-GW	2.00 U	24.00 R	2.00 U	9.00 R	2.00 U	6.50 R	2.00 U	4.00 U	4.00 U	3.90 R
EE9 10-30'	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	2.00 U	4.10 R	2.00 U	4.00 U	2.00 U
EE9 30'-GW	2.00 U	2.00 U	2.00 U	6.30 R	2.00 U	6.00 R	2.00 U	4.00 U	4.50 R	3.80 R

LOCATION	ENDRIN	ENDOSULFAN II	4,4'-DDD	ENDRIN ALDEHYDE	ENDOSULFAN SULFATE	4,4'-DDT	ENDRIN KETONE	METHOXY- CHLOR	CHLORDANE	TOXAPHENE
EE1 10-30'	6.50 R	4.00 U	4.00 U	4.00 U	4.00 U	13.00 R	4.00 U	20.00 U	40.00 U	500.00 U
EE1 30'-GW	4.90 R	4.00 U	4.00 U	4.00 U	4.00 U	9.90 R	4.00 U	20.00 U	40.00 U	500.00 U
EE2 10-30'	4.00 U	4.00 U	4.00 U	4.00 U	20.00 R	4.00 U	4.00 U	20.00 U	50.00 U	600.00 U
EE2 30'-GW	4.00 U	4.00 U	12.00 R	4.00 U	33.00 R	4.00 U	4.00 U	20.00 U	60.00 U	700.00 U
EE3 10-30'	8.00 U	8.00 U	8.00 U	8.00 U	130.00 R	8.00 U	8.00 U	75.00 R	40.00 U	80.00 U
EE3 30'-GW	8.00 U	18.00 U	8.00 U	20.00 R	79.00 R	32.00 R	8.00 U	40.00 U	40.00 U	80.00 U
EE4 10-20'	6.20 R	4.00 U	4.00 U	4.00 U	9.20 R	11.00 R	4.00 U	20.00 U	60.00 U	500.00 U
EE4 20'-GW	7.50 R	4.00 U	4.00 U	4.00 U	30.00 R	13.00 R	4.00 U	20.00 U	60.00 U	500.00 U
EE5 10-20'	7.50 R	4.00 U	4.00 U	4.00 U	4.00 U	18.00 R	4.00 U	20.00 U	70.00 U	600.00 U
EE8 20'-GW	8.40 R	12.00 R	4.00 U	4.00 U	20.00 R	11.00 R	4.00 U	20.00 U	60.00 U	500.00 U
EE6 10-30'	6.30 R	4.00 U	4.00 U	4.00 U	52.00 R	12.00 R	4.00 U	20.00 U	40.00 U	600.00 U
EE6 30'-GW	5.70 R	4.00 U	4.00 U	4.00 U	4.00 U	11.00 R	4.00 U	20.00 U	40.00 U	500.00 U
EE7 10-30'	4.00 U	4.00 U	5.10 R	4.00 U	36.00 R	8.40 R	4.00 U	20.00 U	40.00 U	400.00 U
EE7 30'-GW	5.00 R	4.00 U	4.00 U	4.00 U	47.00 R	12.00 R	4.00 U	20.00 U	40.00 U	500.00 U
EE8 10-30'	5.00 R	4.00 U	4.00 U	4.00 U	4.00 U	9.80 R	4.00 U	20.00 U	40.00 U	500.00 U
EE8 30'-GW	4.00 U	4.00 U	4.00 U	4.00 U	43.00 R	11.00 R	4.00 U	20.00 U	40.00 U	600.00 U
EE9 10-30'	5.40 U	4.00 U	4.00 U	4.00 U	69.00 R	15.00 R	4.00 U	20.00 U	40.00 U	800.00 U
EE9 30'-GW	6.80 R	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	4.00 U	20.00 U	40.00 U	500.00 U

LOCATION	AROCLOR- 1016	AROCLOR- 1221	AROCLOR- 1232	AROCLOR- 1242	AROCLOR- 1248	AROCLOR- 1254	AROCLOR- 1260
EE1 10-30'	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U
EE1 30'-GW	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U
EE2 10-30'	40.00 U	60.00 U	70.00 U	40.00 U	50.00 U	100.00 U	100.00 U
EE2 30'-GW	50.00 U	80.00 U	90.00 U	50.00 U	60.00 U	200.00 U	100.00 U
EE3 10-30'	40.00 U	40.00 U	40.00 U	3100.00 J	40.00 U	1400.00 J	80.00 U
EE3 30'-GW	40.00 U	40.00 U	40.00 U	140.00 R	40.00 U	80.00 U	80.00 U
EE4 10-20'	40.00 U	70.00 U	80.00 U	50.00 U	50.00 U	100.00 U	100.00 U
EE4 20'-GW	40.00 U	70.00 U	80.00 U	50.00 U	50.00 U	100.00 U	100.00 U
EE8 10-20'	60.00 U	90.00 U	100.00 U	60.00 U	60.00 U	200.00 U	100.00 U
EE8 20'-GW	50.00 U	70.00 U	80.00 U	40.00 U	50.00 U	100.00 U	100.00 U
EE6 10-30'	40.00 U	70.00 U	70.00 U	70.00 U	70.00 U	100.00 U	80.00 U
EE6 30'-GW	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U
EE7 10-30'	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U
EE7 30'-GW	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U
EE8 10-30'	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U
EE8 30'-GW	40.00 U	70.00 U	70.00 U	70.00 U	60.00 U	100.00 U	80.00 U
EE9 10-30'	40.00 U	70.00 U	70.00 U	70.00 U	70.00 U	100.00 U	80.00 U
EE9 30'-GW	40.00 U	70.00 U	70.00 U	60.00 U	60.00 U	100.00 U	80.00 U



RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF HERBICIDE RESULTS FOR SUBSURFACE SEDIMENT SAMPLES  
COLLECTED JULY/AUGUST 1985  
(ug/kg) DRY WEIGHT

<u>SAMPLE</u>	<u>PARAMETER</u>			
LOCATION	2,4-D	2,4,5-T	2,4,5-TP	MCPA
EE1 10-30 FT.	10U	5U	*	300U
EE1 30-GW	10U	5U	*	150U
EE2 10-30	25U	15U	15U	600U
EE2 30-GW	2U	1U	1U	40U
EE3 10-30	200U	100U	*	4700U
EE3 30-GW	320U	160U	*	200U
EE4 10-20	5U	3U	*	100U
EE4 20-GW	5U	3U	*	110U
EE5 10-20	5U	3U	*	110U
EE5 20-GW	10U	5U	*	200U
EE6 10-30	10U	5U	*	150U
EE6 30-GW	500U	250U	*	12000U
EE7 10-30	20U	10U	*	1100U
EE7 30-GW	10U	5U	*	500U
EE5 10-30	10U	5U	*	200U
EE8 30-GW	10U	5U	*	50U
EE9 10-30	50U	25U	*	1100U
EE9 30-GW	30U	15U	*	600U

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF TENTATIVELY IDENTIFIED BASE/NEUTRAL/ACID COMPOUNDS  
FOR SUBSURFACE SEDIMENT SAMPLES COLLECTED JULY/AUGUST 1985  
(ug/kg)

COMPOUND	SCAN	EE3 10-30'	EE3 20-GW	EES 10-30'	EE9 30-GW
UNKNOWN	315	4200 J			
DIMETHYL BENZENE ISOMER	343	1700 J			
DIMETHYL BENZENE ISOMER	376	1200 J			
UNKNOWN	413	4600 J			
1-ETHYL-2-METHYL BENZENE	471	860 J			
TRIMETHYL BENZENE	510	1300 J			
DECANE	524	1800 J			
P-PHOSPHORIC ACID,TRIBUTYL ESTER	1106	1700 J			
UNKNOWN	1317	5900 J			
UNKNOWN	1333	2000 J			
UNKNOWN	1391	4200 J			
UNKNOWN	1424	7700 J			
UNKNOWN HYDROCARBON	636	2900 J			
UNKNOWN	1436	5000 J			
UNKNOWN	1453	1800 J			
UNKNOWN	1491	9400 J			
UNKNOWN	1505	2300 J			
UNKNOWN	1520	2400 J			
UNKNOWN	1542	3000 J			
2-BUTOXY ETHANOL	400		520 J		
UNKNOWN	1310		260 J		
UNKNOWN	1421			200 J	
UNKNOWN	416				220 J

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF INORGANIC RESULTS FOR SOIL/SEDIMENT SAMPLES  
COLLECTED JULY/AUGUST 1985  
(mg/kg) DRY WEIGHT

LOCATION	ALUMINUM	ANTIMONY	ARSENIC	BARIUM	BERYLLIUM	CADMIUM	CALCIUM	CHROMIUM	COBALT	COPPER
EE1 10-30'	7315.00	6.00U	5.70	110.00	0.50	1.00U	12938.00	11.00	13.00	12.00
EE1 30-GW	6686.00	10.00	3.20U	101.00	0.50	1.00U	14123.00	10.00	13.00	11.00
EE2 10-30'	6888.00	6.00U	3.20U	97.00	0.50	1.00U	8862.00	10.00	11.00	11.00
EE2 30-GW	4728.00	8.00J	3.30U	81.00	0.40	1.00U	8247.00	7.00	11.00	11.00
EE3 10-30'	7692.00	7.00U	3.40U	114.00	0.30U	1.40	11516.00	28.00	11.00	19.00
EE3 30-GW	5346.00	6.00U	3.20U	92.00	0.30	1.00U	9899.00	7.00	13.00	12.00
EE4 10-20'	8810.00	8.00U	3.90U	119.00	0.60	1.20U	11785.00	12.00	14.00	12.00
EE4 20-GW	4831.00	6.00U	3.20U	88.00	0.30U	1.00U	9354.00	4.00	12.00	13.00
EES 10-20'	8934.00	7.00U	7.10	119.00	0.60	1.00U	15703.00	13.00	13.00	12.00
EES 20-GW	4671.00	6.00U	3.20U	79.00	0.40	1.00U	7616.00	6.00	11.00	10.00
EES 10-30'	8332.00	4.00J	3.20U	106.00	0.80U	2.00U	12054.00	12.00	13.00	12.00
EE6 30-GW	7457.00	7.00U	3.30U	104.00	0.60	1.30	10995.00	10.00	15.00	11.00
EE7 10-30'	8712.00	8.00J	3.30U	103.00	0.50	1.00U	13000.00	12.00	13.00	17.00
EE7 30-GW	6140.00	6.00U	3.30U	112.00	0.30	1.00U	11285.00	8.00	11.00	14.00
EE8 10-30'	7046.00	6.00U	3.30U	104.00	0.50	1.00U	11053.00	12.00	12.00	10.00
EE8 30-GW	6215.00	6.00U	3.30U	99.00	0.50	1.10	10414.00	9.00	13.00	12.00
EE9 10-30'	7087.00	7.00U	3.30U	652.00	0.50	1.00U	10603.00	11.00	12.00	12.00
EE9 30-GW	5785.00	6.00U	3.30U	111.00	0.40	1.00U	10081.00	8.00	13.00	11.00

LOCATION	IRON	LEAD	MAGNESIUM	MANGANESE	MERCURY	NICKEL	POTASSIUM	SELENIUM	SILVER	SODIUM
EE1 10-30'	22753.00	5.70	6962.00	439.00	0.10U	5.00U	2551.00	1.80U	2.50	539.00
EE1 30-GW	23483.00	4.50	6210.00	377.00	0.10U	5.00U	2465.00	1.80U	3.20	535.00
EE2 10-30'	20000.00	5.90	5846.00	411.00	0.10U	9.00U	2610.00	1.90U	2.60	522.00
EE2 30-GW	21334.00	3.20	4549.00	345.00	0.10U	9.00U	1508.00	1.90U	2.30	592.00
EE3 10-30'	22319.00	100.00	6308.00	407.00	0.20	9.00U	2491.00	1.90U	1.50	647.00
EE3 30-GW	23074.00	6.20	4753.00	399.00	0.10U	9.00	1935.00	1.80U	1.90U	580.00
EE4 10-20'	27462.00	5.80	6943.00	485.00	0.10U	10.00U	2942.00	2.20U	2.70	665.00
EE4 20-GW	21375.00	3.60	4524.00	375.00	0.10U	8.00U	1711.00	9.00U	1.70U	528.00
EE5 10-20'	24879.00	8.10	8363.00	486.00	0.10U	14.00	2929.00	1.90U	2.80	725.00
EE5 20-GW	21489.00	2.90	4523.00	313.00	0.10U	5.00U	1888.00	1.50U	2.60	591.00
EE6 10-30'	24587.00	6.30	7076.00	447.00	0.20U	9.00	2523.00	4.00U	1.90	835.00
EE6 30-GW	26310.00	4.30	6043.00	447.00	0.10U	9.00U	2507.00	1.90U	3.40	669.00
EE7 10-30'	25832.00	9.70	7223.00	457.00	0.10U	11.00	2683.00	9.50U	2.50	726.00
EE7 10-GW	20780.00	3.80	5769.00	455.00	0.10U	9.00U	2515.00	1.90U	1.90	605.00
EE5 10-30'	20929.00	5.20	6165.00	398.00	0.10U	9.00U	2740.00	1.90U	3.50	562.00
EE5 30-GW	23027.00	4.50	5876.00	422.00	0.10U	9.00U	2225.00	1.90U	2.80	555.00
EE9 10-30'	21375.00	4.70	6283.00	390.00	0.60	9.00U	2761.00	1.90U	3.30	1406.00
EE9 30-GW	22263.00	4.40	5543.00	378.00	0.20	9.00U	2191.00	1.90U	2.20	605.00

LOCATION	THALLIUM	TIN	VANADIUM	ZINC	CYANIDE
EE1 10-30'	2.00 U	9.00 U	43.10	54.00	*
EE1 30-GW	2.00 U	10.00 U	47.00	50.00	*
EE2 10-30'	2.00 U	10.00 U	38.90	53.00	*
EE2 30-GW	2.00 U	10.00 U	40.50	43.00	*
EE3 10-30'	2.00 U	10.00 U	40.00	76.00	*
EE3 30-GW	2.00 U	10.00 U	45.00	45.00	*
EE4 10-20'	3.00 U	11.00 U	61.30	58.00	*
EE4 20-GW	2.00 U	9.00 U	42.30	42.00	*
EE6 10-20'	2.00 U	10.00 U	45.90	59.00	*
EE6 20-GW	2.00 U	9.00 U	41.80	40.00	*
EE6 10-30'	5.00 U	10.00 U	48.80	68.00	*
EE6 30-GW	2.00 U	10.00 U	56.80	56.00	*
EE7 10-30'	2.00 U	10.00 U	49.30	218.00	*
EE7 30-GW	2.00 U	10.00 U	35.70	59.00	*
EE6 10-30'	2.00 U	10.00 U	42.40	49.00	*
EE6 30-GW	2.00 U	10.00 U	46.00	47.00	*
EE9 10-30'	2.00 U	10.00 U	43.60	49.00	*
EE9 30-GW	2.00 U	10.00 U	43.90	47.00	*

APPENDIX G

GROUND WATER ANALYTICAL RESULTS

Explanation of data modifiers:

U: undetected at specified level

J: estimated concentration only

R: value rejected during Quality Assurance review

\*: not analyzed for

SCAN: Relative Retention Time Indicator

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF VOLATILE ORGANIC COMPOUND RESULTS  
FOR GROUNDWATER SAMPLES COLLECTED JULY/AUGUST 1985  
(ug/l)

LOCATION	CHLOROMETHANE	BROMOMETHANE	VINYL CHLORIDE	CHLOROETHANE	METHYLENE CHLORIDE	ACETONE	CARBON DISULFIDE	1,1-DICHLORO ETHANE	1,1-DICHLORO ETHANE
EE1	50.00 U	50.00 U	50.00 U	50.00 U	15.00 U	765.00	25.00 U	25.00 U	25.00 U
EE2	10.00 U	10.00 U	10.00 U	10.00 U	2.00 U	84.00 U	5.00 U	5.00	15.00
EE3	100.00 U	100.00 U	100.00 U	100.00 U	60.00 U	350.00	50.00 U	50.00 U	64.00
EE4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	330.00	5.00 U	5.00 U	5.00 U
EES	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	3.60 J	5.00 U	5.00 U	5.00 U
EES	100.00 U	100.00 U	100.00 U	100.00 U	40.00	710.00	50.00 U	50.00 U	50.00 U
EE7	200.00 U	200.00 U	200.00 U	200.00 U	72.00	10400.00 U	100.00 U	100.00 U	100.00 U
EE8	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	10.00 U	5.00 U	5.00 U	5.00 U
EE9	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	10.00 U	5.00 U	5.00 U	5.00 U
JUB CNTR	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	354.00	5.00 U	5.00 U	5.00 U
JUB 1	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	47.00	5.00 U	5.00 U	5.00 U
JUB 2	10.00 U	10.00 U	10.00 U	10.00 U	1.00 U	48.00	5.00 U	13.00	35.00
JUB 3	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	1.30 J	5.00 U	5.00 U	5.00 U
JUB 4	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	4.80 J	5.00 U	5.00 U	5.00 U
WSW	10.00 U	10.00 U	10.00 U	10.00 U	5.00 U	4.40 J	5.00 U	5.00 U	5.00 U



LOCATION	TRANS-1,2-DI CHLOROETHENE	CHLOROFORM	1,2-DICHLORO ETHANE	2-BUTANONE	1,1,1-TRI CHLOROETHANE	CARBON TETRA CHLORIDE	VINYL ACETATE	BROMODICHLORO METHANE	1,1,2,2-TETRA CHLOROETHANE
EE1	25.00 U	25.00 U	25.00 U	50.00 U	25.00 U	25.00 U	50.00 U	25.00 U	25.00 U
EE2	9.00	3.00	5.00 U	10.00 U	70.00	5.00 U	10.00 U	5.00 U	5.00 U
EE3	50.00 U	50.00 U	50.00 U	100.00 U	420.00	50.00 U	100.00 U	50.00 U	50.00 U
EE4	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
EE5	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
EE5	50.00 U	50.00 U	50.00 U	100.00 U	50.00 U	50.00 U	100.00 U	50.00 U	50.00 U
EE7	100.00 U	100.00 U	100.00 U	200.00 U	100.00 U	100.00 U	200.00 U	100.00 U	100.00 U
EE5	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
EE9	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
JUB CNTR	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
JUB 1	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
JUB 2	15.00	17.00	4.60 J	10.00 U	168.00	5.00 U	10.00 U	5.00 U	5.00 U
JUB 3	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
JUB 4	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U
WSW	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U	10.00 U	5.00 U	5.00 U

LOCATION	1,2-DICHLORO PROPANE	TRANS-1,3-DI CHLOROPROPENE	TRICHLORO ETHENE	DIBROMOCHLORO METHANE	1,1,2-TRI CHLOROETHANE	BENZENE	CIS-1,3-DI CHLOROPROPENE	2-CHLOROETHYL VINYL ETHER	BROMOFORM
EE1	25.00 U	25.00 U	25.00 U	25.00 U	25.00 U	25.00 U	25.00 U	50.00 U	25.00 U
EE2	5.00 U	5.00 U	65.00	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
EE3	50.00 U	50.00 U	480.00	50.00 U	50.00 U	50.00 U	50.00 U	100.00 U	50.00 U
EE4	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
EE5	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
EES	50.00 U	50.00 U	50.00 U	50.00 U	50.00 U	50.00 U	50.00 U	100.00 U	50.00 U
EE7	100.00 U	100.00 U	100.00 U	100.00 U	100.00 U	100.00 U	100.00 U	200.00 U	100.00 U
EE8	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
EE9	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
JUB CNTR	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
JUB 1	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
JUB 2	5.00 U	5.00 U	164.00	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
JUB 3	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
JUB 4	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U
WSW	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	10.00 U	5.00 U

LOCATION	2-HEXANONE	4-METHYL- 2-PENTANONE	TETRACHLORO ETHYLENE	TOLUENE	CHLOROBENZENE	ETHYL BENZENE	STYRENE	TOTAL XYLENES
EE1	50.00 U	50.00 U	25.00 U	25.00 U	25.00 U	25.00 U	25.00 U	25.00 U
EE2	10.00 U	10.00 U	32.00	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
EE3	100.00 U	100.00 U	50.00 U	230.00	50.00 U	50.00 U	50.00 U	63.00
EE4	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
EES	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
EE6	100.00 U	100.00 U	50.00 U	50.00 U	50.00 U	50.00 U	50.00 U	50.00 U
EE7	200.00 U	200.00 U	100.00 U	100.00 U	100.00 U	100.00 U	100.00 U	100.00 U
EE8	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
EE9	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
JUB CNTR	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
JUB 1	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
JUB 2	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
JUB 3	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
JUB 4	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U
WSW	10.00 U	10.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U	5.00 U

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF BASE/NEUTRAL/ACID COMPOUND RESULTS  
FOR GROUNDWATER SAMPLES COLLECTED JULY/AUGUST 1985  
(ug/l)

LOCATION	N-NITROSO DIMETHYLAMINE	PHENOL	ANILINE	BIS(2-CHLORO ETHYL)ETHER	2-CHLOROPHENOL	1,3-DICHLORO BENZENE	1,4-DICHLORO BENZENE	BENZYL ALCOHOL
EE1	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE2	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE3	20.00 U	20.00 R	20.00 U	20.00 U	20.00 R	20.00 U	20.00 U	20.00 U
EE4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EES	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE6	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE7	24.00 R	24.00 U	24.00 R	24.00 R	24.00 U	24.00 R	24.00 R	24.00 R
EE8	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE9	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
JUB CNTR	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB1	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB2	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB3	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
WSW	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U

LOCATION	1,2-DICHLORO BENZENE	2-METHYLPHENOL	BIS(2CHLOROISO PROPYL)ETHER	4-METHYL PHENOL	N-NITROSO DIPROPYLAMINE	HEXACHLORO ETHANE	NITROBENZENE	ISOPHORONE
EE1	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE2	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE3	20.00 U	20.00 R	20.00 U	6.00 J	10.00 U	10.00 U	10.00 U	10.00 U
EE4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EES	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EES	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE7	24.00 R	24.00 U	24.00 R	24.00 U	24.00 R	24.00 R	24.00 R	24.00 R
EE8	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE9	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
JUB CNTR	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB1	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB2	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB3	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
WSW	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U

LOCATION	2-NITROPHENOL	2,4-DIMETHYL PHENOL	BENZOIC ACID	BIS(2-CHLORO ETHOXY)METHANE	2,4-DICHLORO PHENOL	1,2,4-TRI CHLOROBENZENE	NAPHTHALENE	4-CHLORO ANILINE
EE1	20.00 U	20.00 U	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE2	20.00 U	20.00 U	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE3	10.00 R	10.00 R	100.00 R	20.00 U	20.00 R	20.00 U	20.00 U	20.00 U
EE4	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE5	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE5	20.00 U	20.00 U	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE7	24.00 U	24.00 U	118.00 U	24.00 R	24.00 U	24.00 R	24.00 R	24.00 R
EE8	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE9	20.00 U	20.00 U	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
JUB CNTR	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 1	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 2	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 3	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 4	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
WSW	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U

LOCATION	HEXACHLORO BUTADIENE	4-CHLORO- 3-METHYLPHENOL	2-METHYL NAPHTHALENE	HEXACHLOROXY CLOPENTADIENE	2,4,6-TRI CHLOROPHENOL	2,4,5-TRI CHLOROPHENOL
EE1	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
EE2	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
EE3	20.00 U	20.00 R	20.00 U	20.00 U	20.00 R	100.00 R
EE4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
EE5	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
EE6	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
EE7	24.00 R	24.00 U	24.00 R	24.00 R	24.00 U	118.00 U
EE8	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
EE9	20.00 U	20.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB CNTR	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 1	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 2	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 3	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
WSW	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U

LOCATION	2-CHLORO NAPHTHALENE	2-NITROANILINE	DIMETHYL PHTHALATE	ACENAPHTHYLENE	3-NITROANILINE	ACENAPHTHENE	2,4-DINITRO PHENOL
EE1	20.00 U	100.00 U	20.00 U	20.00 U	100.00 U	20.00 U	100.00 U
EE2	20.00 U	100.00 U	20.00 U	20.00 U	100.00 U	20.00 U	100.00 U
EE3	20.00 U	100.00 U	20.00 U	20.00 U	100.00 U	20.00 U	100.00 R
EE4	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
EE5	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
EE5	20.00 U	100.00 U	20.00 U	20.00 U	100.00 U	20.00 U	100.00 U
EE7	24.00 R	118.00 R	24.00 R	24.00 R	118.00 R	24.00 R	59.00 U
EE8	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
EE9	10.00 U	50.00 U	10.00 U	10.00 U	100.00 U	20.00 U	100.00 U
JUB CNTR	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
JUB 1	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
JUB 2	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
JUB 3	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
JUB 4	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U
WSW	10.00 U	50.00 U	10.00 U	10.00 U	50.00 U	10.00 U	50.00 U



LOCATION	4-NITROPHENOL	DIBENZOFURAN	2,4-DINITRO TOLUENE	2,6-DINITRO TOLUENE	DIETHYL PHTHALATE	4-CHLOROPHENYL PHENYL ETHER	FLUORENE	4-NITROANILINE
EE1	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
EE2	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
EE3	100.00 R	20.00 U	20.00 R	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
EE4	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
EE5	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
EE6	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	100.00 U
EE7	59.00 U	24.00 R	24.00 R	24.00 R	24.00 R	24.00 R	24.00 R	118.00 R
EE8	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
EE9	100.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	100.00 U
JUB CNTR	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 1	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 2	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 3	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
JUB 4	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U
WSW	50.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	50.00 U

LOCATION	4,6-DINITRO-2 METHYLPHENOL	N-NITROSODI PHENYLAMINE	4-BROMOPHENYL PHENYL ETHER	HEXACHLORO BENZENE	PENTACHLORO PHENOL	PHENANTHRENE	ANTHRACENE	DI-N-BUTYL PHTHALATE
EE1	100.00 U	20.00 U	20.00 U	20.00 U	118.00 U	20.00 U	20.00 U	20.00 U
EE2	100.00 U	20.00 U	20.00 U	20.00 U	100.00 U	20.00 U	20.00 U	20.00 U
EE3	100.00 R	20.00 U	20.00 U	20.00 U	20.00 R	20.00 U	20.00 U	20.00 U
EE4	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
EE5	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
EE5	100.00 U	20.00 U	10.00 U	10.00 U	100.00 U	10.00 U	20.00 U	20.00 U
EE7	118.00 R	24.00 R	24.00 R	24.00 R	118.00 U	24.00 R	24.00 R	24.00 R
EE5	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
EE9	100.00 U	20.00 U	20.00 U	20.00 U	50.00 U	20.00 U	20.00 U	20.00 U
JUB CNTR	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
JUB 1	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
JUB 2	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
JUB 3	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
JUB 4	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U
WSW	50.00 U	10.00 U	10.00 U	10.00 U	50.00 U	10.00 U	10.00 U	10.00 U

LOCATION	FLUORANTHENE	BENZIDINE	PYRENE	BUTYL BENZYL PHTHALATE	3,3'-DICHLORO BENZIDINE	BENZO(A) ANTHRACENE	BIS(2-ETHYL HEXYL)PHTHALATE	CHRYSENE	DI-N-OCTYL PHTHALATE
EE1	20.00 U	160.00 U	20.00 U	20.00 U	40.00 U	20.00 U	44.00 U	20.00 U	10.00 U
EE2	20.00 U	160.00 U	20.00 U	20.00 U	40.00 U	20.00 U	6.00 J	20.00 U	20.00 U
EE3	20.00 U	160.00 U	20.00 U	20.00 U	40.00 U	20.00 U	10.00 U	20.00 U	20.00 U
EE4	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	39.00	10.00 U	10.00 U
EES	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	7.80 J	10.00 U	10.00 U
EE6	20.00 U	100.00 U	10.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	6.00 U
EE7	24.00 R	118.00 R	24.00 R	24.00 R	48.00 R	24.00 R	18.00 U	24.00 R	24.00 R
EE8	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE9	20.00 U	160.00 U	20.00 U	20.00 U	40.00 U	20.00 U	40.00 U	20.00 U	12.00 U
JUB CNTR	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 1	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 2	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 3	10.00 U	50.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 4	10.00 U	100.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U
WSW	10.00 U	100.00 U	10.00 U	10.00 U	20.00 U	10.00 U	10.00 U	10.00 U	10.00 U

LOCATION	BENZO(B) FLUORANTHENE	BENZO(K) FLUORANTHENE	BENZO(A)PYRENE	INDENO(1,2,3- CO)PYRENE	DIBENZ(A,H) ANTHRACENE	BENZO(G,H,I) PERYLENE
EE1	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE2	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE3	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE5	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE6	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
EE7	24.00 R	24.00 R	24.00 R	24.00 R	24.00 R	24.00 R
EE8	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
EE9	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U	20.00 U
JUB CNTR	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 1	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 2	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 3	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
JUB 4	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U
WSW	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U	10.00 U

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF PESTICIDE AND PCB/RESULTS FOR  
GROUNDWATER SAMPLES COLLECTED JULY/AUGUST 1985  
(ug/l)

LOCATION	ALPHA-BHC	BETA-BHC	DELTA-BHC	GAMMA-BHC (LINDANE)	HEPTACHLOR	ALDRIN	HEPTACHLOR EPOXIDE	ENDOSULFAN I	DIELDRIN	4,4'-DDE
EE1	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EE2	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EE3	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EE4	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EES	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EES	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EE7	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
EES	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.11 U	0.11 U
EE9	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.06 U	0.11 U	0.11 U
JUB CNTR	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
JUB 1	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
JUB 2	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
JUB 3	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
JUB 4	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U
WSW	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.05 U	0.10 U	0.10 U

LOCATION	ENDRIN	ENDOSULFAN II	4,4'-DDD	ENDRIN ALDEHYDE	ENDOSULFAN SULFATE	4,4'-DDT	ENDRIN KETONE	METHOXY- CHLOR	CHORDANE	TOXAPHENE
EE1	0.10 U	0.10 U	0.10 UJ	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EE2	0.10 UJ	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EE3	0.10 UJ	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EE4	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EES	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EES	0.10 UJ	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EE7	0.10 UJ	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
EE8	0.11 UJ	0.11 U	0.11 U	0.11 U	0.11 U	0.11 U	0.11 U	0.60 U	0.60 U	1.10 U
EE9	0.11 UJ	0.11 U	0.11 U	0.11 U	0.11 U	0.11 U	0.11 U	0.60 U	0.60 U	1.10 U
JUB CNTR	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
JUB 1	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
JUB 2	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
JUB 3	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
JUB 4	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U
WSW	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.50 U	0.50 U	1.00 U

LOCATION	AROCLOR- 1016	AROCLOR- 1221	AROCLOR- 1232	AROCLOR- 1242	AROCLOR- 1248	AROCLOR- 1254	AROCLOR- 1260
EE1	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U
EE2	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U
EE3	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U
EE4	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	0.50 U
EE5	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	0.50 U
EE6	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U
EE7	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U
EE8	0.60 U	0.60 U	0.60 U	0.60 U	0.60 U	1.10 U	1.10 U
EE9	0.60 U	0.60 U	0.60 U	0.60 U	0.60 U	1.10 U	0.60 U
JUB CNTR	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	0.50 U
JUB 1	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U
JUB 2	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	0.50 U
JUB 3	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	0.50 U
JUB 4	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	0.50 U
WSW	0.50 U	0.50 U	0.50 U	0.50 U	0.50 U	1.00 U	1.00 U

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF HERBICIDE RESULTS FOR GROUNDWATER SAMPLES  
COLLECTED JULY/AUGUST 1985  
(ug/l)

<u>SAMPLE</u>		<u>PARAMETER</u>			
LOCATION		2,4-D	2,4,5-T	2,4,5-TP	MCPA
	EE1	1U	1U	*	2U
	EE2	1U	1U	1U	2U
	EE3	1U	1U	1U	2U
	EE4	1U	1U	*	2U
	EES	1U	1U	*	2U
	EES	1U	1U	*	2U
	EE7	1U	1U	*	2U
	EE8	1U	1U	*	2U
	EE9	1U	1U	*	2U
JUB	CONTROL	1U	1U	1U	2U
	JUB 1	1U	1U	1U	2U
	JUB 2	1U	1U	1U	2U
	JUB 3	1U	1U	1U	2U
	JUB 4	1U	1U	1U	1U
	WSW	1U	1U	1U	2U



RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF TENTATIVELY IDENTIFIED BASE/NEUTRAL/ACID COMPOUNDS FOR  
GROUNDWATER SAMPLES COLLECTED JULY/AUGUST 1985  
(ug/l)

LOCATION:		EE1	EE2	EE3	EE4	EE8	EE8	EE7	EE8	EE9	JUB CNTR	JUB1	JUB2	JUB3	JUB4	WSW
COMPOUND	SCAN															
ALCOHOL	431	190J														
ALCOHOL	518	20J														
ALKENE	663	600J	16J				62J									
HYDROCARBON	704	22J														
CARBOXYLIC ACID	914	12J														
CARBOXYLIC ACID	954	94J														
UNK.	2078	26J	8J	4J		15J	68J	12J								
SATURATED HYDROCARBON	965		22J													
UNK.	1812		6J													
DIMETHYL BENZENE	406			696J												
DIMETHYL BENZENE	445			364J												
ALKYL BENZENE	499			12J												
SUBSTITUTED BENZENE	546			26J												
ALKYL BENZENE	559			120J												
TRIMETHYL BENZENE	569			42J												
METHYL KETONE	576			6J												
ALKYL BENZENE	586			40J												
ALKYL BENZENE	606			84J												
ALKYL BENZENE	648			20J												
ALKYL BENZENE	665			6J												

SUMMARY OF TENTATIVELY IDENTIFIED BASE/NEUTRAL/ACID COMPOUNDS (CONT.)

LOCATION:		EE1	EE2	EE3	EE4	EES	EES	EE7	EES	EE9	JUB CNTR	JUB1	JUB2	JUB3	JUB4	WSW
COMPOUND	SCAN															
SUBSTITUTED ALKANE	670			16J												
SUBSTITUTED ALKANE	879			SJ												
KETONE	934			16J												
KETONE	960						160J									
UNK.	1487						12J									
SUBST. CARBOXYLIC ACID	964							ISSJ								
UNKNOWN	1563								14J							
UNKNOWN	2036								SJ							
PHTHALATE	2150								SJ							
UNKNOWN	1166									ISJ						
UNKNOWN	1323									SJ						
UNKNOWN	2035									4J						
UNKNOWN	394				6.7J											
HYDROCARBON	232				11J											
UNKNOWN	1183				27J											
HEXADECANOIC ACID	1502				ISJ											
UNKNOWN	1635				22J											
UNKNOWN	1638				2SJ											
CARBOXYLIC ACID	1654										7.6J	6.2J		4.SJ	5.6J	
C-3 SUBST. BENZENE	468											6.2J		4.SJ	7.2J	
C-2 SUBST. BENZENE	343												13J			

RESOURCE RECOVERY CORP., PASCO, WA.  
SUMMARY OF INORGANIC RESULTS FOR GROUND WATER SAMPLES COLLECTED  
JULY/AUGUST 1985  
(ug/l)

LOCATION	ALUMINUM	ANTIMONY	ARSENIC	BARIUM	BERYLLIUM	CADMIUM	CALCIUM	CHROMIUM	COBALT	COPPER
EE1 BKGRD.	2413.00	12.00 U	10.00 U	103.00	0.50 U	1.90 U	57990.00	24.00	3.90 U	10.00
EE2	70420.00	19.00 J	10.00 U	1929.00	4.50	2.30	190000.00	134.00	102.00	191.00
EE3	8983.00	12.00 U	10.00 U	297.00	0.50 U	1.90 U	101500.00	48.00	15.00	22.00
EE4	4846.00	12.00 U	10.00 U	154.00	1.20	3.50	65940.00	16.00	5.00	13.00
EES	51330.00	12.00 U	10.00 U	2148.00	4.30	2.90	145500.00	83.00	70.00	118.00
EE6	22560.00	16.00 J	10.00 U	400.00	1.10	2.70	70920.00	51.00	32.00	82.00
EE7	9291.00	12.00 U	10.00 U	235.00	0.50 U	1.90 U	65910.00	62.00	12.00	40.00
EE8	18320.00	12.00 U	10.00 U	526.00	2.10	1.90 U	80770.00	62.00	25.00	45.00
EE9	26390.00	12.00 U	11.40 J	773.00	2.70	1.90 U	94780.00	72.00	38.00	62.00
JUB WELL 1	37210.00	12.00 U	10.00 U	896.00	3.10	2.80	101100.00	60.00	67.00	103.00
JUB WELL 2	46670.00	12.00 U	12.00	834.00	3.60	1.90 U	116100.00	71.00	87.00	109.00
JUB WELL 3	17030.00	12.00 U	10.00 U	350.00	1.70	1.90 U	77740.00	31.00	23.00	33.00
JUB WELL 4	40180.00	12.00 U	40.00	838.00	3.00	1.90 U	100700.00	51.00	44.00	77.00
JUB CNTR.	129800.00	12.00 U	37.20	1656.00	10.40	1.90 U	332200.00	176.00	184.00	254.00
WSW	61.00	12.00 U	10.00 U	63.00	0.60	1.90 U	57180.00	11.00	3.90 U	1.70

LOCATION	IRON	LEAD	MAGNESIUM	MANGANESE	MERCURY	NICKEL	POTASSIUM	SELENIUM	SILVER	SODIUM
EE1 BKGRO.	4349.00	5.00 R	21880.00	147.00	0.18 U	24.00	8561.00	25.00 U	3.30 U	35780.00
EE2	167600.00	36.20 R	64500.00	3631.00	0.20	131.00	20700.00	25.00 U	7.80	47580.00
EE3	27090.00	5.90 R	27570.00	2698.00	0.18 U	21.00	11690.00	25.00 U	3.30 U	31920.00
EE4	10630.00	10.50	21330.00	244.00	0.40 U	19.00	7563.00	25.00 U	4.00	32540.00
EES	123700.00	17.90	49050.00	2736.00	0.20 U	80.00	13800.00	25.00 U	7.60	37270.00
EES	52150.00	29.10 R	29930.00	1488.00	0.18 U	50.00	9989.00	25.00 U	3.30 U	36130.00
EE7	21750.00	17.90 R	24040.00	709.00	0.18 U	46.00	8855.00	25.00 U	3.30 U	35220.00
EES	39950.00	84.00 R	29600.00	887.00	0.18 U	46.00	9272.00	25.00 U	6.40	34140.00
EE9	61640.00	33.60 R	31280.00	1264.00	0.30	78.00	12880.00	25.00 U	6.80	32670.00
JUB WELL 1	89890.00	70.00	38990.00	2695.00	0.60	61.00	12410.00 J	25.00 U	9.80	35960.00
JUB WELL 2	105400.00	56.00	41490.00	2232.00	0.20	50.00	13420.00 J	25.00 U	11.10	39370.00
JUB WELL 3	41430.00	13.20	29140.00	733.00	0.60	16.00 U	9598.00 J	25.00 U	8.00	35140.00
JUB WELL 4	95460.00	15.30	39840.00	1394.00	0.20	23.00	12290.00 J	25.00 U	9.30	36120.00
JUB CNTR.	268300.00	180.00	99060.00	5281.00	1.00	138.00	26000.00 J	25.00 U	19.10	41800.00
WSW	24.00	5.00	20600.00	3.00	0.18 U	16.00 U	7315.00 J	5.00 U	5.60	33440.00

LOCATION	THALLIUM	TIN	VANADIUM	ZINC	CYANIDE
EE1 BKGRD.	10.00 U	18.00 U	15.90 J	289.00	*
EE2	10.00 U	18.00 U	281.90 J	443.00	*
EE3	10.00 U	18.00 U	46.40 J	75.00	*
EE4	10.00 U	18.00 U	38.70	142.00	*
EE8	10.00 U	18.00 U	191.80	336.00	*
EE8	10.00 U	18.00 U	111.30 J	297.00	*
EE7	10.00 U	18.00 U	53.80 J	346.00	*
EE8	10.00 U	18.00 U	89.40 J	160.00	*
EE9	10.00 U	18.00 U	116.00 J	439.00	*
JUB WELL 1	10.00 U	18.00 U	164.50	262.00	*
JUB WELL 2	10.00 U	88.00	195.80	354.00	*
JUB WELL 3	10.00 U	18.00 U	79.40	132.00	*
JUB WELL 4	10.00 U	52.00	150.00	211.00	*
JUB CNTR.	10.00 U	18.00 U	493.70	673.00	*
WSW	10.00 U	21.00	23.50	8.00	*

---

# **Uncontrolled Hazardous Waste Site Ranking System**

## **A Users Manual** (HW-10)

Originally Published in  
the July 16, 1982, *Federal Register*

02

United States  
Environmental Protection  
Agency

1984

### REFERENCE 3



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

RECEIVED

DEPARTMENT OF ECOLOGY  
SPokane RECEPTION OFFICE

RANCH OFFICE:  
O. Box 650  
Pasco, Washington 99301

July 2, 1980

Department of Ecology  
E. 103 Indiana  
Spokane, WA. 99207

*File  
Franklin Co  
Resource Recovery  
Land fill  
J2M*

Dear Sirs:

Attached is a breakdown of industrial waste materials brought into the Pasco landfill during the years 1972, 1973, and 1974. Their location in the site is indicated by reference to the survey map prepared by A.D. Stanley & Associates Inc. dated 6/5/80.

Sincerely,

*John R. Kimberly, Jr.*  
John R. Kimberly, Jr.  
President

*Memo for File*

*9-10-80*

*checked recording info. with Auditor  
and it is correct:*

*J2M*



Drums

1972

1973

1974

Site

Paint Waste *SLU*

6314

9195

8691

A

Caustic Wastes *BASE*

959

3277

4538

A

Acid Wastes *ACID*

85

459

---

A

2-4 D mfg. Waste *SLU*

588

4492

---

B

Carcenogenics

---

9

---

A

Pesticide Containers *PSD*

---

863

---

A

Aromatic Tar *OCC*

---

160

---

A

Oil Sludge

---

---

433

A

Cedimum Waste

---

11

---

A

Pesticides *PSD*

---

425

---

A

Metal Finishing *MES*

---

---

304

A

Gallons

1972

1973

1974

Site

Waste Cutting Oil *DLW*

3000

28500

52800

D

Lime Phenol Waste *SOL*

---

217724

467243

C

Metal Cleaning Waste *MES*

---

3703

138938

46224

C

Paint Waste *SLU*

---

6005

60511

D

Acids *ACD*

---

6000

1000

C

Solvents *SOL*

---

12648

---

D

Oily Sludges *SLU*

---

11000

55340

D

Metal Finishing *MES*

---

34017000

---

C

Pounds

1972

1973

1974

Site

Acid metal Cleaning *ACD*

---

490810

1810750

C

Plywood Resin Wastes *SLU*

---

212520

2002920

D

Paint Wastes *SLU*

---

27200

420218

D

Barium Waste with mercury *SLU*

---

5439 tons

6143 tons

E

Fertilizer Mfg. Waste *SLU*

---

---

228288

D

Aromatic Tar *OCC*

---

---

499270

D

Metal Finishing *MES*

---

3652

1460602

C

442 4153

17881  
57910

**REFERENCE 4**

Table I

RESOURCE RECOVERY INC.  
Pasco Facility  
Inventory  
as of  
October 19, 1973

<u>Location</u> (See Map)	<u>Description</u>	<u>Amount</u>
1	For disposal of containerized wastes such as:  Paint wastes (sludge, pigments, resins, colors) Empty pesticide containers Wood treatment wastes Etching solutions Metal casting wastes	  10,258 drums 800 drums 1,100 drums 160 drums 3,300 drums
	All wastes are in containers and buried under 5 feet of soil. There have been no known liquid discharges from this location.	
2	An unlined pond for evaporation of water from simple wastes such as:  Lime sludge and ammonia water	  327,000 gal.
3	A lined pond for evaporation of water from chrome plating wastes	8,790 gal.
4	A lined pond for evaporation of water from miscellaneous liquids - not yet used to any extent	
5	A roughed out pond for later use. Being used as temporary storage for chlor-alkali sludge pending preparation of trenches 10, 11, and 12.	
6	For disposal of containerized herbicide wastes such as:  2,4-D tar MCPA Bleed other miscellaneous	  2,011 drums 3,037 drums 435 drums
	The drums are covered with 5 feet of soil. There have been no known discharges from this location.	
7	The currently active landfill operation.	
8, 9	Unlined trenches for temporary disposal of chlor-alkali sludge. The sludge will be moved to lined trenches 10, 11, and 12.	
10, 11, 12	Proposed site for disposal of chlor-alkali sludges. The lined trenches will be constructed as outlined in Figure 2.	
13, 14,	Space for future landfill operations.	

## REFERENCE 5



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

January 17, 1975

Mr. John Arnquist  
Professional Engineer  
East 103 Indiana Avenue  
Spokane, WA 99027

RECEIVED  
JAN 20 1975  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Dear Mr. Arnquist:

The activity at the Pasco landfill site during the month of December, 1974 was as follows:

Paint Waste	59,058 Pounds
Fertilizer Mfg. Waste	70,220 "
Metal Finishing Waste	633,892 "
Plywood Resin Waste	218,060 "
Resin Mfg. Waste	112,500 Gallons
Cutting Oil Waste	3,000 "
Bilge Cleanings	1,000 "
Paint Wastes	624 Drums
Metal Finishing Waste	118 "
Metal Casting Waste	448 "

This will be the last report on the Pasco site.

Sincerely,

RESOURCE RECOVERY CORP.

*John R. Kimberly, Jr.*  
John R. Kimberly, Jr.  
President

JRK/mam



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

RECEIVED

DEC 23 1974  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

December 19, 1974

Mr. John Arnquist  
Professional Engineer  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist:

The activity at the Pasco landfill site during the month of November, 1974 was as follows:

Barium Sludge	303 Tons
Paint Waste	34,540 Pounds
Metal Finishing Waste	266,560 "
Plywood Resin Waste	130,230 "
Benzoic Acid and Tars	176,000 "
Cutting Oil Waste	5,000 Gallons
Resin Mfg. Wastes	103,756 "
Paint Waste	628 Drums
Metal Casting Waste	504 "
Metal Finishing Waste	80 "

Sincerely,

RESOURCE RECOVERY CORP.

*John R. Kimberly, Jr.*  
John R. Kimberly, Jr.  
President

JRK/mam

Claude



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

November 6, 1974

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist:

The activity at the Pasco landfill site during the month of October, 1974 was as follows:

Paint Waste	61,900	Pounds
Metal Finishing Waste	174,960	"
Plywood Resin Waste	133,450	"
Barium Sludge	504,900	"
Cutting Oil Waste	3,500	Gallons
Resin Mfg. Waste	58,912	"
Paint Waste	192	Drums
Oily Waste	271	"
Metal Casting Waste	285	"

Sincerely,

RESOURCE RECOVERY CORP.

*John R. Kimberly Jr. /mam*  
John R. Kimberly, Jr.  
President

JRK/mam

RECEIVED

NOV 8 1974

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

October 9, 1974

*Claude* ✓  
**RECEIVED**  
*ES* *Eng*  
OCT 12 1974  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist;

The activity at the Pasco landfill site during the month of September, 1974 was as follows:

Solidified Caustic Soda	44,550 Pounds
Paint Wastes	111,280 "
Metal Finishing Waste	182,580 "
Plywood Resin Waste	43,310 "
Fertilizer Mfg. Waste	158,068 "
Cutting Oil Waste	7,500 gallons
Resin Mfg. Waste	37,794 "
Oily Sludge	162 drums
Paint Waste	632 "
Metal Casting Waste	527 "
Chemistry Lab Reagents	1 "

Sincerely,

RESOURCE RECOVERY CORP.

*John R. Kimberly*  
John R. Kimberly, Jr.  
President

JRK/mam





# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

September 11, 1974

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027


Dear Mr. Arnquist:

The activity at the Pasco landfill site during the month of August, 1974 was as follows:

Plywood Resin Waste	176,770 pounds
Acid Wash Solution	222,950 "
Metal Finishing Waste	89,680 "
Oily Sludge	112,340 "
Resin Mfg. Waste	19,746 gallons
Metal Rinse Solution	35,724 "
Cutting Oil Waste	4,000 "
Paint Waste	596 drums
Metal casting waste	374 "
Metal finishing waste	26 "

Sincerely,

RESOURCE RECOVERY CORP.

  
John R. Kimberly, Jr.  
President

JRK/mam

RECEIVED

SEP 14 1974

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

August 6, 1974

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist:

The activity at the Pasco landfill site during the month of July, 1974, was as follows:

Plywood Resin waste	171,910 pounds
Acid Wash Solution	89,400
Oily Sludge	54,340
Acid Sludge	1,000 gallons
Resin Mfg. waste	5,073
Cutting Oil waste	6,000
Paint waste	1,028 drums
Metal Casting waste	336

As you can see, business is down drastically due to the restraint on accepting new business. I have had to refuse two large requests with lead oxide contamination and one with 50 to 70 ppm mercury. I did not check to see where they eventually did dispose of these wastes.

Sincerely,

RESOURCE RECOVERY CORP.

*John R. Kimberly, Jr.*  
John R. Kimberly, Jr.  
President

JRK/mam

RECEIVED

AUG 9 1974

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

July 17, 1974

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist:


The activity at the Pasco disposal site during the month of June, 1974, was as follows:

Barium Sludge	233 tons
Chrome Rinse	173,890 pounds
Plywood resin waste	130,360 "
Metal finishing waste	131,220 "
Paint and solvent waste	72,475 "
Detergent metal wash	10,500 gallons
Resin mfg. waste	18,773 "
Cutting Oil waste	2,000 "
Paint waste	582 drums
Metal casting waste	448 "


This will be the last barium sludge until fall as Weyerhaeuser finished cleaning out their pits and are now starting to accumulate material again.

Sincerely,

RESOURCE RECOVERY CORP.

  
John R. Kimberly, Jr.  
President

JRK/mam



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

July 17, 1974

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist:


The activity at the Pasco disposal site during the month of May, 1974 was as follows:

Barium sludge	1,233 tons
Metal finishing waste	171,540 pounds
Chrome rinse	170,710 "
Plywood resin wastes	130,810 "
Resin Mfg. waste	4,752 gallons
Metal finishing waste	3,800 "
Cutting oil	4,000 "
Paint Waste	762 drums
Metal casting waste	336 "

Sensors and test well readings were normal,

Sincerely,

RESOURCE RECOVERY CORP.

  
John R. Kimberly, Jr.  
President

JRK/maun



# Resource Recovery Corporation

5501 AIRPORT WAY SOUTH  
SEATTLE, WASHINGTON 98108  
PHONE (206) 767-0355

Blue & Claude  
Hwy B  
FILE  
RECEIVED

BRANCH OFFICE:  
P. O. Box 650  
Pasco, Washington 99301

July 17, 1974

JUL 19 1974 Eng  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99027

Dear Mr. Arnquist:


The activity at the Pasco disposal site during the month of April, 1974, was as follows:

Barium Sludge	1,096 tong
Paint Waste	1,018 drums
Metal casting wastes	336 drums
Chrome Rinse	217,800 lbs.
Plywood resin waste	258,480 lbs.
Metal finishing waste	299,220 lbs.
Cutting oil	2,000 gallons
Resin Mfg. waste	31,247 gallons

Sensors and test well readings were normal. The Chrome Rinse, plywood resin waste, and metal finishing waste were expressed in gallons previously. Since the material is weighed rather than measured, I am expressing them as pounds.

Sincerely,

RESOURCE RECOVERY CORP.

  
John R. Kimberly, Jr.  
President

JRK/mam



# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

RECEIVED

MAY 6 1974

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

May 2, 1974

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Ave.  
Spokane, Wa 99207

Bear Mr. Arnquist:

Activity at the Pasco disposal site during the month of March, 1974  
was as follows:

### Received

Paint Waste	921 drums
Metal Finishing Waste	336 drums
Wood Preservative Waste	9,457 gallons
Barium Sludge	1,178 Tons
Chrome Rinse	17,769 gallons
Metal Finishing Waste	12,650 gallons
Paint Waste	8,000 gallons
Wood Treatment Waste	67,120 gallons
Cutting Oil Waste	2,000 gallons

Our sensors and test well readings during the month were normal, indicating  
no leaks or seepage.

Sincerely,

John R. Kimberly Jr.  
President  
Resource Recovery Corporation

JRK/dr



# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

RECEIVED

APR 26 1974

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

April 24, 1974

Mr. John Arnquist  
Professional Engineer  
Dept. of Ecology  
East 103 Indiana Ave.  
Spokane, Wash.

Dear Mr. Arnquist:

Activity at the Pasco Disposal site during February  
1974 was as follows:

### Received

Paint Waste	725 drums
Barium Sludge	812 tons
Chrome Rinse	21,000 gallons
Wood Treatment Waste	57,000 gallons
Tar Aromatic	160 drums
Metal Finishing Waste	412 drums
Paint Waste - Cleaning	60,511 gallons
Metal Finishing Waste	16,520 gallons
Grinding Oil Waste	6,000 gallons

Our sensors and test well readings during the month were  
normal, indicating no leaks or seepage.

Sincerely,

*John R. Kimberly, Jr.*  
John R. Kimberly, Jr.  
General Manager

JRK/rd



# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

RECEIVED

APR 26 1974

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

April 24, 1974

Mr. John Arnquist  
Professional Engineer  
Dept. of Ecology  
East 103 Indiana Ave.  
Spokane, Wash. 99207

Dear Mr. Arnquist:

Activity at the Pasco Disposal site during January,  
1974 was as follows:

### Received

Paint Waste	992 drums
Barium Sludge	1,035 tons
Chrome Rinse	32,585 gallons
Wood Treating Waste	10,050 gallons
Tar Aromatic	88 drums
Cutting Oil Waste	4,000 gallons
Metal Finish Brine	5,500 gallons
Metal Finishing Waste	280 drums


Our sensors and test well readings during the month were  
normal, indicating no leaks or seepage.

Sincerely,

*John R. Kinderly, Jr.*  
John R. Kinderly, Jr.  
General Manager

JRK/rd





# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

*Handwritten: Bill Brown HWB*  
**RECEIVED**  
*Handwritten: 7/3*  
APR 26 1974  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE  
*Handwritten: y r n k*

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

April 24, 1974

Mr. John Arnquist  
Professional Engineer  
Dept. of Ecology  
East 103 Indiana Ave.  
Spokane, Wash. 99207

Dear Mr. Arnquist:

Activity at the Pasco Disposal site during December  
1973 was as follows:

### Received

Paint Waste	445 drums
Barulm Sludge	1,214 tons
Chrome Rinse Water	23,257 gallons
Cutting Oils	2,000 gallons
Meatls Finishing Waste	416 drums
Paint Waste - Cleaning	27,200 gallons
Wood treatment Waste	13,950 gallons
Metal Finishing Waste	8,500 gallons

Our sensors and test well readings during the month were  
normal, indicating no leaks or seepage.

Sincerely,

*Handwritten signature: John R. Kimberly, Jr.*  
John R. Kimberly, Jr.  
General Manager

JRK/rd





# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 357-8443

RECEIVED

December 14, 1973

DEC 18 1973

DEPARTMENT OF ECOLOGY  
SPokane REGIONAL OFFICE

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99202

Dear Mr. Arnquist:

Activity at the Pasco Disposal site during the month of November, 1973 was as follows:

#### Received

Paint Waste (drums)	1
Lime Sludge (gallons)	10
Wood Preservative wastes (drums)	10
Wood Preservative wastes (gallons)	10
Cutting Oil (gallons)	10
Barium Sludge (tons)	10
Chrome Rinsing Water (gallons)	10

Sensor and test well readings during the month indicated operations were normal.

Because of the continuing controversy over the business is not increasing as it should normally be expected to increase.

Yours very truly,

  
James W. Moon  
President

JWM/ebg





# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 357-8443

RECEIVED

DEC 18 1973

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

December 14, 1973

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99207

Dear Mr. Arnquist:

Activity at the Pasco Disposal site during October, 1973  
was as follows:


## Received

Paint Waste (drums)	11
Barium Sludge (tons)	37
Chrome Rinse Water (gallons)	36,540
Cutting Oils (gallons)	6,000
Lime Sludge (gallons)	12,280

Our sensors and test well readings during the month  
were normal indicating no leaks or seepage.

We are still involved with the county over a  
use permit.

Yours very truly,

  
James W. Moon  
President

JWM/eps





# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

RECEIVED

OCT 9 1973 *mlb*

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Portco, Washington 99301

October 3, 1973

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, Washington 99207

Dear Mr. Arnquist:

Conditions A6, All and C4 of DOE Waste Discharge Permit #5301 require monthly reports. Please find below the data required by these conditions for the month of August, 1973.

### Condition A6

Cleaning Solution $\text{NH}_4$ and NaOH	17,238 gallons
Metal Casting Waste	390 drums
Weed Killers MCP Tar	1140 drums 680 pails
Paint Sludge	2331 drums
lime Sludge	13,529 gallons
Emulsion Cutting Oils	3,600 gallons
Pesticide Containers	35 empty containers
Miscellaneous Lab Chemicals	29 small containers
Oil Separator Sludge	5,000 gallons
Magnesia Barium Sulfate Sludge	742 tons
Garbage	3865 yards
Refuse	963 yards

### Condition All

Again this month no progress has been made in our research efforts concerning ponding of plating, wood treatment and paint wastes since we still have received none of these wastes in bulk. Lining has been installed in one pond.

### Condition C4

Moisture sensor readings and test well monitoring results have remained constant all month indicating no liquids have been discharged during the period.



# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

RECEIVED

OCT 9 1973 *lwy*

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

October 3, 1973

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, Washington 99207

Dear Mr. Arnquist:

Conditions A6, A11 and C4 of DOE Waste Discharge Permit #5301 require monthly reports. Please find below the data required by these conditions for the month of July, 1973.

### Condition A6

Etching Solution	80 drums
Insecticide	191 drums
Weed Killers MCP Tar	72 drums
Paint Sludge	160 drums
lime Sludge	31,700 gallons
Emulsion Cutting Oils	3,600 gallons
Pesticide Containers	400 empty containers
Metal Casting Waste	222 drums
Magnesia and Barium Sulfates	
Sludge Mercury Contaminated	340 tons
Garbage	3031 yards
Refuse Misc.	845 yards

### Condition A11

Again this month no progress has been made in our research since we still have received none of these wastes in bulk. It is contemplated linings will be installed in the months of August or September.

### Condition C4

Moisture sensor readings and test well monitoring results have remained constant all month indicating no liquids have been discharged during the period.

Sincerely,

*Newt Clark*  
Newt Clark  
Secretary-Treasurer

cc: Stan Vendettl  
Benton-Franklin Health District



# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

RECEIVED

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

JUL 25 1973

July 24, 1973

DEPARTMENT OF ECOLOGY  
SPokane Region Office

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99207

Dear Mr. Arnquist:

Conditions A6, A11 and C4 of DOE Water Discharge Permit #5301 require monthly reports. Please find below the data required by these conditions for the month of June, 1973.

### Condition A6

Weed killers MC P Tar	240 drums
Paint Sludge	1,409 drums
Lime Sludge	16,047 gallons
Emulsion Cutting Oils	3,600 gallons
Pesticide Containers	360 each

As a recap, as of June 30, 1973, we had received a total of the following from Rhodia Corporation, Portland,

2, 4D Tar	2011 drums
MC P A Bleed	2965 drums
Other, Misc.	435 drums
<u>Total</u>	<u>5411 drums</u>

### Condition A11

Again this month no progress has been made in our research efforts concerning ponding of plating, wood treatment and paint wastes since we still have received none of these wastes in bulk. We have prepared four ponds of the size we contemplate using (50' x 100') to the point where only the lining needs to be installed. The linings will be installed just prior to use.

### Condition C4

Moisture sensor readings and test well monitoring results have remained constant all month indicating no liquids have been discharged during the period.





# Resource Recovery Corporation

P. O. BOX 2431  
OLYMPIA, WASHINGTON 98507  
PHONE (206) 767-0355

## BRANCH OFFICES

5501 Airport Way S.  
Seattle, Washington 98108

P. O. Box 650  
Pasco, Washington 99301

June 11, 1973

RECEIVED

JUN 12 1973  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Mr. John Arnquist  
Professional Engineer  
Department of Ecology  
East 103 Indiana Avenue  
Spokane, WA 99207

Dear Mr. Arnquist:

Conditions A6, A11 and C4 of DOE Water Discharge Permit #5301 require monthly reports. Please find below the data required by these conditions for the month of May, 1973.

### Condition A6

Wastes received were:

Weed Killers - MCP Tar	487 drums
Paint Sludge	850 drums
Lime Sludge	16,629 gallons
Emulsion Cutting Oils	4,800 gallons
Pesticide Containers	250 each

### Condition A11

No progress has been made in our research efforts concerning ponding of plating, wood treatment and paint wastes because we have received none of the wastes in bulk. Of interest, but not conclusive, is the fact that in connection with the discharge of the above noted lime sludge into an unlined pond the solids immediately coated the pond, perhaps in conjunction with the contents of the soil, so that the deepest penetration of moisture was in the neighborhood of 10 inches. This coating action coupled with the rapid evaporation characteristic of the area would appear to preclude the need for the lining of ponds for simple wastes of this type and should prove to be greatly in our

**REFERENCE 6**





## ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 208-624-9537

International Specialists In the Environmental Sciences

### CONTACT REPORT

MEETING: ( )

TELEPHONE: (✓)

OTHER:

REFERENCE NUMBER:

CLIENT:

ADDRESS:

PERSON CONTACTED *PAT BARTTELS - ENGINEERING TECHNICIAN*  
and TITLE: *CITY OF PASCO ENGINEERING DEPT.*

PHONE: *509-545-3441*

FROM: *CHARLES F. PITZ*

TO:

ATTENDEES:

DATE: *5/27/87 - 1015*

CC: G. Neumaier, Central File

*Contact was made to Pasco Engineering Dept.  
to confirm the geographic limits of the  
public water supply system between the  
City of Pasco and the Pasco Sanitary landfill.  
Concluded from the information given that  
there are definitely wells beyond the perimeter  
of public supply service that are within  
a 3 mile radius of the landfill. MR. Bartels is  
unsure whether or not the well #9/30-2891 is tied into  
the city system - recommends I contact Dennis Wright,*

*CFP*

**REFERENCE 7**

# WATER WELL REPORT

STATE OF WASHINGTON

Application No.

Permit No.

OWNER: Name

BURLINGTON NORTHERN

Address

LOCATION OF WELL:

County FRANKLIN

Cent

1/4 NW

1/4 Sec. 15

T. 9N.

N. R. 20E. W.M.

and distance from section or subdivision corner

5) PROPOSED USE: Domestic ☐ Industrial ☐ Municipal ☐

Irrigation ☒ Test Well ☐ Other ☐

4) TYPE OF WORK: Owner's number of well (if more than one) 36

New well ☒ Method: Dug ☐ Bored ☐

Deepened ☐ Cable ☒ Driven ☐

Reconditioned ☐ Rotary ☐ Jetted ☐

5) DIMENSIONS: Diameter of well 16" inches.

Drilled 143 ft. Depth of completed well 143 ft.

6) CONSTRUCTION DETAILS:

Casing installed: 16" Diam. from 0 ft. to 9 ft.

Threaded ☐ " Diam. from ft. to ft.

Welded ☒ " Diam. from ft. to ft.

Perforations: Yes ☒ No ☐

Type of perforator used Mills Knife

SIZE of perforations 3/8 in. by 3" in.

900 perforations from 113 ft. to 137 ft.

perforations from ft. to ft.

perforations from ft. to ft.

Screens: Yes ☐ No ☒

Manufacturer's Name

Type Model No.

Diam. Slot size from ft. to ft.

Diam. Slot size from ft. to ft.

Gravel packed: Yes ☐ No ☒ Size of gravel:

Gravel placed from ft. to ft.

Surface seal: Yes ☒ No ☐ To what depth? 20 ft.

Material used in seal Puddy Clay

Did any strata contain unusable water? Yes ☐ No ☒

Type of water? Depth of strata

Method of sealing strata or

7) PUMP: Manufacturer's Name

Type HP

8) WATER LEVELS: Land-surface elevation above mean sea level 477 ft.

Static level ft. below top of well Date

Test pressure lbs. per square inch Date

Artesian water is controlled by (Cap, valve, etc.)

9) WELL TESTS: Drawdown is amount water level is lowered below static level

as a pump test made? Yes ☐ No ☐ If yes, by whom?

Flow: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Recovery data (time taken as zero when pump turned off) (water level measured from well top to water level)

Time Water Level Time Water Level Time Water Level

" " " " " "

" " " " " "

Rate of test

Flow test: gal./min. with ft. drawdown after hrs.

Test flow g.p.m. Date

Temperature of water Was a chemical analysis made? Yes ☐ No ☒

## (10) WELL LOG:

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Black Sand	0	15 ft
Black Sand & Basalt Gravel	15	32 ft
Basalt Gravel	32	45 ft
Broken Basalt	45	60 ft
Basalt Gravel & Black Sand	60	62 ft
Broken Basalt	62	72 ft
Clay & Basalt Gravel	72	79 ft
Clay	79	100 ft
Clay & Sand	100	104 ft
Clay & Basalt Gravel	104	106 ft
Clay, Sand & Gravel	106	112 ft
Gravel Sand & Water @	112	115 ft
Sand & Gravel	115	118 ft
Black Sand & Gravel	118	140 ft
Bed Rock	140	143 ft

RECEIVED  
SEP 17 1974  
DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Work started 19 Completed 19

## WELL DRILLER'S STATEMENT:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME St. George Drilling Co.  
(Person, firm, or corporation) (Type or print)

Address 701 So. 45th Ave

[Signed] [Signature]  
(Well Driller)

License No. 0482 Date 3-15, 1974

4/30 - 27 p1

(1) OWNER: Name Washington Idaho Laborers Address 3921 E. Francis, Spokane, Wn., 99207  
(2) LOCATION OF WELL: County Franklin N<sup>1</sup>/<sub>2</sub>, NE<sup>1</sup>/<sub>2</sub> SE <sup>1</sup>/<sub>4</sub> SW <sup>1</sup>/<sub>4</sub> Sec 27 T 9 N. R. 30 W. R.  
Distance and bearing from section or subdivision corner

(S) PROPOSED USE: Domestic ☒ Industrial ☐ Municipal ☐  
 Irrigation ☐ Twt Well ☐ Other ☐

**(4) TYPE OF WELL** Owner's number of well  
(If more than one) . . . . .

New well <input checked="" type="checkbox"/>	Method: Dug <input type="checkbox"/>	Road <input type="checkbox"/>
Deepened <input type="checkbox"/>	Cable <input type="checkbox"/>	Driven <input type="checkbox"/>
Reconditioned <input type="checkbox"/>	Rotary <input checked="" type="checkbox"/>	Jetted <input type="checkbox"/>

(5) **DIMENSIONS:** Diameter of well 3 inches.  
 Drilled 135 ft. Depth of completed well 135 ft.

**(6) CONSTRUCTION DETAILS:**

**Casing installed:** 8 " Diam. from #1 ft. to 125 ft.  
 Threaded ☐ " Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
 Welded ☒ " Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

**Perforations:** Yes ☐ No ☒

Type of perforator used \_\_\_\_\_

SIZE of perforations \_\_\_\_\_ in. by \_\_\_\_\_ in.

\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

\_\_\_\_\_ perforations from \_\_\_\_\_ in. to \_\_\_\_\_ in.

Screens: Yes ☒ No ☐ Johnson

Manufacturer's Name Johnson  
Type Stainless Steel Model No. \_\_\_\_\_  
Diam. 8 Slot size 20 from 125 ft. to 135 ft.  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

Gravel packed: Yes ☐ No ☒ Size of gMvel: \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

Surface seal: Yes ☒ No ☐ To what depth? 18 ft.

Material used in seal Bentonite  
Did any strata contain unusable water? Yes ☐ No ☒  
Type of water? \_\_\_\_\_ Depth of strata \_\_\_\_\_  
Method of sealing strata off \_\_\_\_\_

(7) PUMP: Manufacturer's Name Berkeley  
Type: Submersible HP 5

(S) WATER LEVELS: Lead-surface elevation above mean sea level. 420 ft.  
 Static level 74 ft. below top of well Date 8/30  
 Artesian pressure \_\_\_\_\_ lbs. per square inch Date \_\_\_\_\_  
 Artesian water is controlled by \_\_\_\_\_ (Cap. valve, etc.)

**(9) WELL TESTS:** Drawdown is amount water level is lowered below static level

Was a pump test made? Tea <input type="checkbox"/> No <input checked="" type="checkbox"/> If yes, by whom? _____			
Yield:	gal./min. with	ft. drawdown after	hrs.
	"	"	"
	"	"	"

Recovery data (time taken as asro when pump turned off) (water level measured from well top to water level)

Time	Water Level	Time	Water Level	Time	Water Level
.....	.....	.....	.....	.....	.....
.....	.....	.....	.....	.....	.....

Date of test \_\_\_\_\_  
 Ir test 20 gal./min. with 10 ft. drawdown after 2 hrs.  
 Artesian flow \_\_\_\_\_ g.p.m. Date \_\_\_\_\_  
 Temperature of water \_\_\_\_\_ Was a chemical analysis made? Yes ☐ No ☒

**(10) WELL LOG:**

**Formatica:** Describe by color, character, size of emulsion and structure, and show thickness of layers and the kind and nature of the material in each stratum penetrated, with at least an entry for each change of formation.

MATERIAL	FROM	TO
Sand, some clay	0	5
Silty sand	5	11
3/4" minus gravel with sand & clay	11	12
Cemented gravel	12	16
Clay & gravel	16	24
Sand & silt	24	70
Yellow clay	70	76
Clay & gravel- up to 2" some water	76	84
Sand & water	84	104
Clay & sand - no water	104	109
Sand, large boulders some water	109	125
Sand & gravel with water	125	135

~~RECEIVED~~

~~SECRET~~ 1-1980

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Work started 7-15, 1930. Completed 7-18, 1930

**WELL DRILLER'S STATEMENT:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

**NAME B & H DRILLING**  
(Person, firm, or corporation) (Type or print)

Address: Rt. 3 Box 3365-A, Kennewick, Wn. 983

[Signed] H. G. Bultera  
(Well Driller)

License No. 0046 Date 9-8 1951

9/30 - 27E

(1) OWNER: Name Paul (SAVAGE) Address 524 Rd. 37 P.A.S.C.O. WA  
LOCATION OF WELL: County FRANKLIN - SW 1/4 NW 1/4 Sec 27 T. 9 N. R. 30 E W.M.  
ing and distance from section or subdivision corner

**(3) PROPOSED USE:** Domestic ☒ Industrial ☐ Municipal ☐  
Irrigation ☐ Twt Well ☐ Other ☐

(4) TYPE OF WORK: Owner's number of well (if more than one) 1

New well <input checked="" type="checkbox"/>	Method: Dug <input type="checkbox"/>	Bored <input type="checkbox"/>
Deepened <input type="checkbox"/>	Cable <input checked="" type="checkbox"/>	Driven <input type="checkbox"/>
Reconditioned <input type="checkbox"/>	Rotary <input type="checkbox"/>	Jatted <input type="checkbox"/>

(I) DIMENSIONS: Diameter of well 8" inches.  
 Drilled 112 ft. Depth of completed well 112 ft.

**(1) CONSTRUCTION DETAILS:**

Casing Installed: \_\_\_\_\_ " Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
 Threaded ☐ \_\_\_\_\_ " Odam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
 Welded ☒ 2" " Ddam. from 0 ft. to 11.1 ft.

**Perforations:** Ym ☐ No ☒

Type of perforator used \_\_\_\_\_

**SIZE** of perforations \_\_\_\_\_ in. by \_\_\_\_\_ in.

\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

\_\_\_\_\_ perforations from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

**Screens:** Yes ☐ No ☒

**Manufacturer's Name** .....

**Type** ..... **Model No.** .....

**Diam.** ..... **Slot size** ..... **from** ..... **ft. to** ..... **ft.**

**Diam.** ..... **Slot size** ..... **from** ..... **ft. to** ..... **ft.**

Gravel packed: Yes ☐ No ☒ Size of gravel: .....  
Gravel placed from ..... ft. to ..... ft.

Surface seal: Yes ☒ No ☐ To what depth 18 ft.  
Material used in seal: Bentonite  
Did any strata contain unusable water? Yes ☐ No ☒  
Type of water: \_\_\_\_\_ Depth of strata: \_\_\_\_\_  
Method of sealing strata off: \_\_\_\_\_

(7) PUMP: Manufacturer's Name: \_\_\_\_\_  
Type: \_\_\_\_\_ H.P. \_\_\_\_\_

(8) **WATER LEVELS:** Land-surface elevation above mean sea level..... 390 n.  
 Static level ..... ft. below top of well Date .....  
 Artesian pressure ..... lbs. per square inch Date .....  
 Artesian water is controlled by ..... (Cap, valve, etc.)

**(9) WELL TESTS:** Drawdown is amount water level is lowered below static level

Was a pump test made? Yes ☐ No ☒ If yes, by whom? .....

Yield:	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"

Recovery data (time taken as zero when pump turned off) (water level measured from well top to water level)

Time	Water Level	Time	Water Level	Time	Water Level

Rate of test \_\_\_\_\_

Sauer test 25 gal/min. with 6 ft. drawdown after 2 hrs.

Artesian flow \_\_\_\_\_ gpm. Date \_\_\_\_\_

Temperature of water 62 Was a chemical analysis made? Yes ☐ No ☒

**(10) WELL LOG:**

**Formation:** Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Silty sand	0	62
gray sand	62	99
Black coarse sand	99	110
3/4 minus gravel + sand	110	112

RECEIVED

JUL 6 - 1978

DEPARTMENT OF ECOLOGY  
SPOKANE REGIONAL OFFICE

Work started 6/16, 1978. Completed 6/23, 1978.

**WELL DRILLER'S STATEMENT:**

**This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.**

NAME L. W. SMITH WELL DRILLING  
(Parson, firm, or corporation) (Type or print)

Address 9808 W. Argent, Pasco, Wn.

[Signed] Boyd W. Smith  
(Well Driller)

License No. 0985 Date 7/3, 1978





Permit No.

License No. 725 Date 3-30, 198



bearing and distance from section or subdivision corner

License No. 0746 Date 7/22 1977

**REFERENCE 8**

PUBLIC WATER SUPPLY SYSTEM LISTING  
SHAHER/EPA

09/05/8

10 NO. SYSTEM NAME  
SYSTEM MAILING ADDRESS  
MANAGER/OWNER NAME  
BACTI SAMPLING SCHEDULE  
POPULATION  
SOURCE NO. SOURCE NAME

COUNTY  
CITY, ST ZIP

CLASS

TELEPHONE

ACTUAL POTEN

JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC

CATEGORY TYPE INTERTIE DEPTH CAPACITY TREATMENT

TWP RING SEC

453103 LAKEVIEW MOBILE HOME PARK  
Z S 1505 RD 40E  
Mr: RICHARD MEINEMEYER  
Bacti: 1/month  
Per: 800  
Source: 1  
Source: 2  
Source: 3  
Source: 4

FRANKLIN  
PASCO, WA 99301

Class: 1

582-3271 206 0

WELL 103' 70 NONE.  
WELL 89' 350 NONE.  
WELL 99' 220 NONE.  
WELL 100' 490 NONE.

34N 30E 1K  
34N 30E 1N  
34N 30E 1N  
9N 30E 34

464003 PASCO WATER DEPARTMENT  
PO BOX 293  
Mr: JAMES S. AJAI  
Bacti: 22/month  
Per: 19,100  
Source: 1 COLUMBIA RIVER

FRANKLIN  
PASCO, WA 99301

Class: 1

(509) 543-3468 6,350 0

SURF PRI. 12,500 CL2.COAG.SED.FILT.

9N 30E 3N

243039 RADA SONS  
IS E ICE HARBOR DR  
Mr: DOUG RADA  
Bacti: once/12 months  
Per: 16  
Source: 1 WELL #1

FRANKLIN  
PASCO, WA 99301

Class: 4

545-1054 6 5

WELL PRI. 100' 62 NONE.

9N 30E 28

739203 ROGERS-WALLA WALLA INC  
PO BOX 2324  
Mr: WILLIAM T. LAWR  
Bacti: once/ 3 months (\*)  
Per: 0 Transitory  
Source: 1 WELL #1  
Source: 2 WELL #2  
Source: 3 WELL #3  
Source: 4 WELL #4

FRANKLIN  
PASCO, WA 99302

Class: 2t

(509) 547-3851 0 0

500 500 500 500 500 500 500 500 500 500  
WELL PRI. 80' 180 CL2.  
WELL PRI. 87' 280 CL2.  
WELL PRI. 82' 185 CL2.  
WELL PRI. 83' 415 CL2.

9N 30E 6N  
9N 30E 6N  
9N 29E 1R  
9N 30E 6N

8354SP STANDARD OIL OF CALTEORNIA  
P O BOX 413

FRANKLIN  
PASCO, WA 99301

Class: 4

1 0

Bacti: once/12 months  
Per: 20  
Source: 1

WELL 350' NONE.

9N 30E 3SL

233268 WESTERN FARMS SERVICE INC  
E. 10005 MONTGOMERY  
Mr: WAYNE DUFF  
Bacti: once/12 months  
Per: 0 Transitory  
Source: 1 WELL #1

FRANKLIN  
SPOKANE, WA 99206

Class: 4t

(509) 924-9213 0 0

24 24 24 24 24 24 24 24 24 24  
WELL PRI. 120' 80 NONE.

9N 30E 27F

PUBLIC WATER SUPPLY SYSTEM LISTING  
SHAHER/EPA

09/05/86

ID NO.	SYSTEM NAME	COUNTY	CLASS														
	SYSTEM MAILING ADDRESS	CITY, ST ZIP															
	MANAGER/OWNER NAME	TELEPHONE	ACTUAL	POTEN													
	6ACT1 SAMPLING SCHEDULE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC				
	POPULATION																
	SOURCE NO. SOURCE NAME	CATEGORY	TYPE	INTERTIE	DEPTH	CAPACITY	TREATMENT										
035206	AZTLAN CONSTRUCTION INC 2700 E LEWIS Mr: DON NORVELL Bacti: once/12 months Perml: 20 Source: 1	FRANKLIN PASCO, WA 99301 (509) 545-1985	Class: 4		6	0											
		WELL			106'		NONE.	9N 30E 280									
076384	BONNEVILLE POWER ADMIN-FRANKLIN 22 PASCO-KAHLOTUS RD Mr: BOB CUTRIGHT Bacti: once/12 months Perml: 16 Source: 1	FRANKLIN PASCO, WA 99301	Class: 4		1	0											
		WELL			120'		NONE.	9N 30E 27K									
07665B	BONNIE BRAE TRAILER COURT 2508 EAST LEWIS Mr: ROBERT S LAURENCE Bacti: once/ 3 months (#) Perml: 65 Source: 1 WELL NO 1	FRANKLIN PASCO, WA 99301 (509) 345-4205	Class: 2		36	0											
		WELL	PRI.		120'	300	NONE.	9N 30E 28A									
886856	DE VRIES WATER SYSTEM HC 32 BOX 1026 Mr: GARY DE VRIES Bacti: once/12 months Perml: 12 Source: 1 Source: 2 Source: 3	FRANKLIN PASCO, WA 99301 (509) 545-4125	Class: 4		6	0											
		WELL			120'	250	NONE.	9N 30E 220									
		WELL			120'	250	NONE.	9N 30E 22G									
		WELL			120'	250	NONE.	9N 30E 22G									
266300	FRONTIER MACHINERY 1707 EAST JAMES Own: AL-MAC DEVELOPMENT CO. Bacti: once/ 3 months Perml: 0 Transitory: Source: 1 UELL	FRANKLIN PASCO, WA 99301	Class: 3t		0	0											
		WELL	PRI.		120'	250	NONE.	9N 30E Sec 21									
33990R	HOMES HIDAHA (Motel) 2506 E LEWIS Mr: LILLIAN T. HOMME Bacti: once/12 months Perml: 2 Transitory: Source: 1 WELL # 1 Source: 2 WELL # 2	FRANKLIN PASCO, WA 99301 547-3697	Class: 4t		1	0											
		WELL	PRI.		91'	30	NONE.	9N 30E									
		WELL			91'	30	NONE.										

D need \$ 28-1W  
98

**REFERENCE 9**

CONTROL #	SEC #	OLD APP#	OLD PERM	OLD CIFT	DATE CP	S C A	CNTY	PERMIT	NAME	SOURCE OF APPROPRIATION - TRIBUTARY OF						
PTS P	LOC.	OF POD/POW	(CHG CH)	PURPOSE OF USE	USE TYPE	INST	C Q S	ANNUAL	C P S	IPP	C S PRO	TIME OF	P P P			
						DATE	M U U	CA	H U U	AC	M U VIESS	USE	I A C			
WATER RESOURCE INVENTORY AREA- 33																
TOWNSHIP - 05 RANGE - 30 E																
C3-0488LC	01	0A651	04445	04695	00/13/957	WALL	02/14/950	USFWS		WELL						
1	TH25	PASCO FWP /	LEISHT LAND	IRRIGATION	C	800.0	G	484.0		171.0	A	IS				
G3-0076DS	02	00760		00811	00/30/923	WALL	/ /	UNSAPEP P W		WELL						
1	E2 L1			DOMESTIC SINGLE	C	350.0	C 2	180.0	2							
				IRRIGATION	C	350.0	G 2	260.0	2	20.0		IS				
GI-0893OC	02	08930	08244	05971	03/25/947	WELL	01/09/948	WALLA WALLA	FOPT D	WELL						
1	CU			DOMESTIC GENERAL	C	25.0	G 3	28.0								
				ECOMPCIAL/INDUSTRIAL	C	15.0	G 3	12.0	2							
				PIPE PROTECTION	C	25.0	G 3	12.0	2							
33-00540R	03	00540		00636	00/00/923	FRAN	/ /	BENNINGHCVEN C / E	WELL							
1	NE4SU6NE4			DOMESTIC SINGLE	C	400.0	G 2	350.0	2	120.0	X	IS				
				IRRIGATION	C	400.0	G 2	350.0	2							
G3-003413	03	00341		00639	00/00/926	FRAN	/ /	BENNINGHCVEN C / E	WELL							
1	E2SE4NW4			IRRIGATION	C	350.0	C	250.0		120.0	X	IS				
G3-25397C	03			08/15/977	FRAN	08/10/978	NATIONAL MARINE FI	INFILTRATION TP								
1	IN4			FISH PROPAGATION	C	2350.0	C									
S3-07162C	03	07162	05043	03951	05/21/946	FRAN	05/26/947	WA ST PK&REC COMM	SNAKE R (UALIUIA LK1			COL R (WALL LK)				
1	L10			DOMESTIC MULTIPLE	C	.15	C		S							
TOWNSHIP - 02 RANGE - 30 E																
S3-04369PA1	01	08389	07643		11/09/966	FRAN	01/09/967	BURLINGTON NORTHER	WELLS							
2	NE4NW4			DOMESTIC MULTIPLE	C	1300.0	G 2	1.0								
				IRRIGATION	C	1300.0	G 2	548.0		137.0		IS	5 5			
C3-09966PAL	01	09966	09476		01/06/949	FRAN	01/09/987	BURLINGTON NORTHER	WELLS							
2	NE4NW4			DOMESTIC MULTIPLE	C	1800.0	G 2	2.0								
				IRRIGATION	C	1800.0	G 2	552.0		160.0		IS	5 5			
G3-2378APAL	01			06/12/974	FRAN	07/09/975	VOSS RAYMOND C ET	WELLS								
2	GL-A			IRRIGATION	C	2500.0	G	969.4		165.0		IS	2 2 2			
G3-2385UPAC	01			07/05/974	FRAN	07/17/975	VOSS RAYMOND C	WELLS								
2	GL-4			IRRIGATION	C	2300.0	G	1383.0		302.0		IS	2 2 2			
C3-24300PAL	01			05/07/975	FRAN	01/09/967	BURLINGTON NORTHER	WELLS								
2	NE4NW4			IRRIGATION	C	1470.0	G	425.0		107.0		IS	3 5 5			
G3-24325P	01			05/03/975	FRAN	03/23/976	BURLINGTON NORTHER	WELL								
1	CL-4			IRRIGATION	C	3375.0	S	1965.0		375.0		IS				
G3-24775PAL	01			01/15/976	FRAN	07/19/976	VOSS RAYMOND ET UX	WELLS								
2	GL-4			ENVIRONMENTAL QUALITY	C	1300.0	S 2									
				IRRIGATION	C	1500.0	G 2	636.64		160.0		IS	2 2 2			
G3-27029BAI	01			06/03/951	FRAN	01/09/967	BURLINGTON NORTHER	WELLS								
2	NE4NU4			IRRIGATION	C	2700.0	G	1200.0		300.0		IS	6 6 6			
C3-10267P	02	10267	09623		06/16/969	FRAN	06/16/970	MARCHBAI	Q ET AT WELLS							
2	SE4			IRRIGATION	C	1500.0	G	5.0		150.0		IS	2 2 2			
G3-22491P	02			02/04/974	FRAN	06/16/974	TIPPETT ROBERT A	WELLS								
2	NE4 SE4 NU4 & NU4 SU4 NE4			IRRIGATION	C	2160.0	S	1116.0		240.0		IS	03011101			
G3-22499P	02			02/04/974	FRAN	06/16/974	TIPPETT ROBERT A	WELL								
1	NE4SU4NE4			IRRIGATION	C	1440.0	G	744.0		180.0		IS	03011101			
G3-23867P	02			10/24/974	FRAN	07/03/975	TIPPETT ROBERT A	WELLS								
2	SE4NU4, SU4NE4			IRRIGATION	C	2400.0	G	1116.0		240.0		IS	03011101			
G3-2024SPAL	03			06/02/972	FRAN	10/16/965	BURLINGTON NORTHER	WELLS								
2	SU4SU4			IRRIGATION	C	5200.0	G	2101.6		520.0		IS	2 2 2			
G3-25175P	03			01/13/977	FRAN	10/16/985	BURLINGTON NORTHER	WELL								
1	SU4SU4			IRRIGATION	C	1200.0	C	520.0		130.0		IS	01011231			
G3-246410	10			11/08/975	FRAN	/ /	CONN MUT LIFE INS	WELL								
1	SE4NW4SU4			IRRIGATION	C	1400.0	G	530.0		145.0		IS	04011031			

CONTROL #	SEC #	OLD APPL	OLD PERM	OLD CERT	DATE OF PRIORITY	S C A T C M	CNTY	PERMIT DATE	NAME	SOURCE OF APPROPRIATION TRIBUTARY OF						
WUP P	PTS P	LOC. OF POO/POW	(CNG CO)	PURPOSE OF USE	USE TYPE	INST 91	C P S M U W	ANNUAL DA	C P S M U U	IPR AC	C S PRO M O VISOC	TIME OF USE	R R P I A C			
WATER RESOURCE INVENTORY AREA- 33																
TOWNSHIP - 09 WANCLE - SUB E																
G3-2024SPBL 1	11	NW4NW4		X	IRRIGATION	06/02/972	S	FRAM 10/16/985	BURLINGTON NORTHER WELLS	520.0	RBM	02011031	2 2 2			
								5200.0 C	2101.6							
G3-20247P 4	11	NE4, NW4, SW4, SE4		X	IPWICATTON	06/02/972	S	FRAM 10/16/985	BUPLINGTON NORTHER WELLS	520.0	BNM	02011031				
								5200.0 C	2101.6							
G3-06369PBL 3	12	06399 SW4SE4: NW4SE4	07843		DOMESTIC MULTIPLE IRRIGATION	11/09/966	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	137.0	IP	IS	5 5 5			
								1300.0 C 2	1.0							
								1300.0 G 2	546.0							
G3-10897PBL 3	12	10897B SW4SE4	10377		IRRIGATION	05/20/970	S	FRAM 01/09/987	BUPLINGTON NORTHER WELLS	400.0	IP	03011031	5 5 5			
								4000.0 C	1427.0							
G3-24500PBL 1	12	SW4SE4: NW4SE4			IRRIGATION	05/07/975	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	107.0	IP	02011130	5 5 5			
								1470.0 G	426.0							
G3-24546P 2	12	NW4NW4 I SW4NW4			IPRIGATION	06/07/975	S	FRAM 10/03/985	CDNN MUL LIFE INS WELLS	116.0	IPK	01011231				
								1200.0 C	609.4							
G3-27029BBL 3	12	SW4SE4: NW4SE4			IRRIGATION	06/03/981	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	300.0	IPK	02011033	6 6 6			
								2700.0 C	1200.0							
G3-27029BFL 2	13	SW4NW4		X	IRRIGATION	06/03/981	S	FRAM 01/09/987	BUPLINGTON NORTHER WELLS	300.0	IPK	02011133	6 6 6			
								2700.0 G	1200.0							
G3-24312C 1	14	NC4		X	IRRIGATION	01/31/975		FRAM 12/19/975	MIDDLETON WILLIAM UELL	141.0		01011231				
								1400.0 G	744.0							
G3-25135A 1	14	E2NE4: NE4NE4		X	IPWICATTON	04/03/966		FRAM / 7	MIDDLETON WILLIAM WELL	20.0		IS				
								300.0 G								
G3-01177C 1	21	SW4 NE4 SE4	10496	09977	X	IRRIGATION		FRAM 11/23/970	COLUMBIA EAST ITO WELL	266.0	S MP	03011101				
								666.0 G	719.0							
G3-06359PCL 2	23	06359 NE4NE4	07543		DOMESTIC MULTIPLE IRRIGATION	11/09/966	S	FRAM 01/09/987	BUPLINGTON NORTHER WELLS	137.0	IP	IS	5 5 5			
								1300.0 G 2	1.0							
								1300.0 G 2	546.0							
G3-09968PCL 2	23	09968 NE4NE4	09476		DOMESTIC MULTIPLE IRRIGATION	01/06/969	S	FRAM 01/09/987	BUPLINGTON NORTHER WELLS	160.0	IP	02011130	5 5 5			
								1600.0 G 2	2.0							
								1600.0 G 2	552.0							
G3-10897PCL 2	23	10897 NW4NW4	10377	X	IRRIGATION	05/20/970	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	400.0	IP	03011631	5 5 5			
								4000.0 G	1427.0							
G3-20251PAL 3	23	NW4NW4/SW4SE4/NW4SW4		X	IPWICATTON	06/02/972	S	FRAM 02/13/985	BUPLINGTON NORTHER WELLS	315.0	IPM	02011031	2 2 2			
								2743.0 G	2269.0							
G3-24500PCI 2	23	NE4NE4		X	IRRIGATION	05/07/975	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	107.0	IP	02011130	5 5 5			
								1470.0 G	426.0							
G3-27029BCL 2	23	NE4NE4		X	IPRIGATION	06/03/981	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	300.0	IPK	02011130	6 4 4			
								2700.0 G	1200.0							
G3-27881I 1	23	SW4SE4		X	IRRIGATION	05/17/964		FRAM 03/29/985	BURLINGTON NORTHER WELL	200.0	IPBK	IS				
								1600.0 G	600.0							
G3-06389PCL 4	24	06389 NW4NW4	07543		DOMESTIC MULTIPLE IRRIGATION	11/09/966	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	137.0	IP	IS	3 5 5			
								1300.0 G 2	1.0							
								1300.0 G 2	546.0							
G3-09968PCL 4	24	09968 NW4NW4	09476		DOMESTIC MULTIPLE IRRIGATION	01/04/969	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	160.0	IP	02011130	3 5 5			
								1600.0 G 2	2.0							
								1600.0 G 2	562.0							
G3-10897PCL 4	24	10897 NW4NW4	10377	X	IPRIGATION	05/20/970	S	FRAM 01/09/987	BURLINGTON NORTHER WELLS	400.0	IP	03011031	5 5 5			
								4000.0 G	1427.0							
G3-00472C 1	24	09296 E2 NW4 NW4	06617		DOMESTIC SINGLE STOCK WATERING IRRIGATION	03/12/966		FRAM 08/16/966	SULLIVAN ROBERT GJ WELL	20.0	IP	03011031				
								260.0 G 3	2.0							
								200.0 G 3	1.0							
								200.0 C 3	60.0							
G3-24500PCL 4	24	NW4NW4		X	IRRIGATION	05/07/975	S	FRAM 01/09/987	BUPLINGTON NORTHER WELLS	107.0	IP	02011130	5 5 5			
								1470.0 C	426.0							
G3-27029BCL 4	24					06/03/981	S	FRAM 01/09/987	BUPLINGTON NORTHER WELLS							

06/08/87

15:09

DEPT OF ECOLOGY / HQ OLYMPIA WA

003

CONTROL K	SEC K	OLD APPL	OLD PERM	OLD CERT	DATE OF EXPIRITY	S C A T C M	CNTY	PERMIT DATE	NAME	SOURCE OF APPROPRIATION	TRIBUTARY	3F
PTS P LOC. OF POD/POH (CNG CB)	PURPOSE OF USE	USE TYPE	TEST GI	C B S M U U	ANNUAL GA	C B S M U U	TRM AC	C B S M U U	PRO- H O VISOS	YML CF USE	P E P 1 A C	
WATER RESOURCE INVENTORY AREA- 33												
TOWNSHIP - 09 RANGE - 30 E												
4 NW4NW4					X IRRIGATION			2700.0 G	1200.0	300.0	LRK	02011130 4 6 6
03-241440AL 25					01/22/979 S			FRAN 07/02/985	BURLINGTON NORTHER WELL			
1 NW4SU4					X IRRIGATION			400.0 C	160.0	40.0	RMS	01111331 2 2 2
03-00401C 24 11913					05/20/971			FRAN 04/04/973	ALDERSON J R & R WELL	150.0	RMS	03011121
1 SU4NE4					X IRRIGATION			1440.0 G	768.0			
G3-00942C 24 12359					12/31/971			FRAN 10/12/975	COLUMBIA EAST LTD WELLS	500.0	MRS	03011101
2 SE4NW4SE4, NE4SW4NW4					X IRRIGATION			4500.0 G	2500.0			
03-20251PBL 28					04/02/972 S			FRAN 03/13/985	BURLINGTON NORTHER WELL	315.0	IRM	02011031 2 2 2
1 SW4NE4					X IRRIGATION			2745.0 G	1280.0			
03-28144BSL 28					01/22/979 S			FRAN 07/02/985	BURLINGTON NORTHER WELLS	40.0	RMS	01111231 2 2 2
2 SE4SE4					X IRRIGATION			400.0 G	160.0			
03-278971 28					09/27/984			WALL 07/24/985	BURLINGTON NORTHER WELL	75.0	LRK	IS
1 W2SW4					X IRRIGATION			750.0 G	300.0			
G3-01085C 34 07987 07487					03/01/984			FRAN 04/05/984	HILL CECIL C WELLS	15.0	AETHM	IS
3 N2SW4SE4					X DOMESTIC MULTIPLE			500.0 G 2	22.4			
					X IRRIGATION			300.0 G 2	60.0			
03-028330 33 02833 02740					01447 11/28/952			FRAN 05/08/953	TIGERWATER SHAVER WELL		AE	
1 GL-1					DOMESTIC SINGLE			100.0 G 2	140.0 2		AE	
					COMMERCIAL/INDUSTRIAL			100.0 G 2	140.0 2			
03-1869SL 33					01/16/974			WALL 04/05/974	USCE WELL		RHI	
1 GL4					X DOMESTIC MULTIPLE			450.0 G 2	5.0		RHI	
					X IRRIGATION			450.0 G 2	42.83	10.0		03011031
S3N11857C 35 11457 0A889					05191 11/24/952			FRAN 02/20/953	STANDAPO OIL CO CA SWACE R (WALIULA LK)		COL R (WALC LK)	
1 L4					FIRE PROTECTION			438 C				
					X IRRIGATION			101 C		75		04151001
G3-02344C 34 02344 02215					02124 02/18/952			WALL 06/13/952	SOWTH COL BSN IPP WELL			
1 SW4SU4SE4					DOMESTIC MULTIPLE			40.0 G	64.0			
G3-04117C 34 08117 05839					04249 11/28/981			WALL 05/25/942	SPOWN GE / J O WELL			
1 L4 PLAT RIVER BANK BEIGHTS					DOMESTIC SINGLE			28.0 C 2	12.0 2	3.0	AE	IS
					X IRRIGATION			25.0 G 2	12.0 2			
G3-22244C 38					12/14/973			WALL 11/08/974	CARISON WALTER E WELL		R	
1 SU4 SE4 NW4					DOMESTIC SINGLE			39.0 G 2	1.0		R	
					X IRRIGATION			30.0 G 2	7.33	2.0		01011231
G3-25013C 34					08/05/974			WALL 12/07/977	CARLSON WALTER E WELL		R	
1 L-4 BL-I CARISON PL 91					DOMESTIC MULTIPLE			140.0 G 2	10.0		R	
					X IRRIGATION			140.0 G 2	31.0	6.48		01011231
TOWNSHIP - 09 RANGE - 31 E												
G3-10897PAZ 01 19897A 10377A					05/20/970 S			FRAN 01/09/987	BURLINGTON NORTHER WELL	400.0	LR	03011031 5 5 5
2 NE4NW4					X IRRIGATION			4000.0 G	1427.9			
33-24017B 06					05/21/985			FRAN 08/28/988	KENNEDY JOHN O WELL			
1 SL-L					DOMESTIC MULTIPLE			350.0 G 2	2.0			
					X IRRIGATION			350.0 G 2	16.0	6.8		
G3-00389PBL 07 08309 07843					11/09/984 S			FRAN 01/09/987	BURLINGTON NORTHER WELL	137.0	LR	IS 5 5 5
1 NW4NW4					DOMESTIC MULTIPLE			1300.0 G 2	1.0			
					X IRRIGATION			1300.0 G 2	548.0			
03-00988PBL 07 09988 09478					01/08/999 S			FRAN 01/09/987	BURLINGTON NORTHER WELL	140.0	LR	IS 5 5 5
1 NW4NW4					DOMESTIC MULTIPLE			1800.0 G 2	2.0			
					X IRRIGATION			1800.0 G 2	582.0			
03-10597PBL 07 10897 10377					05/20/970 S			FRAN 01/09/987	BURLINGTON NORTHER WELL	400.0	LR	03011031 5 5 5
1 NW4NW4					X IRRIGATION			4000.0 G	1427.0			
G3-24500PBL 07					05/07/975 S			FRAN 01/09/987	BURLINGTON NORTHER WELL	107.0	LR	02011130 5 5 5
1 NW4NW4					X IRRIGATION			1470.0 G	428.0			
G3-27029BEI 07					08/03/981 S			FRAN 01/09/987	BURLINGTON NORTHER WELL	300.0	LR	02011130 4 4 4
1 NW4NW4					X IRRIGATION			2700.0 G	1200.0			

06/08/87

15:11

DEPT OF ECOLOGY / HQ OLYMPIA WA

004



CONTROL R	SEC	OLD	OLD	OLD	DATE OF	S C A	CNTY	PERMIT	NAME	SOURCE OF APPROPRIATION	TRIBUTARY OF				
PTS P LOC. SF P00/P01 (CHG CH)	H	APPL	PCPM	CEPT	PRIORITY	T C M	USE	INST	C P S	ANNUAL	C R S	LRP	C S PRO-	TIME OF	9 8 8
							TYPE	QI	M U U	GA	M U U	AC	M U VIGOS	USE	1 A C
WATER RESOURCE INVENTORY AREA- 34															
TOWNSHIP - 09 RANGE - 29 E															
G3-04249C	29	04249	05694	04320	04/10/1962		FRAN	07/13/1962	PHILIP P F		WELL				
I	L2	BL2	PLAT OF RIVER HOMES	DOMESTIC SINGLE			C	10.0 G		5.4			AN		
				IRRIGATION			C	15.0 G		4.0		1.5	AN		
G3-06795C	29	06705	06368	04630	05/26/1963	E	FRAN	08/32/1963	KUFFEL C F		WELL				
I	L4	BL3	RIVER HOMES FRANK CO	DOMESTIC SINGLE			C	10.0 G		4.0			AEN		
G3-08765C	26	08785	06242	06344	06/09/1967		FRAN	01/09/1968	OLSON R L		WELL				
I	L5	BL3	PIPER HOMES ADD	DOMESTIC SINGLE			C	90.0 G 2		1.0			PH		
				IRRIGATION			C	90.8 G 2		8.0		1.5	PH	IS	
G3-00195C	26	11972			04/24/1971		FRAN	10/24/1972	PHILLIP ROBERT F		WELLS				
2	L2	BL3	PL PIVER HOMES IM GL2	DOMESTIC SINGLE			C	120.0 G 4		2.0	2		PH		
				STOCK WATERING			C	120.0 G 4		2.0	2		PH		
				REC & BEAUTIFICATION			C	120.0 G 4		9.0	2		PH	04011001	
				IRRIGATION			C	110.0 G 6		9.0	2	2.0	PH	04011001	
TOWNSHIP - 09 RANGE - 30 E															
G3-23403P	04				06/06/1974	S	FRAN	07/23/1975	MINNAHAN JAMES		WELL				
I	SE4	SE4		DOMESTIC SINGLE			C	400.0 G 3		2.0	2		PIMB		
				STOCK WATERING			C	400.0 G 3		1.0			PIMB		
				IRRIGATION			C	400.0 G 3		200.9		40.0	PIMB	01011231	
G3-25178P	04				01/14/1977	S	FRAN	10/23/1985	CONN MUT LIFE INS		WELL				
I	NU4	SE4	SE4	IRRIGATION			C	1600.9 G		715.0		137.0	PH	01011251	
G3-20718P	05				06/02/1971	S	FRAN	10/16/1985	BURLINGTON NORTHER WELLS			320.0	PH	02011331	
3	NE4	SW4	NE4	IRRIGATION			C	2700.0 C		1290.0					
G3-26536Z	05				04/16/1980	S	FRAN	10/16/1985	BURLINGTON NORTHER WELLS			70.0	PH	32011031	
I	NE4	SW4		IRRIGATION			C	900.0 S		260.0					
G3-27188P	05				06/25/1981		FRAN	07/07/1982	BURLINGTON NORTHER WELLS			105.0	S	MCIEBIKES	
3	NE4	SW4	NE4	IRRIGATION			C	945.0 C		420.0					
G3-07851CAL	06	07651A	07195A	060204	06/10/1945		FRAN	10/15/1965	ROGERS WALLA WALLA WELL						
I	SL-7			COMMERCIAL/INDUSTRIAL			C	650.0 G 2		1419.0	2			IS	2 2 0
				IRRIGATION			C	650.0 C 2		1419.0	2	50.0			2 2 2
G3-09194P	06	09196	06893		01/02/1968		FRAN	01/20/1969	ROGERS WALLA WALLA WELL						
I	GL-7			COMMERCIAL/INDUSTRIAL			C	180.0 G 3		90.0					
				COMMERCIAL/INDUSTRIAL			C	180.0 G 3		200.0	2				
				IRRIGATION			C	160.0 G 3		200.0	2	50.0			
G3-00932C	06	12306			11/29/1971		FRAN	12/25/1973	TIPPETT ROBERT A		WELL				
I	KL4	SE4	SE4	IRRIGATION			C	1200.0 G		675.0		135.0	MR	C3011101	
G3-22846PAL	06				03/13/1974		FRAN	12/21/1976	ROGERS WALLA WALLA WELLS						
2	SW4	SW4		COMMERCIAL/INDUSTRIAL			C	1060.0 G 2		1709.0	2		PH		2 2 0
				IRRIGATION			C	1060.0 G 2		1739.0	2	162.0	PH	C1011231	2 2 2
G3-24761P	06				01/24/1976	S	FRAN	10/23/1985	MINNEHAN JAMES F		WELL				
I	SC4	SW4	SW4	DOMESTIC SINGLE			C	30.0 G		1.0			PH		
G3-28268P	07				06/02/1972	S	FRAN	10/16/1985	BURLINGTON NORTHER WELLS						
2	SE4	GL-2		IRRIGATION			C	2500.0 G		1000.0		2.5	PH	02011031	
Q1-24674C	07				05/13/1975		FRAN	05/18/1976	AMERICAN FERT I CH WELL						
I	SW4	NC4		COMMERCIAL/INDUSTRIAL			C	100.0 G		5.0			PH		
G3-009310	08	11440			12/17/1970		FRAN	10/25/1973	TIPPETT ROBERT A		WELL				
I	SW4	SE4		IRRIGATION			C	1100.0 G		540.0		135.0	PH	C3011101	
G3-01043P	06	11650			03/01/1971	S	FRAN	11/14/1984	TIPPETT JANET C		WELLS				
2	NE4			IRRIGATION			C	1400.0 G		645.0		160.0	PH	IS	
G3-27581P	06				04/02/1985		FRAN	12/21/1983	TIPPETT JANET C		WELL				
I	NE4			DOMESTIC MULTIPLE			C	30.0 G		4.0			PH		
G3-24978C	09				05/04/1976	S	FRAN	12/15/1976	CONN MUT LIFE INS		WELL				
I	NE4	SE4		IRRIGATION			C	1600.0 G		835.0		160.0	PH	01011231	

CONTROL #	SEC	OID	OLD	OLD	DATE OF	S C A	ENTY	PERMIT	NAME	SOURCE OF APPROPRIATION	TRIBUTARY OF							
PTS	P	LDC	QF	POD/PCW	ICMG	CR1	PURPOSE OF USE	USE	INST	C P S	ANNUAL	C P S	IRR	C S	PRO-	TIME	CF	P P P
								TYPE	PI	M U U	QA	M U W	AC	M U	VZSO:	USE		I A C

## WATER RESOURCE INVENTORY AREA- 36

TUNINGHUR - 09 FANDE - 33 E

G3-25283P	09				03/21/1977	S			FRAN 10/23/1985	WORSHAM RONALD ET	WELL							
1	SW4NE4NW4							C	1440.0 G 2		2.0							
								C	1440.0 G 2		622.0			157.0			1K	01011231
G3-25297P	09				03/21/1977	S			FRAN 10/23/1985	COX HAROLD	WELL							
1	SW4NE4NW4							C	1440.0 G 2		2.0							
								C	1440.0 G 2		622.0			157.0			1PK	01011231
G3-25298P	09				03/21/1977	S			FRAN 09/25/1977	COX HAROLD	WELL							
1	NE4 NW4							C	100.0 G 3		2.0							
								C	100.0 G 3		2.0							
								C	100.0 G 3		24.0			5.0			1PK	01011231
G3-22243P	10				12/17/1973	S			FRAN 10/11/1985	CONN MUT LIFE INS	WELL							
1	SW4NW4							C	1390.0 G		481.0							
G3-24973C	10				05/04/1976	S			FRAN 12/15/1976	CONN MUT LIFE INS	WELL							
1	NW4SE4							C	1400.0 G		640.0							
G3-25286P	10				03/21/1977	S			FRAN 10/19/1985	WORSHAM RONALD	WELL							
1	NW4 NE4							C	1440.0 G 2		2.0							
								C	1440.0 G 2		622.0							
G3-20249C	15				06/02/1972	S			FRAN 06/03/1974	DWRLINGTON NORTHES	WELLS							
2	NE4, SE4							C	4320.0 G		1940.0							
G3-01348C	16	10813	10209		04/07/1970	S			FRAN 03/14/1971	WA ST O N R	WELLS							
5	S2NW4, E2SU4, N2SE4							C	5200.0 G 3		2720.0							
								C	5100.0 G 3		1710.0							
								C	5200.0 G 3		2720.0			520.0				
G3-013480	17	11112	10404		07/31/1970	S			FRAN 09/23/1971	COLUMBIA EAST	WELL							
1	SE4SE4							C	1200.0 G		681.4							
G3-202500	17				06/02/1972	S			FRAN 01/14/1974	BURLINGTON ROBYNS	WELL							
1	NE4NE4							C	1300.0 G		520.0							
G3-24369C	17				09/23/1975	S			FRAN 05/04/1976	DUGAS JAMES	WELL							
1	L-142 PL-COL I - SEJ							C	50.0 G		41.0							
G3-05073C	19	05075	DC622		12/52/1953	S			FRAN 05/22/1959	PASCO CITY OF	WELL							
1	GL1							C	350.0 G		300.0							
G3-22218C	19				11/30/1973	S			FRAN 04/12/1974	PONTAROLO FRANK	WELL							
1	NE4SE4SU4							C	13.0 G		1.3							
G3-00847S	20	00847			00305	00/00/1975			FRAN 7/7	NORTHEPN PACIFIC R	WELL							
1	SW4NW4							C	400.0 G		108.0							
G3-00944C	20	00946	00901		00305	07/03/1966			FRAN 01/06/1969	SEATTLE MAPOWARE	WELL							
1	NE4NW4SW4							C	146.0 G 3		50.0							
								C	104.0 G 5		50.0							
								C	144.0 G 3		16.0			4.0				
G3-04415C	20	04415	04235		02817	06/27/1954			FRAN 05/03/1957	CLOSE I N	WELL							
1	LI CLOSE AOD PASCO							C	15.0 G 2		4.0							
								C	15.0 G 2		4.0			1.0				
G3-0513-C	20	00132	04603		03301	03/04/1959			FRAN 06/23/1959	MUW I V	WELL							
1	12 CAROLE-LEE ADON							C	15.0 G		6.0							
G3-10440C	20	10640	10005		07614	02/10/1970			FRAN 12/11/1970	FANNING J U	WELL							
1	NE4 NW4 NE4							C	70.0 G 2		2.0							
								C	70.0 G 2		30.0			7.0				
G3-01238C	20	10665	10298		02/25/1970	S			FRAN 05/14/1971	FRONTIER MACHINERY	WELL							
1	S2							C	200.0 G 2		20.0							
								C	200.0 G 2		65.0			12.5				
G3-22447C	20				01/25/1974	S			FRAN 05/20/1974	PASCO CITY OF	WELL							
1	NE4 SW4							C	140.0 G 2		2.0							
								C	140.0 G 2		55.4			15.0				
G3-01176C	21	10693	09974		03/11/1970	S			FRAN 11/23/1970	COLUMBIA EAST	WELL							
1	SW4NE4NW4							C	765.0 G		645.0							

06/08/87

15:15

DEPT OF ECOLOGY / HQ OLYMPIA WA

006

CONTROL #	SEC	010 APPL	010 PEPM	OLD CEPT	DATE OF PRIORITY	S C A T C T	CNTV DATE	PERMIT DATE	NAME	SOURCE OF APPROPRIATION	TESTATORY OF		
SCP P	PTS P	DOE. OF FCD/PCU	(CHG CB)	PURPOSE OF USE	USE TYPE	IRST QI	C R S M U U	ANNUAL GA	C P S M U U	IRV AC	C S PPO- M W VIICG	TIME OF WSE	P S E I A C
WATER RESOURCE INVENTORY AREA- 36													
TOWNSHIP - 09 RANCE - 30 E													
G3-04909C	22	069C9	04681	J05571	10/17/963		FRAN	01/31/964	DIETRICH J	WELL			
1	SM4NH4			X	IRRIGATION		C	90.0 G	72.0		38.0	AE	IS
G3-00247PAL	22	10E43A			05/11/970		FRAN	01/25/973	TOMLINSON DAIRY FA WELLS				
J	S2				DOMESTIC MULTIPLE		C	3500.0 G 3	3.0			MR	01011231 2 2 0
				X	STOCK WATERING		C	3500.0 G 3	354.0			MR	01011231 2 2 0
				X	IRRIGATION		C	3500.0 G 3	1800.0		345.0	MR	01011231 2 2 2
G3-24724C	22				01/09/976		FRAN	05/15/974	PAIONAREZ JOE	WELL			
1	NE4SE4				DOMESTIC SINGLE		C	120.0 G 3	2.0	2		SP	
				X	STOCK WATERING		C	120.0 G 3	2.0	2		SP	
				X	IRRIGATION		C	120.0 G 3	124.0		24.0	IF	C3011031
G3-27049B	22				05/19/981		FRAN	10/17/982	BUCCEN RAY M	WELL			
1	E2SU4NE4			X	DOMESTIC MULTIPLE		C	300.0 G 2	13.4			PK	
				X	IRRIGATION		C	300.0 G 2	70.0		20.3	PK	IS
G3-06534C	27	94534	064C3	04810	10/30/962		FRAN	11/22/963	USDI EPA	WELL			
I	NH4 SE4				DOMESTIC SINGLE		C	230.0 G 2	114.6	2		AN	
					HEAT EXCHANGE		C	230.0 G 2	114.6	2		AN	
G3-00247PBL	27	10563B			05/11/970		FRAN	01/25/973	TOMLINSON DAIRY FA WELL				
1	E2SU4				DOMESTIC MULTIPLE		C	3500.0 G 3	3.0			MR	01011231 2 2 0
				X	STOCK WATERING		C	3500.0 G 3	336.0			MR	01011231 2 2 0
				X	IRRIGATION		C	3500.0 G 3	1806.0		345.0	MR	01011231 2 2 2
G3-24863B	27				02/26/981		FRAN	04/02/982	EASTERN WA ID LETT WELL				
1	SE4SU4			X	DOMESTIC SINGLE		C	70.0 G 2	1.0			PM	
				X	IRRIGATION		C	70.0 G 2	17.5		5.0	PM	IS
G3-27795C	27				03/14/984		FRAN	03/29/985	WESTERN FARM SEPV	WELL			
1	SE4NU6				DOMESTIC SINGLE		C	100.0 G 2	25.0	2		SRK	
					COMMERCIAL/INDUSTRIAL		C	100.0 G 2	25.0	2		SRK	
G3-00247PBL	28	PTIAL	05497	06071	01/17/768		FRAN	05/28/768	DUNGERMEY C P	WELL			
1	NH4NU4SE4				DOMESTIC MULTIPLE		C	150.0 G	8.0			RNE	
G3-20149C	28				04/35/972		FRAN	06/27/973	SPOONER HENRY B JU WELL				
1	NH4 NE4 SE4			X	DOMESTIC MULTIPLE		C	30.0 G 2	7.0			HNPTPN	03011031
				X	IRRIGATION		C	30.0 G 2	5.0		1.0		
G3-23824C	28				06/28/974		FRAN	06/25/975	REISINGER LESLIE M WELL				
1	SEA SEA			X	DOMESTIC SINGLE		C	35.0 G 3	2.0	2		R	
				X	STOCK WATERING		C	35.0 G 3	2.0	2		R	
				X	IRRIGATION		C	35.0 G 3	8.56		2.0	P	01011231
G3-23828C	28				06/28/974		FRAN	06/25/975	REISINGER BENNETH WELL				
1	SE4 SE4			X	DOMESTIC SINGLE		C	70.0 G 3	2.0	2		R	
				X	STOCK WATERING		C	70.0 G 3	2.0	2		R	
				X	IRRIGATION		C	70.0 G 3	34.07		6.5	R	01011231
G3-24839C	28				03/26/976		FRAN	09/08/976	MANH W F	WELL			
1	SU3SE4			X	IRRIGATION		C	250.0 G	52.41		10.0	PK	IS
G3-27363P	28				07/01/982		FRAN	10/24/983	LAURENCE ROBERT S	WELL			
1	NH4SE6				DOMESTIC MULTIPLE		C	110.0 G	23.5			SRK	
G3-2777EB	28				02/27/984		FRAN	12/06/984	JOHNSON GENEVIE	WELL			
1	LOT 1 BL 12 CRSH ADDN PATCO			X	DOMESTIC SINGLE		C	60.0 G 2	1.0			SRK	
				X	IRRIGATION		C	60.0 G 2	22.0		5.5	SRK	IS
G3-27864P	28				07/31/984		FRAN	03/29/985	PASCO CITY OF	WELL			
1	NU4SU4				IRRIGATION		C	250.0 G	40.0		10.0	SRK	IS
G3-08151C	29	08241	07739	05857	08722/968		FRAN	01/18/977	CLARKES HOSPITAL	WELL			
I	111 815 SYLVESTER PK ADD			X	DOMESTIC MULTIPLE		C	50.0 G 2	10.0	2		A	
				X	IRRIGATION		C	50.0 G 2	10.0	2	.3	A	IS
G3-27943P	30				01/14/985		FRAN	10/31/985	PASCO CITY OF	WELL			
1	ME4SU4			X	IRRIGATION		C	250.0 G	40.0		10.0	SPK	IS
G3-22727C	31				03/08/974		FRAN	10/10/974	PASCO CITY OF	WELL			
1	GL-7				IRRIGATION		C	73.0 G	34.4		7.61	PK	03010930
S3417900C	31	17906	13179	11660	05/13/983		FRAN	09/17/983	PASCO CITY OF	COL R (WALIUA LK)			PACIFIC OCEAN
1	GL8				DOMESTIC MUNICIPAL		C	35.0 C	7000.0	S		SO	

06/08/87

15:16

DEPT OF ECOLOGY / HQ OLYMPIA WA

007

CONTROL #	SEC #	OID APPL	OLD PERM	OLD CERT	DATE OF PERMITS	S C A T C M	CNTY	PERMIT DATE	NAME	SOURCE OF APPROPRIATION	TRIBUTARY OF		
SUP P	PTS P	LOC. OF POD/POW	(CHG C#)	PURPOSE OF USE	USE TYPE	Q1	C R S M U U	ANNUAL C P S QA	C P S M U U	IPD AC	C S PRO- N U VISOS	TIME OF USE	R P E I A C

## WATER RESOURCE INVENTORY AREA- 31

TOWNSHIP - 09 RANGE - 25 E

1 NW6NE4

HIGHWAY  
ENVIRONMENTAL QUALITYC 450.0 G 2  
C 450.0 G 2

TOWNSHIP - 09 RANGE - 29 E

S4-01217C 28 20104 13102  
1 GL 7 & 802/15/967  
FISH PROPAGATION  
PIC & BEAUFICATIONBENT 02/29/968 BENTON CO PK-REC D UKN SPRS  
N 1.0 C 2  
N 1.0 C 2

COL R (WALL LK)

S4-279413 28  
1 SW402/15/982  
IRRIGATIONBENT 03/02/983 BENTON CO PK-REC D COL P (WALLULA LK)  
C 1.0 C 2 16.0 4.0 4.0 4.0

PACIFIC OCEAN

G4-26844N 31  
1 NE4SW406/25/980  
IRRIGATIONBENT 01/08/981 KENNEWICK SCH DI # UELL  
C 50.0 G 40.0

04011C31

G4-28825B 31  
1 NW4SW411/06/985  
IRRIGATIONBENT 03/11/996 LOS CHUPCH UELL  
C 40.0 G 2.2

04011C01

G4-27559P 32  
1 NE4NE407/16/981  
DOMESTIC MULTIPLEBENT 09/07/982 KENNEWICK CITY OF UELL  
C 3500.0 G 5823.0

KP

G4-26252C 33  
1 NW4SW406/01/979  
IRRIGATIONBENT 06/22/980 KENNEWICK SCH 015 WELL  
C 50.0 G 25.0

04011C01

G4-04533C 35 04539 04372  
2 CL103/97 02/27/957  
DOMESTIC MUNICIPALBENT 11/19/957 KENNEWICK CITY OF INFILTRATION TR  
C 13500.0 C 5600.0S4-23963C 35  
1 GL 105/06/975  
IRRIGATIONBENT 05/28/975 BENTON CO PK-REC COL 9 (WALLULA LK)  
C 1.5 C 2 10.0 13.5 5

PACIFIC OCEAN

G3-20015C 36  
1 NW4SW403/09/972  
IRRIGATIONBENT 06/16/973 WA ST HIGHWAY COMM WELL  
C 120.0 G 75.0

04011C31

TOWNSHIP - 09 RANGE - 30 E

G4-01390C 31 01390 01248  
5 GL-201805 02/23/950  
DOMESTIC MUNICIPALBENT 08/23/950 KENNEWICK CITY OF KELIS/INFILTRATION TR  
C 4950.0 G 4800.0S4-25479C 31  
1 SW4SW406/10/977  
DOMESTIC MUNICIPALBENT 12/05/978 KENNEWICK CITY OF COL R (WALLULA LK)  
C 55.7 C 2 10400.0 5

PACIFIC OCEAN

06/08/87

15:20

DEPT OF ECOLOGY / HQ OLYMPIA WA

002

CONTROL #	SEC 3	OLD APPL	OLD PERM	OLD CERT	DATE OF PROPRIETY	S C A T C M	CNTY	PERMIT DATE	NAME	SOURCE OF APPROPRIATION	TRIBUTARY OF		
WATER RESORCE INVENTORY AREA	PTS P	LOC. OF PCO/PGU	(CHG CS)	PURPOSE OF USE	USE TYPE	INST 01	C P S H U U	ANNUAL GA	C P S H U U	IRR AC	C S PFO- M U VESOC	TIME OF USE	P P P : A C
WATER RESOURCE INVENTORY AREA 36													
TOWNSHIP - 09 RANGE - 30 E													
S3W10704C	33	10704	10192	07203 03/12/970	DOMESTIC MUNICIPAL			FRAN 03/04/971	PASCO PORT OF	WEIL			
1	SW4 SE4			X IRRIGATION				C 375.0 G 2	196.0				
								C 375.0 G 2	13.0		3.0	HP HR	01011231
G3-01149CAL	33	11111A	10403A	07731/970 S	IRRIGATION			FRAN 09/13/971	COLUMBIA EAST	WELL	495.0	PH	03011101 2 2 2
1	SE4NE4			X				C 4500.0 G	2568.0				
G3-24314C	33			01/24/975	STOCK WATERING			FRAN / /	STORY JOEL C	WELL			
1	SW4NE4NW4			X IRRIGATION				C 750.0 G 2	1.0			RNI	
								C 750.0 G 2	362.0		73.0	RNI	E1011231
G3-01349CBL	34	11111B	10403B	07731/970 S	IRRIGATION			FRAN 09/23/971	COLUMBIA EAST	WEIL	495.0	PH	03011101 2 2 2
1	SW4NE4			X				C 4500.0 G	2568.0				
G3-20442C	34			12/11/972	DOMESTIC MULTIPLE			FRAN 01/25/974	WILL CECIL C	WELL			
1	S2 SW4 SE4			X IRRIGATION				C 750.0 G 2	116.0			PH	
								C 750.0 G 2	81.0		10.0	PH	02011101
G3-00673C	35	12071		07713/971	DOMESTIC GENERAL			MALL 06/05/973	USCE	WELL			
1	SE4 SE4			X IRRIGATION				C 200.0 C 2	14.0			HPP	
								C 200.0 G 2	37.0		100.0	HPP	03011001
TOWNSHIP - 10 RANGE - 28 E													
G3-01021C	02	01021	01302	00310 10/25/946	DOMESTIC SINGLE			FRAN 08/11/950	USBR	WELL			
1	GL4							C 30.0 G	20.0			A	
G3-27465B	12			03/04/983	DOMESTIC SINGLE			FRAN 11/07/983	YOUNG JOHN R	WELL			
1	NE4SE4			X IRRIGATION				C 108.0 G 2	1.0			HYDE	
								C 108.0 G 2	42.0		12.0	MIK	IS
G3-241530	13			01/27/979	DOMESTIC SINGLE			FRAN 07/03/979	LUNDRIAN MAPIOM H	WELL			
1	L-3 B-1 RIVERPIDGE ESTATES			X STOCK WATERING				C 20.0 G 3	2.0			WID	
								C 20.0 G 3	2.0			PID	
								C 20.0 G 3	2.0		.75	WID	01011101
G3-27504P	13			04/07/963	DOMESTIC MULTIPLE			FRAN 01/06/984	SANDEBSON GEORGE	WELL			
1	LOT A RIVER PIDGE ESTATES							C 100.0 C	29.0			PRK	
TOWNSHIP - 10 RANGE - 29 E													
G3-25354P	01			04/06/977 S	DOMESTIC MULTIPLE			FRAN 10/12/965	OANOEIL SCG FARMS	WELLS			
3	SE4SW4 6 NE4SE4			COMMERCIAL/INDUSTRIAL				C 150.0 G 2	6.0			LK	
								C 150.0 C 2	2.0			LK	
G3-24208P	06			04/04/979	DOMESTIC MULTIPLE			FRAN 11/20/979	BETA GROUP/BOLAND	WELL			
1	PU 168 BL 18 C 5 P							C 80.0 G	2.0			PH	
G3-03730C	10	03730	03530	02300 08/10/954 E	DOMESTIC GENERAL			FRAN 01/14/955	USBR	WELL			
1	NW4NW4							C 18.0 G	28.6				
G3-00286C	19	00266	00176	00753 04/22/946	DOMESTIC MULTIPLE			FRAN 10/22/946	USBR	WELL			
1	SW4SE4							C 100.0 C	100.0				
G3-27907JAL	25			10/03/964	IRRIGATION			FRAN 10/31/965	BURLINGTON NORTHER WELLS		450.0	PH	IS 2 2 2
4	S2SE4							C 4500.0 G	1800.0				
G3-27251P	24			04/09/982	COMMERCIAL/INDUSTRIAL			FRAN 03/04/963	BURLINGTON NORTHER WELLS				
1	SE4SE4							C 30.0 G	20.0			PH	
G3-27907JSL	24			10/03/964	IRRIGATION			FRAN 10/31/965	BURLINGTON NORTHER WELLS		450.0	PH	IS 2 2 2
1	S2NW4							C 4500.0 G	1800.0				
G3-00823P	25	12502		02/23/972 S	COMMERCIAL/INDUSTRIAL			FRAN 10/23/965	POREGRO CO/BURLINGO	WELL			
1	SE4SU4NE4							C 35.0 C	19.0			PH	
G3-20237P	25			04/02/972 S	IRRIGATION			FRAN 10/16/965	BURLINGTON NORTHER WELLS		70.0	PH	IS 2 2 2
1	SU4SU4							C 600.0 G	280.0				
G3-24328PAL	27			03/05/975 S	IRRIGATION			FRAN 07/10/965	BURLINGTON NORTHER WELLS				
1	NE4							C 9995.0 G	2220.0		3.33	PH	IS 2 2 2
G3-01063C	18	06596	06200	01/29/963	IRRIGATION			FRAN 04/12/963	BHOCOTTI WILLIAM	WELLS	180.0	B	IS
2	NW4, E2SE4SU4							C 1750.0 G	800.0				
G3-26021B	29			07/27/978				FRAN 08/30/979	JOB NORDERT	WELL			

06/08/87

15:18

DEPT OF ECOLOGY / HQ OLYMPIA WA

008

**REFERENCE 10**

## EXHIBIT 5-14

FORM NO 9-1904-A

SITE NO. \_\_\_\_\_

Recorded by \_\_\_\_\_

U.S. DEPT. OF THE INTERIOR  
GEOLOGICAL SURVEY  
WATER RESOURCES DIVISION  
GROUND WATER SITE INVENTORY  
SITE SCHEDULE

Date \_\_\_\_\_

Check One \_\_\_\_\_ English \_\_\_\_\_ Metric Units

## GENERAL SITE DATA I01

SIM Mnt No 5 19 RG Number R-0 Transaction T= A D M V \*  
add, delete, modify, omitted

Site-Type 2= C D H I M P T W \* Data Reliability 3= C U L M \* Reporting Agency 4= \*  
collector, drain, sinkhole, connector, multiple, pond, tunnel or, well shaft li=li checked, unchecked, insectos net, mineral concrete, date

Project No. 5= \* District 8= \* State 7= \* County (or town) 8= \*

Latitude 9= \* Longitude 10= \* Lat-Long Accuracy 11= S F T M \*  
deg min sec deg min sec He. 5 mc 10 mc, etc

Local Number 12= \* Land Net Loc. 13= S T R \*  
1/4 1/4 1/4 section, township, range, merid

Location Map 14= \* Scale 15= \*

Altitude 16= \* Method of Measurement 17= A L M \* Accuracy 18= \*  
altimeter, level, map

Topo Setting 19= D C E F H K L Ø P S T U V W \* Hydrologic Unit (OWOCI) 20= \*  
depression, stream, dune, flat, hilltop, sink, swamp, offshore, sediment, hillside, terrace, undulating, valley, upland channel, flat, draw

Date of First Construction/Completion 21= \* Use of Site 23= A O E G H Ø M P R S T U W X Z \*  
month day year anode, dam, geo- seismic, heat, observ. mine, oil or, recharge, raprem, test, unused, with: waste, destroyed thermal, reservoir, alien, gas, drawal

Use of Water 24= A B C D E F H I M N P R S T U Y Z \*  
air cond., bottling, commercial, domestic, power, fire, domestic, irrigation, medicinal, industrial, public, recreation, stock, institution, unused, detail, other supply

Secondary Water Use 25= \* Tertiary Use of Water 26= \* Depth of Hole 27= \* Depth of Well 28= \* Source of Depth Date 29= \*

Water Level 30= \* One Measured 31= \* Source 33= \*  
month day year

Method of Measurement 34= A C E G H L M R S T V Z \*  
axline, calibrated, estimated, pressure, calibrated, geophysical, manometer, reported, new, electric, calibrated, other tape measure, geoph. logs, tape, electric tape

Site Status 37= D F G H Ø P R S T V X Z \*  
dry, flowing, nearby, nearby, obstruction, pumping, recently, nearby, nearby, foreign, waste water, other, recently, flowing, pumped, pumping, recently, pumped, substance, effect

Source of Geohydrologic Data 36= \* Pump Used 35= \* Measuring Point 266= \* Measuring Point Date 267= \*  
no month day year

## OWNER IDENTIFICATION I11

R=158 \* T= A D M \* Date of Ownership 159# \*  
add, delete, modify month day year

Name: Last 161= \* First 162= \* Middle Initial 163= \*

## OTHER SITE IDENTIFICATION NUMBERS I11

R=189 \* T= A D M \* Ident 190# \* Assigner 191= \*  
add, delete, modify

New Card Same R & T Ident 190# \* Assigner 191= \*

## SITE VISIT DATA I11

R=185 \* T= A O M \* Date of Visit 187# \* Name of Person 188= \*  
add, delete, modify month day year

## FIELD WATER QUALITY MEASUREMENTS I11

R=192 \* T= A D M \* Date 1930 \* Geohydrologic Unit 195# \*  
add, delete, modify month day year

New Card Same R thru 195 Temperature 196# 0 0 0 1 0 \* Degree C 197= \*

Conductance 196# 0 0 0 9 5 \*  $\mu$ Mhos 197= \*

Other (STORET) Parameter 196# \* Value 197= \*

Other (STORET) Parameter 196# \* Value 197= \*

## FOOT NOTES:

① Source of Data Codes:

S Ø Ø A R L G Z  
reporting, driller, owner, other gov't, other logs, geologist, other agency reported

## USGS well records

9/30 - 21, 22, 27, 28

ENTER COMMAND &gt;RUN MARCIA

LOCAL NO. =09N/30E-21C01  
LATITUDE =461508  
LONGITUDE =1190402  
DATA LOCATION =C  
WELL DEPTH = 125.00  
WELL USE =W  
NO.1 WATER USE =I  
NO.2 WATER USE =  
DATE DRILLED =09/ /1970  
OPENING TOP = 78.00  
OPENING BOTTOM = 118.00  
OPENING DIAMETER = 16.00  
OPENING TOP = 120.00  
OPENING BOTTOM = 125.00  
OPENING DIAMETER = 16.00  
OWNER'S NAME =COLUMBIA E , PARTNERSHIP  
DATE OWNED =09/24/1970

LOCAL NO. =09N/30E-22E01  
LATITUDE =461504  
LONGITUDE =1190310  
DATA LOCATION =C  
WELL DEPTH = 110.00  
WELL USE = ?  
X NO.1 WATER USE =  
NO.2 WATER USE =  
DATE DRILLED = / /1962  
OPENING TOP = 0.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 0.00 ?  
OWNER'S NAME =DIETRICH , JOHN  
DATE OWNED = / /

*Land fill well ?*

LOCAL NO. =09N/30E-22J01  
LATITUDE =461447  
LONGITUDE =1190208  
DATA LOCATION =C  
WELL DEPTH = 142.00  
WELL USE =W  
NO.1 WATER USE =I  
NO.2 WATER USE =  
DATE DRILLED =02/24/1976  
OPENING TOP = 132.00  
OPENING BOTTOM = 142.00  
OPENING DIAMETER = 12.00  
OWNER'S NAME =PALOMAREZ , J  
DATE OWNED =02/24/1976

LOCAL NO. =09N/30E-22J02  
LATITUDE =461443  
LONGITUDE =1190216  
DATA LOCATION =C  
WELL DEPTH = 128.00  
WELL USE =W  
NO.1 WATER USE =N  
NO.2 WATER USE =  
DATE DRILLED =04/20/1972



OPENING TOP = 90.00  
OPENING BOTTOM = 128.00  
OPENING DIAMETER = 16.00  
OWNER'S NAME = TOMLINSON , DAIRY FARMS  
DATE OWNED = 05/08/1972

LOCAL NO. = 09N/30E-22K01 \*  
LATITUDE = 461439  
LONGITUDE = 1190216  
DATA LOCATION =  
WELL DEPTH = 138.40  
WELL USE = W  
NO.1 WATER USE = H  
NO.2 WATER USE =  
DATE DRILLED = 8/ 7/1979  
OPENING TOP = 133.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 6.00  
OWNER'S NAME = PALMAREZ , JOE  
DATE OWNED = 8/ 8/1979

LOCAL NO. = 09N/30E-22L01  
LATITUDE = 461443  
LONGITUDE = 1190216  
DATA LOCATION = C  
WELL DEPTH = 145.00  
WELL USE = W  
NO.1 WATER USE = 1  
NO.2 WATER USE =  
DATE DRILLED = 06/ /1974  
OPENING TOP = 90.00  
OPENING BOTTOM = 140.00  
OPENING DIAMETER = 16.00  
OWNER'S NAME = TOMLINSON , DAIRY FARMS  
DATE OWNED = 07/ /1974

\* Including one irr. well

LOCAL NO. = 09N/30E-22R01 \*  
LATITUDE = 461433  
LONGITUDE = 1190210  
DATA LOCATION =  
WELL DEPTH = 139.00  
WELL USE = W  
NO.1 WATER USE = H  
NO.2 WATER USE =  
DATE DRILLED = 3/22/1983  
OPENING TOP = 139.00 ?  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 6.00  
OWNER'S NAME = MARQUEZ , GILBERT  
DATE OWNED = 3/24/1983

---

LOCAL NO. = 09N/30E-23M01  
LATITUDE = 461449  
LONGITUDE = 1190148  
DATA LOCATION = C  
WELL DEPTH = 157.00  
WELL USE = W  
NO.1 WATER USE = 1  
NO.2 WATER USE =  
DATE DRILLED = 08/ /1982

OPENING TOP = 0.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 0.00  
OWNER'S NAME =USBR  
DATE OWNED =03/24/1955

---

LOCAL NO. =09N/30E-27F01  
LATITUDE =461405  
LONGITUDE =1190250  
DATA LOCATION =  
WELL DEPTH = 120.00  
WELL USE =W  
X NO.1 WATER USE =N  
NO.2 WATER USE =  
DATE DRILLED =11/ 9/1982  
OPENING TOP = 115.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 8.00  
OWNER'S NAME =WESTERN FARM , SERVICE  
DATE OWNED =12/28/1982

LOCAL NO. =09N/30E-27G01  
LATITUDE =461405  
LONGITUDE =1190221  
DATA LOCATION =C  
WELL DEPTH = 98.00  
WELL USE =W  
NO.1 WATER USE =1  
NO.2 WATER USE =  
DATE DRILLED =09/26/1975  
OPENING TOP = 83.00  
OPENING BOTTOM = 88.00  
OPENING DIAMETER = 16.00  
OPENING TOP = 88.00  
OPENING BOTTOM = 93.00  
OPENING DIAMETER = 16.00  
OPENING TOP = 93.00  
OPENING BOTTOM = 98.00  
OPENING DIAMETER = 16.00  
OWNER'S NAME =ALDERSON  
DATE OWNED =11/13/1975

LOCAL NO. =09N/30E-27H01 ✕  
LATITUDE =461407  
LONGITUDE =1190216  
DATA LOCATION =  
WELL DEPTH = 93.00  
WELL USE =W  
NO.1 WATER USE =H  
NO.2 WATER USE =  
DATE DRILLED = 3/17/1977  
OPENING TOP = 88.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 6.00  
OWNER'S NAME =CREEK , KEN  
DATE OWNED = 3/22/1977  
OWNER'S NAME =JOHNSON&BUXBAUM, --  
DATE OWNED = 2/24/1986

LOCAL NO. =09N/30E-27K01

9/30 - 27K1

LATITUDE =461355  
LONGITUDE =1190229  
DATA LOCATION =C  
WELL DEPTH = 121.00  
WELL USE =  
NO.1 WATER USE = ?  
X NO.2 WATER USE =  
DATE DRILLED =06/ /1951  
OPENING TOP = 0.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 0.00  
OWNER'S NAME =USDI Interior?  
DATE OWNED =06/ /1951

LOCAL NO. =09N/30E-28H01  
LATITUDE =461408  
LONGITUDE =1190327  
DATA LOCATION =  
WELL DEPTH = 97.60  
WELL USE =U  
X NO.1 WATER USE =U - New owner - used 100 or in future X  
NO.2 WATER USE =  
DATE DRILLED = 6/19/1980  
OPENING TOP = 92.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 6.00  
OWNER'S NAME =KEYES & SCANLAN,--  
DATE OWNED = 6/19/1980  
OWNER'S NAME =YENNE ,AL (New)  
DATE OWNED = 2/27/1986

LOCAL NO. =09N/30E-28K01 \*  
LATITUDE =461358  
LONGITUDE =1190343  
DATA LOCATION =C  
WELL DEPTH = 110.00  
WELL USE =W  
NO.1 WATER USE =H  
NO.2 WATER USE =  
DATE DRILLED =10/ /1961  
OPENING TOP = 0.00  
OPENING BOTTOM = 0.00  
OPENING DIAMETER = 0.00 ?  
OWNER'S NAME =BUMGARNER ,CLINTON  
DATE OWNED =10/ /1961

LOCAL NO. =09N/30E-28M01  
LATITUDE =461355  
LONGITUDE =1190420  
DATA LOCATION =C  
WELL DEPTH = 70.00  
WELL USE =W  
X NO.1 WATER USE =1  
NO.2 WATER USE =  
DATE DRILLED =04/09/1985  
OPENING TOP = 57.00  
OPENING BOTTOM = 70.00  
OPENING DIAMETER = 8.00  
OWNER'S NAME =PASCO ,CITY OF  
DATE OWNED =04/09/1985

Wells Within About One Mile of Disposal Site


*What's code*

<u>USCS designation</u>	<u>Owner</u>	<u>Use</u>
9/30-22E1	John Dietrich (disposal site) <sup>11</sup>	Irrigation of cover crop
9/30-16A1	Charlie Cox	Irrigation of potato farm (first season of use)
9/30-16F1 <i>have</i>	US Bur. Reclamation	Observation well
9/30-16K1	Charlie Cox	Irrigation of potato farm (first season of use)
9/30-16M1	Charlie Cox	Irrigation of potato farm (first season of use)
9/30-21F1	Columbia West	Irrigation well - unused
9/30-28H1	Devon Dall	<sup>120</sup> Domestic, stock-water and irrigation well
9/30-28H2	Howard Craven	Well never used - no development of land
9/30-28H3	Rada Construction	Well used only intermitter in making of septic tanks, dry wells, etc.
9/30-28J1	Welch Garage wrecking yard	Little used
9/30-28J2	Spooner Hotel	Commercial use for domestic and sanitary water
9/30-28J3	Cunningham	Domestic well
9/30-28K1	Rasmussen	Domestic well
9/30-28K2 and 3	Bonnie Brac Motel and Bunnarner home	Commercial and domestic wells
9/30-27B1	Dave Whitehead	Stock water
9/30-22Q1	Alderson	Domestic well
9/30-23N1	US Bur Reclamation	Observation well
9/30-26D1	US Bur Reclamation	Observation well
9/30-22J1	Tomlinson Dairy	commercial use in dairy
9/30-22K1	Tomlinson Dairy	not in use. Too low capacity.
9/30-27K1	Bonnoville Power Administration	Sanitary and local irrigation











**REFERENCE 11**

**Bearing and distance from section or subdivision corner**


 3





## REFERENCE 12










**REFERENCE 13**





, edited, and published by the Geological Survey  
 USGS and NOS/NOAA  
 y by photogrammetric methods from aerial  
 rs taken 1973. Field checked 1974. Map edited 1979  
 and 10,000-foot grid ticks: Washington coordinate  
 uth zone (Lambert conformal conic)  
 er Universal Transverse Mercator grid ticks,  
 shown in blue. 1927 North American datum  
 n the predicted North American Datum 1983,  
 projection lines 19 meters north and  
 east as shown by dashed corner ticks  
 ashed lines indicate selected fence and field lines  
 rally visible on aerial photographs



ROAD CLASSIFICATION

Primary highway, hard surface	Light-duty road, hard or improved surface
Secondary highway, hard surface	Unimproved road
Interstate Route	U. S. Route
	State Route

**GLADE, WASH.**  
 SE/4 ELTOPIA 15' QUADRANGLE  
 N4615-W11900/7.5

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS  
 FOR SALE BY U. S. GEOLOGICAL SURVEY, DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092



**REFERENCE 14**



# ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

## CONTACT REPORT

Agency/  
Organization: Washington Dept. of Ecology - EASTERN DISTRICT OFFICE

Address: SPOKANE, WA

Contact: LINDY CHRISTIAN

Phone: 509-456-2926

FROM: CHARLES F. PITZ

TO:

SUBJ: WATER RIGHTS INFORMATION IN VICINITY OF PASCO LANDFILL

DATE: 5/28/87

CC:

Phone call to get information on acreage irrigated by  
some selected wells in a 3 mile radius of the  
Pasco Landfill (from 5/87 Water Rights Computer Listing)

9/30 - 16	-	520	acres
9/30 - 21C	-	268	acres
9/30 - 22K	-	26	acres
9/30 - 22L	-	345	acres
9/30 - 23M	-	315	acres
9/30 - 28M	-	10	acres

Charles F. Pitz

**REFERENCE 15**



E P A PROJECT

ECOLOGY AND ENVIRONMENT, INC.

CONTACT REPORT: REGION X-SEATTLE

TO: Tomlinson Farms, Inc

PERSON CONTACTED: Jean Tomlinson

PHONE: (509) 545-4896

CONTACTED BY: Gloria Skinner

SUBJECT: Ownership & Origin of Tomlinson Dairy Pond

DATE: 5/29/87, 10:17 a.m

CC:

COMMENTS:

Pond is a man-made lagoon. to collect waste farm water which is recycled as irrigation.

Owned by: Tomlinson Farms, Inc.  
Gilbert & Jean Tomlinson, Owners  
3682 Selph Landing Rd.  
Pasco, WA 99301

*Gloria Skinner*

**REFERENCE 16**

E P A PROJECT

ECOLOGY AND ENVIRONMENT, INC.

CONTACT REPORT: REGION X-SEATTLE

TO: *Franklin County Fire Marshall*  
PERSON CONTACTED: *Don Carter*

PHONE: *(509) 545-3586*

CONTACTED BY: *Gloria Skinner*

SUBJECT: *Re: Fire Hazard and Explosive Potential at Pasco Sanitary  
Landfill and Resource Recovery Corporation.*

DATE: ~~*6-5-87*~~ *6-1-87*

CC:

COMMENTS:

*Material of botanical origin is burned in a controlled  
manner above ground. There is no other source for above  
ground fire hazard.*

*To his knowledge, the buried material presents no  
explosive potential.*

*Gloria Skinner*



## ecology and environment, Inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

PRELIMINARY SITE INSPECTION  
REPORT OF RESOURCE RECOVERY  
CORPORATION  
PASCO, WASHINGTON

TDD R10-3408-22

Report Prepared By: Ecology and Environment, Inc.  
Project Leader: Christopher Nadler  
Date: January 8, 1985

Submitted To: J.E. Osborn, Regional Project Officer  
Field Operations and Technical Support Branch  
U.S. Environmental Protection Agency  
Region X  
Seattle, Washington

PRELIMINARY  
SITE INSPECTION REPORT

Resource Recovery Corporation  
TDD R10-8408-22

Site Name/Address

Resource Recovery Corporation  
Pasco Sanitary Landfill  
Kahlotus Road and Highway 12  
Pasco, WA 99301

Investigation Participants

Peter Evers, Ecology and Environment, Inc. (E&E), (206) 624-9537  
Rich Brooks, Ecology and Environment, Inc. (E&E), (206) 624-9537  
Chris Nadler, Ecology and Environment, Inc. (E&E), (206) 624-9537  
Mike Gallagher, Washington Department of Ecology (WDOE),  
Environmentalist II, (206) 459-5515

Principal Site Contacts

Larry Dietrich, Owner and Operator,  
Pasco Sanitary Landfill, (509) 547-4802  
John Zillich, Project Manager, J-U-B Engineers (JUB),  
(509) 783-2144  
Ron West, Operator, Resource Recovery Corp., (206) 767-0355

Date of Inspection

9/12/84 0800 hrs.

1.0 Introduction

Resource Recovery Corporation (RRC)/Pasco Sanitary Landfill (PSL) has been identified by the U.S. Environmental Protection Agency (EPA) Region X and WDOE from preliminary assessment screening as requiring additional information to accurately profile the nature and extent of past waste disposal activity at the site. E&E has been requested by EPA under Technical Directive Document No. R10-8408-22 to conduct a site inspection and evaluate the facility's status within the Agency's Uncontrolled Hazardous Waste Site Program. This report summarizes the results of E&E's preliminary site inspection and is divided into the following sections:

- o Site Location
- o Hydrogeology
- o Disposal Practices
- o Past Investigations
- o Observations

## 2.0 Site Location

The PSL is located 1.5 miles northeast of Pasco, Washington in the SW 1/4 of Section 5 and the NW 1/4 of Section 22, Townshio 09 north, Range 30 east, Willamette Meridian, Franklin County (Figure 2.1). The PSL has been operated as a landfill since 1956 (1). The facility has received orimarily municipal wastes with the exception of a period from 1972 to 1980 when it was also operated as a regional hazardous waste site.

The site has been owned and operated by Larry Dietrich since January 1981. Records indicate that John Dietrich owned the site from 1956 to 1981. The site was leased to the Resource Recovery Corporation during the time period when it was operated as a regional hazardous waste site (1).


The average elevation of the site is 410 feet above mean sea level (MSL) with the land sloping approximately 1 to 3 percent to the west-southwest. The land in the general vicinity of the site is rural (population approximately 35 people within a 1 mile radius) intermixed with irrigated agricultural fields and range land.

## 3.0 Hydrogeology

The generalized description of the geologic units underlying PSL is presented in Table 3.1.

TABLE 3.1  
DESCRIPTION OF GEOLOGIC UNITS (2,3,4)

Geologic Unit Sub-Unit	Depth (feet)	Description	Permeability (cm/sec)
Eolian Sand and Silt	surface	Light brown. Very fine sands and silts.	$10^{-3}$ - $10^{-5}$
Touchet Formation	0-40	Light to medium brown. Very fine to medium grained sands. Occasionally slight to very silty.	$10^{-3}$ > $10^{-5}$
Pasco Gravels	40-60	Dark grey. Locally fine to coarse grained sands with occasional gravel.	$>10^{-3}$
Ringhold Formation Ringhold Sands	60-100	Dark grey. Medium to coarse grain with gravel. Gravel increasing and getting coarser with depth.	$>10^{-3}$
Ringhold Gravels	100-110	Tan gravel with sand.	$>10^{-3}$
Ringhold Clays	>110-140	Blue clay.	
Yakima Basalt	>140	Basalt	$10^{-2}$ - $10^{-5}$



# LEGEND

CONTOUR INTERVAL: 20 FEET

SCALE: 1 INCH=1 MILE



## FIGURE 2.1

TITLE: VICINITY MAP  
PASCO SANITARY LANDFILL

CLIENT: EPA REGION X

R.D.D. R10-8408-22

ecology and environments, inc.  
SEATTLE, WASHINGTON



Groundwater beneath the site occurs in the Yakima Basalt sequence and the overlying sedimentary materials. The disposal site will have a potential impact only on the groundwater in the sedimentary materials (2). The depth to the water table aquifer is approximately 55 feet below the average land surface (approximately 355 feet MSL), thus the surface of the groundwater tops the Ringhold Sands and is in the Pasco Gravels (2). Groundwater movement is in a general southwesterly direction toward the Columbia River (Figure 3.1). The major use of groundwater in the area is crop irrigation. The site has a semi-arid climate with an overall negative water budget of approximately 32-inches per year (3). The two year 24-hour rainfall is 0.8-inches, with July being the driest month having less than 0.2-inches of rainfall (6).

#### **4.0 Disposal Practices**

The PSL site was operated as an open burning dump from 1956 to 1971 (1). The primary wastes accepted were municipal wastes which were dumped on the ground surface and periodically burned. In 1971 the operation was changed from an open burning dump to a sanitary landfill; the burning activity stopped and the refuse was periodically covered with soil (1).

Resource Recovery Corporation leased a portion of the landfill in 1972 from the landowner John Dietrich and began operating a regional hazardous waste site. The site was managed by Larry Dietrich (John's son) as an employee of the corporation. The operator accepted and disposed of hazardous wastes in sub-sites from 1973 through 1981 under WDOE Permit #5301 issued March 21, 1973. The majority of hazardous wastes were accepted from 1972 to 1974; Table 4.1 summarizes the types, quantities and disposal locations (if known) for this period. The sanitary landfill operation also continued during the period of time Resource Recovery leased the site. In addition, in 1974 a sewage evaporation lagoon was constructed for the disposal of septic tank wastes (Figure 3.1).

Resource Recovery Corporation operated the site until January 1981, at which time the operation lease terminated and all interests RRC had in the operation reverted to the Dietrichs. Larry Dietrich has operated the site as a sanitary landfill since 1981.

#### **5.0 Past Investigations**

##### **5.1 WDOE Investigation**

In September 1973, the WDOE ordered an investigation of RRC operation at PSL. This was initiated because of the concerns of local farmers and the WDOE relating to the potential effects of the materials buried at the site on the local agricultural crops. The investigation included a site visit to ascertain current site conditions, waste types disposed of at the site and their potential impact on groundwater, as well as possible air contamination. No samples of the wastes or groundwater were collected or analyzed by the WDOE.




TABLE 4.1  
WASTE QUANTITIES DISPOSED OF  
AT PSL BY RRC

Location(5)	Description(7) (Size*/Lining)	Waste Type(2.8)	Estimated Quantity (2,5,8)	Units
Site A	100'x100' bottom unlined top lined	acids	544	drums
		aromatic tars	160-248	drums
		carcinogenics (unspecified)	9	drums
		caustics	8,774	drums
		cedium	11	drums
		metal finishing	244-304	drums
		oil sludge	433	drums
		paint	10,258-24,200	drums
		pesticides	425	drums
		pesticide containers (empty)	791-863	drums
Site B	50'x50' bottom unlined top lined	2,4-D manufacturing	2,011-5,080	drums
Site C	75'x75' bottom unlined top lined	acids	7,000	gallons
		acid metal cleaning	2,301,560	pounds
		lime phenol	684,967	gallons
		metal cleaning	185,162	gallons
		metal finishing	17,000-35,724	gallons
		metal finishing	1,460,602-1,949,652	pounds
Site D	75'x75' bottom unlined top lined	aromatic tar	499,270	pounds
		cutting oil	76,350-84,300	gallons
		fertilizer manufacturing	228,288	pounds
		oily sludge	6,000-66,340	gallons
		paint	72,475-497,418	pounds
		paint	66,516-95,711	gallons
		plywood resin	1,393,380-2,215,440	pounds
		solvents	12,648	gallons
Site E	unknown bottom and top lined	barium with mercury	10,500-11,582	tons
Unknown	unknown	acid sludges	1,000	gallons
		acid wash solution	312,350	pounds
		benzoic acid and tar	176,000	pounds
		chemistry lab reagents	1	drum
		chrome rinse water	700,901	pounds
		DCP tar	8,790	gallons
		etching solution	1,914	barrels
		lime sludge	80-160	drums
		MCPA bleed	104,318-327,000	gallons
		MCPA tar	2,965-3,037	drums
			939	drums
			2,813	barrels
			680	pails
		metal casing wastes	3,300-5,760	drums
		misc. lab chemicals	29	sm. containers
		NH <sub>4</sub> <sup>+</sup> and NaOH		
		chemical solutions	17,238	gallons
		oily sludge	166,680	pounds
		other miscellaneous	435	drums
		pesticide containers	1,045	each
		resin manufacturing	392,553	gallons
		solid caustic soda	44,550	pounds
		woud treatment/preservative	294,662	gallons
			238	drums

\*The depths of the burial sites are unknown. All linings are 4 mil polyethylene and all sites are covered with soil.

The WDOE prepared a report which was published in December 1973. In their report, WDOE stated that the site was in an excellent location for ground disposal of industrial solid wastes, if the proper safeguards are observed. Further, that the arid climate prevents the leaching of solid wastes disposed into the ground and is conducive to on-site concentration and desiccation of liquid wastes. They also concluded that since the water table is relatively shallow, it is not acceptable to dispose of liquid wastes directly to the ground in unlined pits or trenches. The state decided that the probability of air pollution at the site was considered to be low. Figure 5.1 explains the site structure during this WDOE investigation. The report concluded the following recommendations:

- o all materials received for disposal at the site shall be recorded as to the type, chemical composition and quantity;
- o abandoned disposal sites must be permanently monumented;
- o all trenches intended for the disposal of hazardous wastes should be lined.

## 5.2 J-U-B Engineers Reports

J-U-B Engineers have been contracted by the operator of the PSL as consultants to plan and implement the groundwater quality program at the PSL site. The engineering firm has completed 2 major reports on the PSL.

J-U-B Engineers first report (June 1981) responded to several issues which the WDOE raised in a letter to the PSL on 18 February 1981. The report included the following (9):

- o a discussion of the percolation of septic wastes and their impact on hazardous wastes which were disposed of on-site;
- o documentation procedures of septic wastes received at PSL;
- o direction and velocity of groundwater flow;
- o current groundwater monitoring program;
- o estimated the transmissivity and permeability of the water table aquifer at the site.

The authors concluded that:

- o the industrial waste disposal sites are not being saturated by lateral movement of waste waters from the sewage lagoons;
- o the groundwater flow direction and quality have been determined near the landfill site but an additional well is needed at the southern boundary to verify flow;
- o a groundwater monitoring program has been established to determine current and future impacts of site operations.

In July 1983, J-U-B Engineers published a second report on the PSL which was a summary of past quarterly groundwater sampling. This report included:

- o a summary of the construction of six groundwater monitoring wells completed in January 1982 (Figure 5.2);
- o tentatively identified the direction of groundwater flow;
- o summarized the analytical results of quarterly groundwater samples collected by J-U-B Engineers from January 1982 to March 1983;
- o compared the groundwater quality to health effect limits.

J-U-B Engineering concluded the following:


- o existing monitoring wells are located in such a manner that they will detect any leachate migration from the industrial and solid waste areas and the sewage evaporation lagoon;
- o the wells are constructed to obtain water from the upper 20 feet of the water table aquifer where contaminants from the landfill would be most readily observed;
- o sampling results for health-effect related parameters show concentration to be largely below detection limits and in all cases below the EPA allowable contaminant levels.

There are a number of discrepancies between the disposal sub-site descriptions in Figure 5.1 and 5.2. The exact size and location of each disposal sub-site is in question as is the identification numbering system. Table 5.1 is a cross reference of both parties numbering systems.

TABLE 5.1  
CROSS REFERENCE OF J-U-B AND WDOE  
DISPOSAL SUB-SITE NUMBERING SYSTEM (10)


J-U-8	WDOE	Description
A	1	Disposal of containerized wastes
B	6	Disposal of containerized herbicide wastes
C and D	2 to 5	Evaporation ponds
E	8 and 9	Unlined trenches for disposal of chloralkali sludges
F <sub>1</sub>	NI	Solid Waste fill area
F <sub>2</sub>	7	Solid Waste fill area
NI	10 to 14	Never used

NI - Not Identified



Location (See Map)	Description	Amount
1	For disposal of containerized wastet such as: Paint watter (sludge, pigments, resins, colors) Empty pesticide containers Wood treatment wastes Etching solutions Metal casting wastet	10,258 drums 800 drums 1,100 drums 160 drums 3,300 drums
	All wastes are in containers and buried under 5 feet of soil. There have been no known liquid discharges from this location.	
2	An unlined pond for evaporation of water from simple wastes such as:  Lime sludge and ammonia water	327,000 gal.
3	A lined pond for evaporation of water from: chrome plating wastes	8,790 gal.
4	A lined pond for evaporation of water from: miscellaneous liquids - not yet used to any extent	
5	A roughed out pond for later use. Being used as temporary storage for chlor-alkali sludge pending preparation of trenches 10, 11, and 12.	
6	For disposal of containerized herbicide wastes such as:  2,4-D tar MCPA Bleed other miscellaneous	2,011 drums 1,017 drums 435 drums
	The drums are covered with 5 feet of soil. There have been no known discharges from this location.	
7	The currently active landfill operation.	
8, 9	Unlined trenches for temporary disposal of chlor-alkali sludge. The sludge will be moved to lined trenches 10, 11, and 12.	
10, 11, 12	Proposed site for disposal of chlor-alkali sludges. The lined trenches will be constructed as outlined in Figure 2.	
13, 14	Space for future landfill operations.	

FIGURE 5.1  
AREAS OF DISPOSAL OCTOBER 1973 (2)



**FIGURE 5.2**  
PASCO SANITARY LANDFILL  
WASTE DISPOSAL AND WELL LOCATIONS(5)

### 5.3 Preliminary Assessments (PA) and Site Inspections (SI)

Table 5.2 summarizes the PA's and SI's which have been conducted to date.

TABLE 5.2  
SUMMARY OF PA AND SI ACTIVITIES (11)

Activity	Date	Responsible Agency
Identification of Potential Problem	07-79	EPA
SI	07-79	EPA
PA	08-79	EPA
SI	04-80	WDOE
PA	04-84	JRB Associates
Hazard Ranking		
System Score	04-84	Unknown
SI	09-84	E&E

### 6.0 Observations

On September 12, 1984, a site inspection was conducted at PSL. The site inspection began at 0800. Mike Gallagher (WDOE), Larry Deitrich (PSL), John Zillich (J-U-B Engineering), Peter Evers (E&E), and Richard Brooks (E&E), were present. The inspection included a discussion about background information, a site tour, and sample collection. It was noted during the site tour that no drums or hazardous wastes were visible at the surface and no color stains or leachate seeps were observed.

Three groundwater samples were collected during the inspection. The results of the analysis of these samples are contained in Appendix A. This data indicates that there is no organic contamination from the site reaching the groundwater which was sampled. The inorganic analysis revealed higher levels of heavy metals in the well which has been identified as the control well (Table 6.1).



TABLE 6.1  
COMPARISON OF SELECTED HEAVY METALS (ug/l)

Metal	Upgradient Well	Well No. 3	EPA Recommended Level*
Aluminum	102,000	41,500	---
Arsenic**	39	28	50
Barium	1,531	785	1,000
Beryllium	7	5 U	1.17
Cadmium	1.9	1 U	10
Chromium	106	46	50
Cobalt	170	5 U	---
Copper**	280	120	1,000
Iron	199,900	97,450	---
Lead	160	70	50
Manganese	4,380	1,694	---
Nickel**	162	63	13.4
Vanadium	302	200 U	---
Zinc	514	207	5,000

\*Compiled from a) National Interim Primary Drinking Water Regulations, EPA Office of Water Supply, 1979.

b) Water Quality Criteria Documents, Federal Register, Vol. 45, No. 231, November 1980.

U - Under detection limit (listed next to value).

\*\* - Refer to cover memorandum to the inorganic data for discussion of these values.


This data suggests that:

- o the actual direction of groundwater flow is possibly not in the direction which has been tentatively identified;
- o hazardous wastes may have been disposed of upgradient of the control well which have not been identified in past reports and may have migrated to this well.

Because of this uncertainty, it can not be determined if the inorganic contamination is originating on or off-site.

## 7.0 Discussion

One factor that may effect the quality of analytical data of the groundwater samples collected from the PSL is the monitoring well design (Figure 7.1). The wells are screened at 2 intervals separated by approximately 15 feet. The water samples are obtained by placing a



**FIGURE 7.1**  
**WELL NO. 2 (5)**  
**INSTALLED 1-14-82**

pump halfway between these screens. Utilizing this design there is no assurance that:

- o equal amounts of water are extracted from each screened interval;
- o the depth from which the sample is being collected is accurately known;
- o the concentrations of contaminants are representative of the actual groundwater conditions due to the potential unequal volumes of water are extracted from each screened interval.

It is difficult to compare previous groundwater analytical data available and establish possible trends of contamination at the PSL. The samples collected by J-U-B Engineers were analyzed for different parameters than those collected by E&E. The analytical data which is contained in the J-U-B report is incomplete in that the units of measurement are not given. The exception to this are the metals data which are contained in Table 7.1, these metals were analyzed for by both firms.

**TABLE 7.1**  
**COMPARISON OF PREVIOUS ANALYTICAL DATA METAL (ug/l)**

Well Number	Date Sampled	Arsenic	Barium	Cadmium	Chromium	Lead
Upgradient	17-18/02/84	10 U	100 U	1 U	5 U	5 U
	12/09/84	39**	1,631	1.9	106	160
3	17-18/02/84	10 U	100 U	1 U	5 U	5 U
	12/09/84	28**	785	1 U	46	70

U - Under detection limit (listed next to value)

\*\* - To cover memorandum to the inorganic data for discussion of these values

It can be interpreted from the data contained in Table 7.1 that the levels of metal contamination have increased between samplings. Records of materials disposal of on-site indicate that at least 3 of the 5 metals described in Table 7.1 were disposed at the PSL. These include: Barium, Chromium, and Lead.

Evaluation and Recommendation - Resource  
Recovery Corporation

Based on existing data and documentation, further investigation is needed to assess the potential hazard associated with this site. Because of the toxic nature of many of the compounds (e.g. 2,4-D, MCPA) which have been disposed of at PSL and the observed increase of contaminants in the on-site and control wells, the following recommendations should be considered:

- 1) Further investigation should be carried out to determine the validity of the site's disposal records. There are a number of variations relating to the quantities and types of wastes which have been disposed of at the PSL.
- 2) Resample all of the wells on-site and analyze for the compounds identified on the EPA Priority Pollutant List including dioxins.
- 3) Monitor the wells and determine whether or not seasonal fluctuations (due to local irrigation demands) of groundwater flow exist which could transport contaminants toward the on-site control well.
- 4) Collect subsurface soils samples adjacent to all waste disposal areas to determine whether or not wastes are leaching from these areas.
- 5) Contact the chemical toilet firm which is disposing waste water in the sewage lagoon and determine if any chemicals which they are using are hazardous.

These recommendations should be pursued on a ~~medium~~ <sup>HIGH</sup> priority basis.

6) GROUNDWATER FLOW DIRECTION SHOULD  
BE FURTHER INVESTIGATED.

7) Determine if wastes disposed of  
"upgradient" of control well.

8) Determine if inorganic contamination is  
originating from on or off site.

## REFERENCES

1. Doug Hansen, Director, EPA Air and Hazardous Materials Division; Letter to the EPA files; August 2, 1979.
2. Resource Recovery Corporation Industrial Disposal Site Evaluation, Report by Washington Department of Ecology December 1973 contained in the Region X EPA ERRIS site files.
3. HRS User's Manual (draft) 10 June 1982, document developed for U.S. Environmental Protection Agency by the Mitre Corporation (pg. 15).
4. Basalt Waste Isolation Project, Annual Report - Fiscal Year 1980, RHO-BW1-80-100, document prepared for U.S. Department of Energy under contract OE-AC06-77RL01030 by Rockwell International.
5. Summary Report - Groundwater Quality in the Vicinity of the Pasco Landfill, by J-U-B Engineers, Kennewick, Washington, July 1983. Contained in the Region X U.S. EPA ERRIS site files.
6. The Climatic Atlas of the United States, U.S. Department of Commerce, June 1958. (reprinted by NOAA, 1979).
7. Personal communication with Larry Dietrich during site inspection.
8. EPA Files on RRC. Monthly wastes accepted, reports from RRC to WDOE, May 1973 to December 1974.
9. Evaluation of the Pasco Sanitary Landfill Waste Disposal Practices, J-U-B Engineers, Kennewick, Washington, June 1981.
- 7 10. Telephone Conversation. Mike Gallagher, Environmentalist II, WDOE, Chris Nadler, FIT Investigator, E&E, Seattle, 11 December 1984, 135D.
11. EPA files.

APPENDIX A

QUALITY ASSURANCE MEMOS AND ANALYTICAL DATA SHEETS  
RESOURCE RECOVERY CORPORATION, PASCO, WASHINGTON

CASE NO.: 3206

SITE INSPECTION - 9/12/84

ECOLOGY AND ENVIRONMENT, INC., SEATTLE



## ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

### M E M O R A N D U M

DATE: November 7, 1984

TO: John Osborn, FIT RPO  
EPA, Region X

THRU: Dave Buecker, FIT RPM  
E&E, Seattle

FROM: Jim Farr, Senior Chemist  
E&E, Seattle

SUBJ: QA of Sample Results for Case 3206

I have finished my review of data for Case 3206. Chemtech analyzed three water samples for inorganics. I believe the data to be acceptable except for the following comment:

Duplicate data for arsenic, copper, and nickel gave high RPD's. I have starred all results on the data sheets that are associated with the duplicate. The starred values (\*) suggest a larger imprecision for measuring that particular element. The imprecision would suggest error of  $\pm 44\%$  for arsenic,  $\pm 46\%$  for copper, and  $\pm 24\%$  for nickel.

Otherwise all results are as reported. Please call me if you have questions.

CC: Peter Evers  
JF:pc  
attachment

APPENDIX A

U.S. EPA-Contract Laboratory Program  
Sample Management Office  
P.O. Box 818 - Alexandria, VA 22313  
703/557-2490; FTS: 8-557-2490

EPA Sample No.

MT 9043

Date 10-24-84

INORGANIC ANALYSIS DATA SHEET

LAB NAME CHEMTECH

CASE NO. 3206

LAB SAMPLE ID. NO. G-2-322-01

QC REPORT NO. 322

Elements Identified and Measured

Matrix Low Water

ug/L or mg/kg (Circle One)

1. Aluminum	<u>102000</u>	13. Manganese	<u>NR</u>
2. Antimony	<u>420-20 u</u>	14. Manganese	<u>4380</u>
3. Arsenic	<u>39*</u>	15. Mercury	<u>40-2 0.2u</u>
4. Barium	<u>1631</u>	16. Nickel	<u>162*</u>
5. Beryllium	<u>7</u>	17. Potassium	<u>NR</u>
6. Cadmium	<u>0.15m 1.9</u>	18. Selenium	<u>2</u>
7. Calcium	<u>NR</u>	19. Silver	<u>40 10u</u>
8. Chromium	<u>106</u>	20. Sodium	<u>NR</u>
9. Cobalt	<u>170</u>	21. Thallium	<u>410-10u</u>
10. Copper	<u>280*</u>	22. Tin	<u>420-20u</u>
11. Iron	<u>199900</u>	23. Vanadium	<u>302</u>
12. Lead	<u>160</u>	24. Zinc	<u>514</u>
Cyanide	<u>40 10u</u>	Percent Solids	<u>NR</u>

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: \_\_\_\_\_

Lab Manager E. Hector



U.S. EPA Contract Laboratory Program  
Sample Management Office  
P.O. Box 918 - Alexandria, VA 22313  
703/557-2490 FTS: 8-557-2490

EPA Sample No.

MS 9044

Date 10-24-81

INORGANIC ANALYSIS DATA SHEET

LAB NAME CHEMTECH

CASE NO. 3206

LAB SAMPLE ID. NO. 62-322-02

CC REPORT NO. 322

Elements Identified and Measured

Matrix Low Water

ug/L or mg/kg (Circle One)

1. Aluminum	203	13. Magnesium	NR
2. Antimony	<20 20u	14. Manganese	<10 10u
3. Arsenic	<10 10u	15. Mercury	<0.2 0.2u
4. Barium	<100 100u	16. Nickel	<40 40u
5. Beryllium	<5 5u	17. Potassium	NR
6. Cadmium	<1 1u	18. Selenium	<2 2u
7. Calcium	NR	19. Silver	<10 10u
8. Chromium	<10 10u	20. Sodium	NR
9. Cobalt	<50 50u	21. Thallium	<10 10u
10. Copper	<50 50u	22. Tin	<20 20u
11. Iron	163	23. Vanadium	<200 200u
12. Lead	<5 5u	24. Zinc	<10 10u
Cyanide	<10 10u	Percent Solids	NR

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments:

Lab Manager

U.S. EPA Contract Laboratory Program  
Sample Management Office  
P.O. Box 818 - Alexandria, VA 22313  
703/557-2490 FTS: 8-557-2490

EPA Sample No.

MJ 9045

Date 10-24-84

INORGANIC ANALYSIS DATA SHEET

LAB NAME CHEMTECH

CASE NO. 3206

LAB SAMPLE ID. NO. G2-322-03

QC REPORT NO. 322

Elements Identified and Measured

Matrix Lw Water

ug/l or mg/kg (Circle One)

1. Aluminum	<u>41500</u>	13. Magnesium	<u>NR</u>
2. Antimony	<u>&lt;20 20u</u>	14. Manganese	<u>1694</u>
3. Arsenic	<u>28*</u>	15. Mercury	<u>&lt;0.2-0.2u</u>
4. Barium	<u>785</u>	16. Nickel	<u>63*</u>
5. Beryllium	<u>&lt;5 5u</u>	17. Potassium	<u>NR</u>
6. Cadmium	<u>&lt;1 1u</u>	18. Selenium	<u>2</u>
7. Calcium	<u>NR</u>	19. Silver	<u>&lt;10 10u</u>
8. Chromium	<u>42</u>	20. Sodium	<u>NR</u>
9. Cobalt	<u>&lt;50 50u</u>	21. Thallium	<u>&lt;10 10u</u>
10. Copper	<u>120*</u>	22. Tin	<u>&lt;20 20u</u>
11. Iron	<u>97450</u>	23. Vanadium	<u>&lt;200-200u</u>
12. Lead	<u>70</u>	24. Zinc	<u>207</u>
Cyanide	<u>&lt;10 10u</u>	Percent Solids	<u>NR</u>

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: \_\_\_\_\_

Lab Manager E. Hecht



## ecology and environment, inc.

108 SOUTH WASHINGTON, SUITE 302, SEATTLE, WASHINGTON 98104, TEL. 206-624-9537

International Specialists in the Environmental Sciences

### M E M O R A N D U M

DATE: November 27, 1984

TO: John Osborn, FIT RPO, USEPA Region X

FROM: Andy Hafferty, Chemist, E&E, Seattle  
J. Farr, Sr. Chemist, E&E, Seattle

THRU: D. Buecker, FIT RPM, E&E, Seattle

SUBJ: QA of Data; Case 3206 - Resource Recovery Corp.

REF: TDD R10-8410-06

The review of three water samples sent to PEDCO Environmental, Inc., Cincinnati, OH, has been completed. These samples were given a full organics analysis.

Sample numbers are J2271, J4548, and J4549.

Volatile surrogate recoveries were all within QC limits.

Half of the pesticide surrogate recoveries were outside QC limits.

Sample Dibutyl Chlorendate (67-114)

J2271	69%
J4548	22% out
J4549 (field blank)	120% out
Lab Blank	95%

There is no explanation for the out of control recovery reported in the field blank.

Eleven out of 36 surrogate recoveries of the Semi-volatile (BNA) fraction were out of control. The samples were not re-extracted and re-analyzed as required by the CLP. The lab blank showed three out of six recoveries outside of QC limits. The field blank, J4549, had two out of six recoveries out of control. Again, there is NO explanation for these unacceptable blank results.

All pesticide matrix spike and matrix spike duplicates (MS/MSD) were within recovery (REC) and reproducibility (RPO) quality control limits.

Two out of 10 volatile MS/MSD recoveries were outside QC limits.

Seven out of 14 base/neutral MS/MSD recoveries were outside QC limits and all seven out of seven base/neutral MS/MSD RPD's were OUT of control.

Eight out of ten acid MS/MSD recoveries were outside QC limits and, including one 0 value, four out of five acid MS/MSD RPD's were OUT of control.

Methylene chloride and acetone in the volatiles lab blank and Bis (2-ethylhexyl) phthalate in the BNA lab blank were found at concentrations above the contract specified maximum.

Copies of the PEDCO lab summary sheets have been included in this report.

The laboratory was called on November 8, 1984 by Dr. James Farr (a copy of the telephone log has been included in this report) regarding missing spectra and the failure of the laboratory to carry out contract required re-extraction and re-analysis. The missing spectra have been received and added to the data package. The laboratory's response regarding the failure to re-examine the BNA fraction was that since no compounds were detected, repetitive analyses were unnecessary. The CLP clearly states that the laboratory must repeat the analyses without regard to the presence or lack of quantifiable analytes.

This is the second case of samples received from PEDCO with serious unexplained quality control anomalies. Please refer to the E&E, quality assurance memorandum dated November 2, 1984, regarding QA of Data from the Tulalip Indian Reservation, Case 3270.

The following list summarizes the recommendations regarding this data and the performance of the laboratory.

1. The Volatile and Pesticide data are acceptable.
2. The Semi-volatile data is unacceptable. If this data must be used, extreme caution should be exercised in drawing any conclusions based on these results.
3. The SMO should be notified regarding the continuing quality control problems at PEDCO Environmental, Inc.
4. PEDCO should be required to perform the work as specified in the CLP on all future work.

AH:pc  
Attachments  
CC: Bill Ritthaler  
Arnold Gahler

USEPA-SAMPLE MANAGEMENT OFFICE  
PO BOX 818 ALEXANDRIA, VA 22313

SAMPLE NO.  
J2271

## ORGANICS ANALYSIS DATA SHEET

LABORATORY NAME \_\_\_\_\_ PEDCO ENV.  
LAB SAMPLE ID NO \_\_\_\_\_ DT147  
SAMPLE MATRIX \_\_\_\_\_ WATER  
DATA RELEASE AUTHORIZED \_\_\_\_\_ *AN*

CASE NO: \_\_\_\_\_ 3204  
QC REPORT NO. \_\_\_\_\_  
CONTRACT NO. \_\_\_\_\_ 48-01-6779  
DATE SAMPLE RECEIVED \_\_\_\_\_ 9/13/84

## VOLATILES

CONCENTRATION \_\_\_\_\_ LOW  
DATE PREPARED \_\_\_\_\_ 9/13/84  
DATE ANALYZED \_\_\_\_\_ 9/13/84  
PER CENT MOISTURE \_\_\_\_\_ N/A  
CONCENTRATION/DIL. FACTOR \_\_\_\_\_ 0.2

PP#	CAS#	UG/L
(2V)	107-02-OACROLEIN	100U
(3V)	107-13-1ACRYLONITRILE	100U
(4V)	71-43-2SENEZENE	5U
(6V)	54-23-2CARBON TETRACHLORIDE	5U
(7V)	108-90-7CHLORO BENZENE	5U
(10V)	107-06-21,2-DICHLOROETHANE	5U
(11V)	71-55-61,1,1-TRICHLOROETHANE	5U
(13V)	75-34-31,1-DICHLOROETHANE	5U
(14V)	79-00-51,1,2-TRICHLOROETHANE	5U
(15V)	79-34-51,1,2,2-TETRACHLOROETHANE	10U
(16V)	75-00-3CHLOROETHANE	10U
(19V)	110-75-92-CHLOROETHYL VINYLETHER	10U
(23V)	67-66-3CHLOROFORM	5U
(29V)	75-35-41,1-DICHLOROETHENE	5U
(30V)	156-60-5TRANS-1,2-DICHLOROETHENE	5U
(32V)	73-87-51,2-DICHLOROPROPANE	10U
(33V)	10061-02-6TRANS-1,3-DICHLOROPROPENE	5U
	10061-01-05CIS-1,3-DICHLOROPROPENE	5U
(38V)	100-41-4ETHYLBENZENE	5U
(64V)	75-09-2METHYLENE CHLORIDE	5U
(65V)	74-87-3CHLOROMETHANE	10U
(66V)	74-83-9BROMOMETHANE	10U
(67V)	75-25-2BROMOFORM	10U
(48V)	75-27-4BROMODICHLOROMETHANE	5U
(49V)	75-69-4FLUOROTRICHLOROMETHANE	5U
(50V)	75-71-3DICHLOROFLUOROMETHANE	NA
(51V)	124-48-1CHLOROFLUOROMETHANE	5U
(85V)	127-18-4TETRACHLOROETHENE	5U
(86V)	108-88-3TOLUENE	5U
(87V)	79-01-6TRICHLOROETHENE	5U
(88V)	75-01-4VINYL CHLORIDE	10U
	67-64-1ACETONE	5U
	78-93-32-BUTANONE	5U
	75-15-0CARBON DISULFIDE	1U
	519-78-62-HEXANONE	5U
	108-10-14-METHYL-2-PENTANONE	5U
	100-42-5STYRENE	5U
	108-05-4VINYL ACETATE	5U
	1330-20-7TOTAL XYLENES	5U

## PESTICIDES

CONCENTRATION \_\_\_\_\_ LOW  
DATE EXTRACTED \_\_\_\_\_ 9/13/84  
DATE ANALYZED \_\_\_\_\_ 10/4/84  
PERCENT MOISTURE \_\_\_\_\_ N/A  
CONCENTRATION/DIL. FACTOR \_\_\_\_\_ 10

PP#	CAS#	UG/L
(89P)	309-00-2 ALORIN	.005U
(90P)	40-57-1 DIELDRIN	.005U
(91P)	57-74-9 CHLORDANE	.05U
(92P)	50-29-3 4,4'-DDT	.01U
(93P)	72-55-9 4,4'-DDE	.005U
(94P)	72-54-3 4,4'-DDE	.1U
(95P)	115-29-7 ALPHA-ENDOSULFAN	.005U
(96P)	115-29-7 BETA-ENDOSULFAN	.005U
(97P)	1031-07-8 ENDOSULFAN SULFATE	.01U
(98P)	72-20-8 ENDRIN	.005U
(99P)	7421-93-4 ENDRIN ALDEHYDE	.01U
(100P)	74-44-8 HEPTACHLOR	.005U
(101P)	1024-57-3HEPTACHLOR EPOXIDE	.005U
(102P)	319-84-6 ALPHA-BHC	.005U
(103P)	319-85-7 BETA-BHC	.005U
(104P)	319-84-8 DELTA-BHC	.005U
(105P)	58-89-9 GAMMA-BHC (LINCANE)	.005U
106P	53449-21-9PCB-1242	.05U
107P	11097-69-1PCB-1254	.1U
108P	11104-28-2PCB-1221	.1U
109P	11161-16-5PCB-1232	.05U
110P	12672-29-6PCB-1248	.1U
111P	11094-82-5PCB-1260	.1U
112P	12676-11-2PCB-1016	.2U
113P	8001-35-2TOXAPHENE	.05U

USEPA-SAMPLE MANAGEMENT OFFICE  
PO BOX 818 ALEXANDRIA, VA 22313

SAMPLE NO.  
J2271

0000028

ORGANICS ANALYSIS DATA SHEET

LABORATORY NAME \_\_\_\_\_ PEDCO ENV.  
LAB SAMPLE ID NO. \_\_\_\_\_ DT147  
SAMPLE MATRIX \_\_\_\_\_ WATER  
DATA RELEASE AUTHORIZED \_\_\_\_\_ *AQ*

CASE NO.: \_\_\_\_\_ 3206  
QC REPORT NO. \_\_\_\_\_  
CONTRACT NO. \_\_\_\_\_ 68-01-6779  
DATE SAMPLE RECEIVED \_\_\_\_\_ 9/13/84

SEMIVOLATILE COMPOUNDS

CONCENTRATION \_\_\_\_\_ LCM  
DATE EXTRACTED \_\_\_\_\_ 9/13/84  
DATE ANALYZED \_\_\_\_\_ 9/26/84  
PER CENT MOISTURE \_\_\_\_\_ N/A  
CONCENTRATION/DIL. FACTOR \_\_\_\_\_ 500

PPM	CASH	UG/L		PPM	CASH	UG/L			
(21A)	88-06-2	2,4,6-TRICHLOROPHENOL	10	J	(52B)	87-63-3	HEXACHLOROBUTADIENE	10	J
(22A)	59-50-7	P-CHLORO-M-CRESOL	10		(533)	77-47-4	HEXACHLOROCYCLOPENTADIENE	10	
(24A)	95-57-8	2-CHLOROPHENOL	10		(548)	73-59-1	ISOPHORONE	10	
(31A)	120-33-2	2,4-DICHLOROPHENOL	10		(55S)	91-20-3	NAPHTHALENE	10	
(34A)	105-67-9	2,6-DIMETHYLPHENOL	10		(56B)	98-95-3	NITROBENZENE	10	
(57A)	88-75-5	2-NITROPHENOL	20		(62B)	86-30-4	N-NITROSODIPHENYLAMINE	10	
(58A)	100-02-7	4-NITROPHENOL	50		(63B)	621-64-7	N-NITROSODIPROPYLAMINE	10	
(59A)	51-23-5	2,4-DINITROPHENOL	50		(66B)	117-81-7	BIS(2-ETHYLHEXYL) PHTHALATE	530	
(60A)	534-52-1	4,6-DINITRO-O-CRESOL	20		(67B)	85-68-7	BENZYL BUTYL PHTHALATE	3	
(64A)	87-36-5	PENTACHLOROPHENOL	10		(68B)	84-74-2	DI-N-BUTYL PHTHALATE	17.4	
(65A)	108-95-2	PHENOL	10		(69B)	117-84-0	DI-N-OCTYL PHTHALATE	10	
	65-85-0	BENZOIC ACID	100		(70B)	84-66-2	DIETHYL PHTHALATE	10	
	95-48-7	2-METHYLPHENOL	5		(713)	131-11-3	DIMETHYL PHTHALATE	10	
	108-39-4	4-METHYLPHENOL	5		(72B)	56-55-3	BENZO(A)ANTHRACENE	10	
	95-95-4	2,4,5-TRICHLOROPHENOL	100		(73B)	50-32-3	BENZO(A)PYRENE	20	
(1B)	83-32-9	ACENAPHTHENE	10		(74B)	205-99-2	BENZO(B)FLUORANTHENE AND/	20	
(5B)	92-87-5	BENZIDINE	40		(75B)	207-08-9	BENZO(K)FLUORANTHENE OR	20	
(83)	120-82-1	1,2,4-TRICHLOROBENZENE	10		(76B)	218-01-9	CHRYSENE	20	
(9B)	118-74-1	HEXACHLOROBENZENE	10		(77B)	208-96-8	ACENAPHTHYLENE	10	
(123)	67-72-1	HEXACHLOROETHANE	10		(78B)	120-12-7	ANTHRACENE	10	
(18B)	111-44-4	BIS(2-CHLOROETHYL) ETHER	10		(79B)	191-24-2	BENZO(GHI)PERYLENE	20	
(20B)	91-58-7	2-CHLORONAPHTHALENE	10		(80B)	86-73-7	FLUORENE	10	
(25B)	95-50-1	1,2-DICHLOROBENZENE	10		(81B)	85-01-8	PHENANTHRENE	10	
(26B)	541-73-1	1,3-DICHLOROBENZENE	10		(82S)	53-70-3	DIBENZO(AH)ANTHRACENE	20	
(27B)	106-46-7	1,6-DICHLOROBENZENE	10		(83B)	193-39-5	INDENO(123-CD)PYRENE	20	
(23B)	91-94-1	3,3'-DICHLOROBENZIDINE	20		(84B)	129-00-0	PYRENE	10	
(35B)	121-14-2	2,4-DINITROTOLUENE	20			62-53-3	ANILINE	5	
(36B)	606-20-2	2,6-DINITROTOLUENE	20			100-51-6	BENZYL ALCOHOL	20	
(37B)	122-66-7	1,2-DIPHENYLHYDRAZINE	20			106-47-9	4-CHLOROANILINE	50	
(57B)	206-44-0	FLUORANTHENE	10			132-64-9	DIBENZOFURAN	10	
(40B)	7005-72-3	4-CHLOROPHENYLPHENYLETHER	10			91-57-6	2-METHYLNAPHTHALENE	20	
(61B)	101-55-3	4-BROMOPHENYLPHENYLETHER	10			88-74-4	2-NITROANILINE	100	
(42B)	39633-32-9	BIS(2-CHLOROISOPROPYL) ETHER	20			99-09-2	3-NITROANILINE	100	
(43B)	111-91-1	BIS(2-CHLOROETHOXY) METHANE	20	J		100-01-6	4-NITROANILINE	100	J

USEPA-SAMPLE MANAGEMENT OFFICE  
PO BOX 818 ALEXANDRIA, VA 22313

0000056

SAMPLE NO.  
J6543

## ORGANICS ANALYSIS DATA SHEET

LABORATORY NAME PEDCO ENV.  
LAB SAMPLE ID NO DT148  
SAMPLE MATRIX WATER  
DATA RELEASE AUTHORIZED AK

CASE NO: 3204  
OC REPORT NO.                       
CONTRACT NO. 68-01-6779  
DATE SAMPLE RECEIVED 9/13/84

## VOLATILES

CONCENTRATION LOW  
DATE PREPARED 9/13/84  
DATE ANALYZED 9/13/84  
PER CENT MOISTURE N/A  
CONCENTRATION/DIL. FACTOR 0.2

PP#	CAS#	UG/L
(2V)	107-02-SACROLEIN	100U
(3V)	107-13-1ACRYLONITRILE	100U
(4V)	71-43-2EENE	5U
(6V)	56-23-2CARBON TETRACHLORIDE	5U
(7V)	108-90-7CHLOROBENZENE	5U
(10V)	107-06-21,2-DICHLOROETHANE	5U
(11V)	71-55-61,1,1-TRICHLOROETHANE	5U
(13V)	75-34-31,1-DICHLOROETHANE	5U
(14V)	79-00-51,1,2-TRICHLOROETHANE	5U
(15V)	79-34-51,1,2,2-TETRACHLOROETHANE	10U
(16V)	75-00-3CHLOROETHANE	10U
(19V)	110-75-82-CHLOROETHYL VINYLETHER	10U
(23V)	67-66-3CHLOROFORM	5U
(29V)	75-35-41,1-DICHLOROETHENE	5U
(30V)	156-60-5TRANS-1,2-DICHLOROETHENE	5U
(32V)	78-87-51,2-DICHLOROPROPANE	10U
(33V)	10061-02-3TRANS-1,3-DICHLOROPROPENE	5U
	10061-01-0CIS-1,3-DICHLOROPROPENE	5J
(38V)	100-41-4ETHYLBENZENE	5U
(44V)	75-09-3METHYLENE CHLORIDE	5U
(45V)	74-87-3CHLOROMETHANE	10U
(66V)	74-83-98BROMOMETHANE	10U
(47V)	75-25-2BROMOFORM	10U
(48V)	75-27-4BROMODICHLOROMETHANE	5U
(49V)	75-49-4FLUOROTRICHLOROMETHANE	5U
(50V)	75-71-80ICHLOROIFLUOROMETHANE	NA
(51V)	124-48-1ICHLORODIBROMOMETHANE	5U
(85V)	127-18-4TETRACHLOROETHENE	5U
(86V)	108-88-3TOLUENE	5U
(87V)	79-01-3TRICHLOROETHENE	5U
(88V)	75-01-4VINYL CHLORIDE	10U
	67-64-1ACETONE	5U
	78-93-32-BUTANONE	5U
	75-15-0CARBON DISULFIDE	1U
	519-78-62-HEXANONE	5U
	108-10-14-METHYL-2-PENTANONE	5U
	100-42-5STYRENE	5U
	108-05-4VINYL ACETATE	5U
	1330-20-7TOTAL XYLENES	5U

## PESTICIDES

CONCENTRATION LOW  
DATE EXTRACTED 9/13/84  
DATE ANALYZED 10/4/84  
PERCENT MOISTURE N/A  
CONCENTRATION/DIL. FACTOR 10

PP#	CAS#	UG/L
(89P)	309-00-2 ALDRIN	.005U
(90P)	60-57-1 DIELDRIN	.005U
(91P)	57-74-9 CHLORDANE	.05U
(92P)	50-29-3 4,4'DDT	.01U
(93P)	72-55-9 4,4'DDE	.005U
(94P)	72-54-8 4,4'DDD	.1U
(95P)	115-29-7 ALPHA-ENDOSULFAN	.005U
(96P)	115-29-7 BETA-ENDOSULFAN	.005U
(97P)	1031-07-8 ENDOSULFAN SULFATE	.01U
(98P)	72-20-3 ENDRIN	.005U
(99P)	7421-93-4 ENDRIN ALDEHYDE	.01U
(100P)	76-44-3 HEPTACHLOR	.005U
(101P)	1024-57-3HEPTACHLOR EPOXIDE	.005U
(102P)	319-84-6 ALPHA-BHC	.005U
(103P)	319-85-7 BETA-BHC	.005U
(104P)	319-86-8 DELTA-BHC	.005U
(105P)	58-89-9 GAMMA-BHC (LINDANE)	.005U
106P	53469-21-9PCB-1242	.05U
107P	11097-69-1PCB-1254	.1U
108P	11106-25-2PCB-1221	.1U
109P	11141-16-5PCB-1232	.05U
110P	12672-29-6PCB-1248	.1U
111P	11096-82-5PCB-1260	.1U
112P	12676-11-2PCB-1016	.2U
113P	8001-35-2TOXAPHENE	.05U

USEPA-SAMPLE MANAGEMENT OFFICE  
PO BOX 818 ALEXANDRIA, VA 22313

0000057

SAMPLE NO.  
J4548

ORGANICS ANALYSIS DATA SHEET

LABORATORY NAME PEDCO ENV.  
LAB SAMPLE ID NO. DT148  
SAMPLE MATRIX WATER  
DATA RELEASE AUTHORIZED MA

CASE NO: 3206  
QC REPORT NO.           
CONTRACT NO. 68-01-6779  
DATE SAMPLE RECEIVED 9/13/84

SEMIVOLATILE COMPOUNDS

CONCENTRATION LOW  
DATE EXTRACTED 9/13/84  
DATE ANALYZED 9/26/84  
PER CENT MOISTURE R/A  
CONCENTRATION/DIL. FACTOR 500

PP#	CAS#	UG/L	PP#	CAS#	UG/L		
(21A)	88-06-2	2,4,6-TRICHLOROPHENOL	10	(528)	87-68-3	HEXACHLOROBUTADIENE	10
(22A)	59-50-7	P-CHLORO-M-CRESOL	10	(538)	77-47-4	HEXACHLOROCYCLOPENTADIENE	10
(24A)	95-57-8	2-CHLOROPHENOL	10	(548)	78-59-1	ISOPHORONE	10
(31A)	120-83-2	2,4-DICHLOROPHENOL	10	(558)	91-20-3	NAPHTHALENE	10
(34A)	105-67-9	2,4-DIMETHYLPHENOL	10	(568)	98-95-3	NITROBENZENE	10
(57A)	83-75-5	2-NITROPHENOL	20	(628)	86-30-6	N-NITROSOOIPHENYLAMINE	10
(SSA)	100-02-7	4-NITROPHENOL	50	(638)	621-64-7	N-NITROSOOIPROPYLAMINE	10
(59A)	51-28-5	2,4-DINITROPHENOL	50	(668)	117-81-7	BIS(2-ETHYLHEXYL) PHTHALATE	82.6
(60A)	534-52-1	4,6-DINITRO-O-CRESOL	20	(678)	85-68-7	BENZYL BUTYL PHTHALATE	2.8
(64A)	87-36-5	PENTACHLOROPHENOL	10	(638)	84-74-2	DI-N-BUTYL PHTHALATE	22.6
(65A)	103-95-2	PHENOL	10	(698)	117-84-0	DI-H-OCTYL PHTHALATE	10
	65-85-0	BENZOIC ACID	100	(708)	84-66-2	DIETHYL PHTHALATE	3.6
	95-48-7	2-METHYLPHENOL	5	(713)	131-11-3	0IMETHYL PHTHALATE	10
	108-39-6	4-METHYLPHENOL	5	(728)	56-55-3	BENZO(A) ANTHRACENE	10
	95-95-4	2,4,5-TRICHLOROPHENOL	100	(733)	50-32-3	BENZO(A) PYRENE	20
( IB)	83-32-9	ACENAPHTHENE	10	(748)	205-99-2	BENZO(B) FLUORANTHENE AND/OR	20
( 55)	92-87-5	BENZIDINE	40	(758)	207-08-9	BENZO(K) FLUORANTHENE OR	20
( 88)	120-32-1	1,2,4-TRICHLOROBENZENE	10	(768)	218-01-9	CHRYSENE	20
( 98)	118-74-1	HEXACHLOROBENZENE	10	(778)	208-96-8	ACENAPHTHYLENE	10
(12S)	67-72-1	HEXACHLOROETHANE	10	(788)	120-12-7	ANTHRACENE	10
(188)	111-44-4	BIS(2-CHLOROETHYL) ETHER	10	(793)	191-24-2	BENZO(GHI) PERYLENE	20
(208)	91-58-7	2-CHLORONAPHTHALENE	10	(803)	86-73-7	FLUORENE	10
(25S)	95-50-1	1,2-DICHLOROBENZENE	10	(818)	85-01-8	PHENANTHRENE	10
(268)	541-73-1	1,5-DICHLOROBENZENE	10	(828)	53-70-3	DIBENZO(AH) ANTHRACENE	20
(278)	106-46-7	1,4-DICHLOROBENZENE	10	(838)	193-39-5	INDENO(123-CD) PYRENE	20
(288)	91-94-1	3,3'-DICHLOROBENZIDINE	20	(848)	129-00-0	PYRENE	10
(358)	121-14-2	2,4-DINITROTOLUENE	20		62-53-3	ANILINE	5
(368)	606-20-2	2,6-DINITROTOLUENE	20		100-51-6	BENZYL ALCOHOL	20
(378)	122-66-7	1,2-DIPHENYLHYDRAZINE	20		106-47-8	4-CHLOROANILINE	50
(399)	206-44-0	FLUORANTHENE	10		132-64-9	DIBENZOFURAN	10
(408)	7005-72-3	4-CHLOROPHENYLPHENYLETHER	10		91-57-6	2-METHYLNAPHTHALENE	20
(418)	101-55-3	4-BROMOPHENYLPHENYLETHER	10		88-74-4	2-NITROANILINE	100
(423)	39638-32-9	BIS(2-CHLOROISOPROPYL) ETHER	20		99-09-2	3-NITROANILINE	100
(438)	111-91-1	BIS(2-CHLOROETHOXY) METHANE	20		100-01-6	4-NITROANILINE	100



USEPA-SAMPLE MANAGEMENT OFFICE  
PO BOX 818 ALEXANDRIA, VA 22313

00000093

SAMPLE NO.  
J4549

## ORGANICS ANALYSIS DATA SHEET

LABORATORY NAME PEDCO ENV.  
LAB SAMPLE ID NO. DT149  
SAMPLE MATRIX WATER  
DATA RELEASE AUTHORIZED [Signature]

CASE NO: 3206  
OC REPORT NO.           
CONTRACT NO. 68-01-6779  
DATE SAMPLE RECEIVED 9/13/84

## VOLATILES

CONCENTRATION LOW  
DATE PREPARED 9/13/84  
DATE ANALYZED 9/13/84  
PER CENT MOISTURE N/A  
CONCENTRATION/DIL. FACTOR 0.2

PP#	CASH	UG/L
(2U)	107-02-8ACROLEIN	100U
(3U)	107-13-1ACRYLONITRILE	100U
(4U)	71-43-2SENEZENE	5U
(6U)	56-23-2CARBON TETRACHLORIDE	5U
(7U)	108-90-7CHLOROGENE	5U
(10U)	107-06-21,2-DICHLOROETHANE	5U
(11U)	71-55-61,1,1-TRICHLOROETHANE	5U
(13U)	75-34-31,1-DICHLOROETHANE	5U
(14U)	79-00-51,1,2-TRICHLOROETHANE	5U
(15U)	79-34-51,1,2,2-TETRACHLOROETHANE	10U
(16U)	75-00-3CHLOROETHANE	10U
(19U)	110-75-82-CHLOROETHYL VINYLETHER	10U
(23U)	67-66-3CHLOROFORM	5U
(29U)	75-35-41,1-DICHLOROETHENE	5U
(30U)	156-60-5TRANS-1,2-DICHLOROETHENE	5U
(32U)	78-87-51,2-DICHLOROPROPANE	10U
(33U)	10061-02-6TRANS-1,3-DICHLOROPROPENE	5U
	10061-01-0CIS-1,3-DICHLOROPROPENE	5U
(38U)	100-41-4ETHYLBENZENE	5U
(44U)	75-09-2METHYLENE CHLORIDE	12.1 M
(45U)	74-87-3CHLOROMETHANE	10U
(46U)	74-83-9BROMOMETHANE	10U
(47U)	75-25-2BROMOFORM	10U
(48U)	75-27-4BROMODICHLOROMETHANE	5U
(49U)	75-69-4FLUOROTRICHLOROMETHANE	5U
(50U)	75-71-8DICHLORODIFLUOROMETHANE	NA
(51U)	124-48-1CHLORODIBROMOMETHANE	5U
(85U)	127-18-4TETRACHLOROETHENE	5U
(86U)	108-98-8TOLUENE	5U
(87U)	79-01-6TRICHLOROETHENE	5U
(88U)	75-01-4VINYL CHLORIDE	10U
	67-64-1ACETONE	5U
	78-93-32-BUTANONE	5U
	75-15-0CARBON DISULFIDE	1U
	519-78-62-HEXANONE	5U
	108-10-14-METHYL-2-PENTANONE	5U
	100-42-5STYRENE	5U
	103-05-4VINYL ACETATE	5U
	1330-20-7TOTAL XYLENES	5U

## PESTICIDES

CONCENTRATION LOW  
DATE EXTRACTED 9/13/84  
DATE ANALYZED 10/4/84  
PERCENT MOISTURE N/A  
CONCENTRATION/OIL FACTOR 10

PP#	CASH	UG/L
(89P)	309-00-2 ALDRIN	.005U
(90P)	60-57-1 DIELDRIN	.005U
(91P)	57-74-9 CHLORDANE	.05U
(92P)	50-29-3 6,4'DDT	.01U
(93P)	72-55-9 4,4'DOE	.005U
(94P)	72-54-8 4,4'DOO	.1U
(95P)	115-29-7 ALPHA-ENDOSULFAN	.005U
(96P)	115-29-7 BETA-ENDOSULFAN	.005U
(97P)	1031-07-8 ENDOSULFAN SULFATE	.01U
(98P)	72-20-3 ENDRIN	.005U
(99P)	7421-93-4 ENDRIH ALDEHYDE	.01U
(100P)	76-44-3 HEPTACHLOR	.005U
(101P)	1024-57-3HEFTACHLOR EPOXIDE	.005U
(102P)	319-84-6 ALPHA-BHC	.005U
(103P)	319-85-7 BETA-BHC	.005U
(104P)	319-86-8 DELTA-BHC	.005U
(105P)	58-89-9 GAMMA-SHC (LINDANE)	.005U
106P	53469-21-9PCB-1242	.05U
107P	11097-69-1PCB-1254	.1U
108P	11104-28-2PCB-1221	.1U
109P	11141-16-5PCB-1232	.050
110P	12672-29-6PCB-1248	.1U
111P	11096-82-5PCB-1260	.1U
112P	12674-11-2PCB-1016	.2U
113P	8001-35-2TOXAPHENE	.05U

USEPA-SAMPLE MANAGEMENT OFFICE  
PO BOX 818 ALEXANDRIA, VA 22313

0000010

SAMPLE NO.  
J4549

ORGANICS ANALYSIS DATA SHEET

LABORATORY NAME \_\_\_\_\_ PEDCO ENV.  
LAB SAMPLE ID NO. \_\_\_\_\_ DT149  
SAMPLE MATRIX \_\_\_\_\_ WATER  
DATA RELEASE AUTHORIZED \_\_\_\_\_ A9

CASE NO. \_\_\_\_\_ 3206  
QC REPORT NO. \_\_\_\_\_  
CONTRACT NO. \_\_\_\_\_ 68-01-6779  
DATE SAMPLE RECEIVED \_\_\_\_\_ 9/13/84

SEMIVOLATILE COMPOUNDS

CONCENTRATION \_\_\_\_\_ LOW  
DATE EXTRACTED \_\_\_\_\_ 9/13/84  
DATE ANALYZED \_\_\_\_\_ 9/26/84  
PER CENT MOISTURE \_\_\_\_\_ H/A  
CONCENTRATION/DIL. FACTOR \_\_\_\_\_ 500

PPM	CAS#	UG/L	PPM	CAS#	UG/L		
(21A)	88-06-2	2,4,6-TRICHLOROPHENOL	10	(528)	87-68-3	HEXACHLOROBUTADIENE	10
22A)	59-50-7	P-CHLORO-M-CRESOL	10	(538)	77-47-4	HEXACHLOROCYCLOPENTADIENE	10
(24A)	95-57-3	2-CHLOROPHENOL	10	(548)	78-59-1	ISOPHORONE	10
(31A)	120-83-2	2,4-DICHLOROPHENOL	10	(558)	91-20-3	NAPHTHALENE	10
(34A)	105-67-9	2,4-DIMETHYLPHENOL	10	(568)	98-95-3	NITROBENZENE	10
(57A)	88-75-5	2-NITROPHENOL	20	(628)	86-30-6	N-NITROSODIPHENYLAMINE	10
(55A)	100-02-7	4-NITROPHENOL	50	(638)	621-64-7	N-NITROSODIPROPYLAMINE	10
(59A)	51-23-5	2,4-DINITROPHENOL	50	(666)	117-81-7	BIS(2-ETHYLNEXYL) PHTHALATE	20.6
(60A)	534-52-1	4,6-DINITRO-O-CRESOL	20	(678)	85-68-7	BENZYL BUTYL PHTHALATE	10
(64A)	87-86-5	PENTACHLOROPHENOL	10	(688)	84-74-2	DI-N-BUTYL PHTHALATE	9.2
(65A)	108-95-2	PHENOL	10	(698)	117-84-0	DI-N-OCTYL PHTHALATE	10
	65-85-0	BENZOIC ACID	100	(708)	84-66-2	DIETHYL PHTHALATE	10
	95-43-7	2-METHYLPHENOL	5	(718)	131-11-3	DIMETHYL PHTHALATE	10
	108-39-4	4-METHYLPHENOL	5	(728)	56-55-3	BENZO(A)ANTHRACENE	10
	95-95-4	2,4,5-TRICHLOROPHENOL	100	(738)	50-32-3	BENZO(A)PYRENE	20
( 18)	83-32-9	ACENAPHTHENE	10	(748)	205-99-2	BENZO(B)FLUORANTHENE AND/	20
( 58)	92-37-5	BENZIDINE	40	(758)	207-08-9	BENZO(C)FLUORANTHENE OR	20
( 88)	120-32-1	1,2,4-TRICHLOROBENZENE	10	(768)	218-01-9	CHRYSENE	20
( 98)	118-74-1	HEXACHLOROBENZENE	10	(778)	208-96-8	ACENAPHTHYLENE	10
(128)	67-72-1	HEXACHLOROCTANE	10	(788)	120-12-7	ANTHRACENE	10
(188)	111-46-4	BIS(2-CHLOROETHYL) ETHER	10	(798)	191-24-2	BENZO(GHI)PERYLENE	20
(208)	91-58-7	2-CHLORONAPHTHALENE	10	(808)	86-73-7	FLUORENE	10
(258)	95-50-1	1,2-DICHLOROBENZENE	10	(818)	85-01-8	PHENANTHRENE	10
(268)	541-73-1	1,3-DICHLOROBENZENE	10	(828)	53-70-3	DIBENZO(AH)ANTHRACENE	20
(278)	106-46-7	1,6-DICHLOROBENZENE	10	(838)	193-39-5	INDENO(123-CD)PYRENE	20
(288)	91-94-1	3,3'-DICHLOROBENZIDINE	20	(848)	129-00-0	PYRENE	10
(353)	121-14-2	2,4-DINITROTOLUENE	20		62-53-3	ANILINE	5
(368)	606-20-2	2,6-DINITROTOLUENE	20		100-51-6	BENZYL ALCOHOL	20
(378)	122-66-7	1,2-DIPHENYLHYDRAZINE	20		106-47-8	4-CHLOROANILINE	50
(398)	206-44-0	FLUORANTHENE	10		132-64-9	DIBENZOFURAN	10
(608)	7005-72-3	4-CHLOROPHENYLPHENYLETHER	10		91-57-6	2-METHYLNAPHTHALENE	20
(418)	101-55-3	4-BROMOPHENYLPHENYLETHER	10		88-74-4	2-NITROANILINE	100
(628)	39638-32-9	BIS(2-CHLOROISOPROPYL) ETHER	20		99-09-2	5-NITROANILINE	100
(438)	111-91-1	BIS(2-CHLOROETHOXY) METHANE	20		100-01-6	4-NITROANILINE	100

FORM 111  
WATER SURROGATE PERCENT RECOVERY SUMMARY

LOW LEVEL \_\_\_\_\_  
WATER \_\_\_\_\_  
QC REPORT NO. \_\_\_\_\_

CONTRACTOR PEDCO Environmental  
MED. LEVEL

CONTRACT NO. 68-01-6779  
HIGH LEVEL \_\_\_\_\_  
OTHER (Specify) \_\_\_\_\_

<b> -----Volatile ----- </b>	<b> -----Semi-Volatile----- </b>	<b>(Pesticide)---(Olefin)</b>
------------------------------	----------------------------------	-------------------------------

[illegible]

\* Asterisked values are outside of QC limits.

♦♦ Advisory Limit

**Comments:**

**Volatiles:** 0 out of 18; outside of QC limits

# MATRIX SPIKE DUPLICATE/RECOVERY

CASE NO. 3206  
 LOU LEVEL ✓  
 WATER ✓  
 QC REPORT NO.           

CONTRACTOR PEE ASSOC.  
 MED. LEVEL             
 SOIL/SED.           

CONTRACT NO. LF-01-6779  
 HIGH LEVEL             
 OTHER (Specify)             
 UNITS (Circle) ug/Kg ug/l

FRACTION	COMPOUND	CONC. SPIKE ADDED	CONC. MS	% REC.	CONC. MSD	% REC.	RPD	QC LIMITS*		COMMENTS
								RPD	RECOVERY	
VOA SMD # J4588	1,1-Dichloroethylene	49.9	57.2	115	59.8	120	4	<15%	51-151	
	Trichloroethylene	55.4	64.5	116	65.4	118	7	<15%	74-128	
	Chlorobenzene	42.3	59.2	140*	64.3	152*	8	<15%	67-131	
	Toluene	42.1	52.3	124	51.7	123	1	<15%	58-132	
	Benzene	41.7	44.9	108	45.0	108	0	<15%	56-132	
B/N SMD # J4588	1,2,4-Trichlorobenzene	51.7	11.4	22*	40.4	78	112*	<50%	38-108	
	Acenaphthene	50.3	22.1	44*	55.4	110	86*	<50%	57-115	
	2,4-Dinitrotoluene	52.2	4.0	8*	15.5	30*	116*	<50%	43-113	
	Di-H-Butylphthalate	69.5	14.6	21	39.8	57	92*	<50%	13-113	
	Pyrene	65.0	50.4	78	109.9	168*	73*	<50%	25-137	
	N-Nitrosodi-N-Propylamine	56.1	10.8	19*	38.8	69	114*	<50%	34-114	
	1,4-Dichlorobenzene	60.7	11.6	19*	45.0	75	119*	<50%	33-103	
ACID SMD # J4588	Pentachlorophenol	101.2	9.6	9*	11.8	12*	29	<40%	19-123	
	Phenol	103.8	46.4	45	16.8	16*	93*	<40%	23-81	
	2-Chlorophenol	110.4	74.8	68	22.8	27*	69*	<40%	33-107	
	p-Chloro-H-Cresol	100.8	19.0	19*	8.2	8*	81*	<40%	32-108	
	4-Nitrophenol	100.8	0	0*	0	0*	0	<40%	15-93	
PEST SMD # J2271	Lindane	12.6	12.5	99	12.3	98	7	<40%	87-107	
	Heptachlor	9.9	7.8	78	7.9	79	1	<40%	43-125	
	Aldrin	10.8	10.0	92	9.9	91	1	<40%	45-109	
	Dieldrin	10.1	10.7	106	10.0	99	7	<40%	56-122	
	Endrin	10.4	9.5	91	9.0	86	5	<40%	89-101	
	p,p-DDT	10.1	8.8	87	8.2	81	6	<40%	82-102	

\*Asterisked values are outside QC limits.

RPD: VOAs 0 out of 5; outside QC limits  
 B/N 7 out of 7; outside QC limits  
 ACID 3 out of 3; outside QC limits  
 PEST 0 out of 6; outside QC limits

RECOVERY: VOAs 2 out of 10; outside QC limits  
 B/N 7 out of 14; outside QC limits  
 ACID 8 out of 10; outside QC limits  
 PEST 0 out of 12; outside QC limits

\*Date Limits Set 12/82  
 Revision Due 6/83

# REAGENT BLANK SUMMARY

Case No. 3206 Contractor PEI Assoc Contract No. 68-01-6779

FILE ID	DATE OF ANALYSIS	FRACTION	MATRIX	CONC. LEVEL	INST. ID	CAS NUMBER	COMPOUND (ISL. TIC OR UNKNOWN)	CONC.	UNITS	CROL
VOABCK 0913	9-13	VOA	W	L	T		Methylene Chloride	9.6	ug/l	5
							Acetone	11.3	"	10
							2-Butanone	5.0	"	10
BNABCK 0926	9-26	BIA	W	L	R		Bis(2-ethylhexyl) phthalate	17.8	ug/l	10
PEST BCK	10-4	PE	W	L	V		None			

Comments:

---



---



---

Bill Gess (513) 745-7700  
Fedco Environmental, Inc.  
11499 Chester Rd.  
Cincinnati, OH 45246

In Reference to Case No(s):

3206

Contract Laboratory Program  
REGIONAL/LABORATORY COMMUNICATION SYSTEM

Telephone Record Log

Date of Call: 11/6/84

Laboratory Name: Fedco Env. Inc.

Lab Contact: Bill Gess

Region: 10

Regional Contact: Jim Farn

Call Initiated By: ☐ Laboratory ☒ Region

In reference to data for the following sample number(s):

74547, 74548, 74549

Summary of Questions/Issues Discussed:

Discussing DFTPP macrobenthos  
Is a problem to be solved with sumneria recoveries  
Will not in time recoveries for BAP fraction  
We didn't have to be an attempt at restriction  
at least it wasn't acknowledged.

Summary of Resolution:

Will send missing sections  
Data hits in the water therefore no  
+ analysis

Signature

Date: 11/6/84

Distribution: (1) Lab Copy, (2) Region Copy, (3) SMO Copy

APPENDIX B

SAMPLE DOCUMENTATION  
RESOURCE RECOVERY CORPORATION, PASCO, WASHINGTON  
CASE NO.: 3206  
SITE INSPECTION - 9/12/84  
ECOLOGY AND ENVIRONMENT, INC., SEATTLE

# APPENDIX B - SAMPLE DOCUMENTATION

FI- 108408 -22

Resource Recovery Corp.

Case No.: 3206

Location Number	Latitude/Longitude	STORE Station Number	Sample Containers	Date and Time	Loss/Day Forri Number	Sample Lab. Number	Sample Type (forab)	Means of Preservation	Analysis Requested	Destination
Control Well	46° 45' 00" 119° 02' 30"	05A013	2 ½-gal. jars	9/12/84 10:30	10-1282	J 4548	Aqueous	Iced	Extractable Organics	Pedco
			2 40-ml. vials	9/12/84 10:30	10-1282	J 4548	(Grab)	Iced	Volatile Organics	Pedco
			2 1-liter Poly bottles	9/12/84 10:30	10-1283	MJ 9043	Aqueous (Grab)	NaOH HNO <sub>3</sub>	Cyanide Heavy Metals	Chem Tech Chem Tech
Well #3	46° 45' 00" 119° 02' 30"	05A014	2 ½-gal. jars	9/12/84 14:30	10-1282	J 2271	Aqueous	Iced	Extractable Organics	Pedco
			2 40-ml. vials	9/12/84 14:30	10-1282	J 2271	(Grab)	Iced	Volatile Organics	Pedco
			2 1-liter Poly bottles	9/12/84 14:30	10-1283	MJ 9045	Aqueous (Grab)	NaOH HNO <sub>3</sub>	Cyanide Heavy Metals	Chem Tech Chem Tech
Transfer Blank	-----	-----	2 ½-gal. jars	9/12/84 10:15	10-1282	J 4549	Aqueous	Iced	Extractable Organics	Pedco
			2 40-ml. vials	9/12/84 10:15	10-1282	J 4549	(Grab)	Iced	Volatile Organics	Pedco
			2 1-liter Poly bottles	9/12/84 10:15	10-1283	MJ 9044	Aqueous (Grab)	NaOH HNO <sub>3</sub>	Cyanide Heavy Metals	Chem Tech Chem Tech



APPENDIX C

SITE INSPECTION REPORT EORM  
9/12/84

RESOURCE RECOVERY CORPORATION  
PASCO, WASHINGTON  
COMPILED BY  
ECOLOGY AND ENVIRONMENT, INC.  
SEATTLE, WASHINGTON



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION  
01 STATE WA 02 SITE NUMBER WAD991281874

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Resource Recovery Corporation		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Kahlotus Rd. & Hwy 12			
03 CITY Pasco	04 STATE WA	05 ZIP CODE 99301	06 COUNTY Franklin	07 COUNTY CODE 021	08 CONG DIST 05
09 COORDINATES LATITUDE 46 15 07.0 LONGITUDE 119 03 13.5		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER			

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 9 / 12 / 84 MONTH DAY YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION as a hazardous waste site, 1972 to 1980 1956 I Present UNKNOWN BEGINNING YEAR ENDING YEAR
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input checked="" type="checkbox"/> B. EPA CONTRACTOR E & F <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR <input type="checkbox"/> G. OTHER		

05 CHIEF INSPECTOR Peter Evers	06 TITLE Environmental Chemist	07 ORGANIZATION E&E	08 TELEPHONE NO. (206) 624-9537
09 OTHER INSPECTORS Rich Brooks	10 TITLE Biologist	11 ORGANIZATION E&E	12 TELEPHONE NO. (206) 624-9537
Mike Gallagher	Environmentalist II	WDOE	(206) 753-2353
			( )
			( )
			( )
13 SITE REPRESENTATIVES INTERVIEWED Larry Dietrich, Pasco Sanitary Landfill	14 TITLE Owner/Operator	15 ADDRESS 420 E. Ainsworth	16 TELEPHONE NO. (509) 547-4802
John Zillich, Engineering	Project Mgr.	J.U.B. Engineers, Inc.	(509) 783-2144
Consultant to Above.		N.W. Crossing Office #201	( )
		2810 W. Clearwater Ave.	( )
		Kennewick, WA 99335	( )
			( )

17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 8:00 a.m.	19 WEATHER CONDITIONS Sunny & Warm
--	------------------------------------	---------------------------------------

IV. INFORMATION AVAILABLE FROM

01 CONTACT Debbie Flood	02 OF (Agency/Organization) EPA	03 TELEPHONE NO. (208) 442-2722		
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Christopher M. Nadler	05 AGENCY EPA/FIT	06 ORGANIZATION E & E	07 TELEPHONE NO. (206) 624-9537	08 DATE 12/12/84 MONTH DAY YEAR



☒ I. HIGHLY VOLATILE  
☐ J. EXPLOSIVE  
☒ K. REACTIVE  
☐ L. INCOMPATIBLE  
☐ M. NOT APPLICABLE



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION  
01 STATE: WA 02 SITE NUMBER: WAD991281874

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☒ OBSERVED (DATE: 9/12/84) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: 100 04 NARRATIVE DESCRIPTION

Analysis of groundwater samples collected during E&E site inspection revealed levels of barium (1,631 µg/l), beryllium (7 µg/l), chromium (706 µg/l), lead (160 µg/l), and nickel (162 µg/l) above the EPA recommended levels.

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: ) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: 0 04 NARRATIVE DESCRIPTION

No observed release. It appears that due to lack of surface waters and lack of rain, little potential exist for surface water contamination.

01 ☒ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: ) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: unknown 04 NARRATIVE DESCRIPTION

No observed release. Local farmers and residents expressed concern over burial of 2,4-D and MCPA wastes and their effects on local grapevines.

01 ☒ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: ) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: unknown 04 NARRATIVE DESCRIPTION

No documented evidence of threat.

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: ) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: unknown 04 NARRATIVE DESCRIPTION

No reported incidents. Site is not fenced and could be accessible to trespassers. WDOE, however, relieved site of a fencing requirement due to "lack of problems experienced without one". Operator's residence is on site.

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: ) ☒ POTENTIAL ☐ ALLEGED  
03 AREA POTENTIALLY AFFECTED: unknown (ACRES) 04 NARRATIVE DESCRIPTION

The liquid wastes were disposed of in unlined trenches. The ground water samples which were collected 9/12/84 revealed heavy metal contamination, therefore the potential exists for soil contamination.

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: ) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: >100 04 NARRATIVE DESCRIPTION

None observed. Concern however, for potential seepage from septic disposal area laterally migrating to hazardous waste areas. Also concern for unlined disposal sites leaking into water table aquifer.

01 ☒ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: ) ☒ POTENTIAL ☐ ALLEGED  
03 WORKERS POTENTIALLY AFFECTED: <10 04 NARRATIVE DESCRIPTION

None observed. Disposal area coverings are eroding and potential for worker exposure although slight, is possible.

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: ) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: <100 04 NARRATIVE DESCRIPTION

None observed. Potential for significant population exposure is slight due to wastes being buried, lack of open evaporation ponds and remote location. However, due to lack of fencing around facility results in uncontrolled access.



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION  
01 STATE 02 SITE NUMBER  
WA WAD991281874

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J. DAMAGE TO FLORA  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☒ POTENTIAL

☐ ALLEGED

None observed. However, accusations were made in 1973 over the site accepting 2,4-D and MCPA wastes which are toxic to local crops (grapevines).

01 ☒ K. DAMAGE TO FAUNA  
04 NARRATIVE DESCRIPTION (INCLUDE NUMBER OF SPECIES)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None observed.

01 ☒ L. CONTAMINATION OF FOOD CHAIN  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None observed.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES

(Soils Runoff/Sludging liquids, Leaking drums)

03 POPULATION POTENTIALLY AFFECTED: <100

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☒ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

Hazardous wastes were disposed in unlined bottom trenches. Wind is eroding the soils covering the trenches.

01 ☒ N. DAMAGE TO OFFSITE PROPERTY  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None observed.

01 ☒ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTFS  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None observed. Unknown if these systems are in this area.

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None observed.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL OR ALLEGED HAZARDS

None known.

III. TOTAL POPULATION POTENTIALLY AFFECTED: 8,523

IV. COMMENTS

Due to the nature of wastes disposed of and method of disposal at the site, periodic inspection should be carried out for leakage from disposal areas.

V. SOURCES OF INFORMATION (List specific references e.g., State files, company records, reports)

EPA Files, Seattle, WA  
WDOE Files, Olympia, WA  
E&E water sampling on 9/12/84



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION  
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE WA 02 SITE NUMBER WAD991281874

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input checked="" type="checkbox"/> G. STATE (Specify)	5301	3/21/73		state waste discharged permit
<input type="checkbox"/> H. LOCAL (Specify)				for Resource Recovery Corp.
<input checked="" type="checkbox"/> I. OTHER (Specify) State	CUF 82-5			conditional use permit for
<input type="checkbox"/> J. NONE				asco Sanitary Landfill.

III. SITE DESCRIPTION

01 STORAGE/PROCESSING (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input checked="" type="checkbox"/> A. SURFACE IMPOUNDMENT	unknown		<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input checked="" type="checkbox"/> B. PILES	unknown		<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input checked="" type="checkbox"/> H. OTHER Evaporation (Specify)	
<input checked="" type="checkbox"/> I. OTHER drums below ground unknown (Specify)				

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)  
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☒ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, CILKING, LINERS, BARRIERS, ETC.

Chloro-alkali sludge has been stored in unlined ponds. Barium sludges with mercury are buried in a total lined (4mil polyethylene) trench. Other hazardous wastes have been buried with only a 4mil polyethylene top liner. Sewage wastes are disposed of in an unlined pond.


V. ACCESSIBILITY

01 WASTES ONLY ACCESSIBLE: ☒ YES ☐ NO  
02 COMMENTS

Site is not fence, but in a remote area.

VI. SOURCES OF INFORMATION (List source, reference, or significant sample analysis results)

WDOE FILES, OLYMPIA, WA  
EPA FILES, SEATTLE, WA



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART E - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION  
01 STATE 02 SITE NUMBER  
WA WAD991291974

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY (Check all that apply)	02 STATUS	03 DISTANCE TO SITE															
<table border="0"><tr><td>SURFACE</td><td>WELL</td></tr><tr><td>COMMUNITY A <input checked="" type="checkbox"/></td><td>B <input type="checkbox"/></td></tr><tr><td>NON-COMMUNITY C <input type="checkbox"/></td><td>D <input checked="" type="checkbox"/></td></tr></table>	SURFACE	WELL	COMMUNITY A <input checked="" type="checkbox"/>	B <input type="checkbox"/>	NON-COMMUNITY C <input type="checkbox"/>	D <input checked="" type="checkbox"/>	<table border="0"><tr><td>unknown</td></tr><tr><td>ENDANGERED A <input type="checkbox"/></td><td>AFFECTED B <input type="checkbox"/></td><td>MONITORED C <input type="checkbox"/></td></tr><tr><td>D <input type="checkbox"/></td><td>E <input type="checkbox"/></td><td>F <input type="checkbox"/></td></tr></table>	unknown	ENDANGERED A <input type="checkbox"/>	AFFECTED B <input type="checkbox"/>	MONITORED C <input type="checkbox"/>	D <input type="checkbox"/>	E <input type="checkbox"/>	F <input type="checkbox"/>	<table border="0"><tr><td>A. 3.5 (mi)</td></tr><tr><td>B. on-site (mi)</td></tr></table>	A. 3.5 (mi)	B. on-site (mi)
SURFACE	WELL																
COMMUNITY A <input checked="" type="checkbox"/>	B <input type="checkbox"/>																
NON-COMMUNITY C <input type="checkbox"/>	D <input checked="" type="checkbox"/>																
unknown																	
ENDANGERED A <input type="checkbox"/>	AFFECTED B <input type="checkbox"/>	MONITORED C <input type="checkbox"/>															
D <input type="checkbox"/>	E <input type="checkbox"/>	F <input type="checkbox"/>															
A. 3.5 (mi)																	
B. on-site (mi)																	

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check all that apply)											
<table border="0"><tr><td>C A. ONLY SOURCE FOR DRINKING</td><td><input checked="" type="checkbox"/> B. DRINKING (OTHER SOURCES AVAILABLE)</td><td>C C. COMMERCIAL INDUSTRIAL IRRIGATION (LISTING OTHER SOURCES AVAILABLE)</td><td>C D. NOT USED, UNDETECTABLE</td></tr><tr><td colspan="4">COMMERCIAL INDUSTRIAL IRRIGATION (NO OTHER WATER SOURCES AVAILABLE)</td></tr></table>				C A. ONLY SOURCE FOR DRINKING	<input checked="" type="checkbox"/> B. DRINKING (OTHER SOURCES AVAILABLE)	C C. COMMERCIAL INDUSTRIAL IRRIGATION (LISTING OTHER SOURCES AVAILABLE)	C D. NOT USED, UNDETECTABLE	COMMERCIAL INDUSTRIAL IRRIGATION (NO OTHER WATER SOURCES AVAILABLE)			
C A. ONLY SOURCE FOR DRINKING	<input checked="" type="checkbox"/> B. DRINKING (OTHER SOURCES AVAILABLE)	C C. COMMERCIAL INDUSTRIAL IRRIGATION (LISTING OTHER SOURCES AVAILABLE)	C D. NOT USED, UNDETECTABLE								
COMMERCIAL INDUSTRIAL IRRIGATION (NO OTHER WATER SOURCES AVAILABLE)											
02 POPULATION SERVED BY GROUNDWATER		03 DISTANCE TO NEAREST DRINKING WATER WELL									
unknown		on-site (mi)									
04 DEPTH TO GROUNDWATER	05 DIRECTION OF GROUNDWATER FLOW	06 DEPTH TO AQUIFER CF GCECFN	07 POTENTIAL YIELD OF AQUIFER								
55 (ft)	SW (assumed)	55 (ft)	unknown (GPD)								
08 SOLE SOURCE AQUIFER <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO											

03 DESCRIPTION OF WELLS (including name, depth, and location relative to population and discharge)

The on-site well provides drinking water for the owner's residence. Other wells around site provide irrigation water.

10 RECHARGE AREA	11 DISCHARGE AREA
<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
COMMENTS	COMMENTS
	only through groundwater wells.

IV. SURFACE WATER

01 SURFACE WATER USE (Check all that apply)							
<table border="0"><tr><td><input checked="" type="checkbox"/> A. RECREATION, RECREATION OR DRINKING WATER SOURCE</td><td><input type="checkbox"/> B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCE</td><td><input type="checkbox"/> C. COMMERCIAL INDUSTRIAL</td><td><input type="checkbox"/> D. NOT CURRENTLY USED</td></tr></table>				<input checked="" type="checkbox"/> A. RECREATION, RECREATION OR DRINKING WATER SOURCE	<input type="checkbox"/> B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCE	<input type="checkbox"/> C. COMMERCIAL INDUSTRIAL	<input type="checkbox"/> D. NOT CURRENTLY USED
<input checked="" type="checkbox"/> A. RECREATION, RECREATION OR DRINKING WATER SOURCE	<input type="checkbox"/> B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCE	<input type="checkbox"/> C. COMMERCIAL INDUSTRIAL	<input type="checkbox"/> D. NOT CURRENTLY USED				
02 AFFECTED, POTENTIALLY AFFECTED BODIES OF WATER							
NAME	AFFECTED	DISTANCE TO SITE					
Snake River	<input type="checkbox"/>	2.7 (mi)					
Columbia River	<input type="checkbox"/>	3.1 (mi)					
	<input type="checkbox"/>	(mi)					

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN			02 DISTANCE TO NEAREST POPULATION
ONE (1) MILE OF SITE A. 34 NO. OF PERSONS	TWO (2) MILES OF SITE B. 1,090 NO. OF PERSONS	THREE (3) MILES OF SITE C. 10,640 NO. OF PERSONS	on-site (mi)
03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE			04 DISTANCE TO NEAREST OFF-SITE BUILDING
278			0.8 (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site: 0.5, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000, 1001, 1002, 1003, 1004, 1005, 1006, 1007, 1008, 1009, 1010, 1011, 1012, 1013, 1014, 1015, 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1027, 1028, 1029, 1030, 1031, 1032, 1033, 1034, 1035, 1036, 1037, 1038, 1039, 1040, 1041, 1042, 1043, 1044, 1045, 1046, 1047, 1048, 1049, 1050, 1051, 1052, 1053, 1054, 1055, 1056, 1057, 1058, 1059, 1060, 1061, 1062, 1063, 1064, 1065, 1066, 1067, 1068, 1069, 1070, 1071, 1072, 1073, 1074, 1075, 1076, 1077, 1078, 1079, 1080, 1081, 1082, 1083, 1084, 1085, 1086, 1087, 1088, 1089, 1090, 1091, 1092, 1093, 1094, 1095, 1096, 1097, 1098, 1099, 1100, 1101, 1102, 1103, 1104, 1105, 1106, 1107, 1108, 1109, 1110, 1111, 1112, 1113, 1114, 1115, 1116, 1117, 1118, 1119, 1120, 1121, 1122, 1123, 1124, 1125, 1126, 1127, 1128, 1129, 1130, 1131, 1132, 1133, 1134, 1135, 1136, 1137, 1138, 1139, 1140, 1141, 1142, 1143, 1144, 1145, 1146, 1147, 1148, 1149, 1150, 1151, 1152, 1153, 1154, 1155, 1156, 1157, 1158, 1159, 1160, 1161, 1162, 1163, 1164, 1165, 1166, 1167, 1168, 1169, 1170, 1171, 1172, 1173, 1174, 1175, 1176, 1177, 1178, 1179, 1180, 1181, 1182, 1183, 1184, 1185, 1186, 1187, 1188, 1189, 1190, 1191, 1192, 1193, 1194, 1195, 1196, 1197, 1198, 1199, 1200, 1201, 1202, 1203, 1204, 1205, 1206, 1207, 1208, 1209, 1210, 1211, 1212, 1213, 1214, 1215, 1216, 1217, 1218, 1219, 1220, 1221, 1222, 1223, 1224, 1225, 1226, 1227, 1228, 1229, 1230, 1231, 1232, 1233, 1234, 1235, 1236, 1237, 1238, 1239, 1240, 1241, 1242, 1243, 1244, 1245, 1246, 1247, 1248, 1249, 1250, 1251, 1252, 1253, 1254, 1255, 1256, 1257, 1258, 1259, 1260, 1261, 1262, 1263, 1264, 1265, 1266, 1267, 1268, 1269, 1270, 1271, 1272, 1273, 1274, 1275, 1276, 1277, 1278, 1279, 1280, 1281, 1282, 1283, 1284, 1285, 1286, 1287, 1288, 1289, 1290, 1291, 1292, 1293, 1294, 1295, 1296, 1297, 1298, 1299, 1300, 1301, 1302, 1303, 1304, 1305, 1306, 1307, 1308, 1309, 1310, 1311, 1312, 1313, 1314, 1315, 1316, 1317, 1318, 1319, 1320, 1321, 1322, 1323, 1324, 1325, 1326, 1327, 1328, 1329, 1330, 1331, 1332, 1333, 1334, 1335, 1336, 1337, 1338, 1339, 1340, 1341, 1342, 1343, 1344, 1345, 1346, 1347, 1348, 1349, 1350, 1351, 1352, 1353, 1354, 1355, 1356, 1357, 1358, 1359, 1360, 1361, 1362, 1363, 1364, 1365, 1366, 1367, 1368, 1369, 1370, 1371, 1372, 1373, 1374, 1375, 1376, 1377, 1378, 1379, 1380, 1381, 1382, 1383, 1384, 1385, 1386, 1387, 1388, 1389, 1390, 1391, 1392, 1393, 1394, 1395, 1396, 1397, 1398, 1399, 1400, 1401, 1402, 1403, 1404, 1405, 1406, 1407, 1408, 1409, 1410, 1411, 1412, 1413, 1414, 1415, 1416, 1417, 1418, 1419, 1420, 1421, 1422, 1423, 1424, 1425, 1426, 1427, 1428, 1429, 1430, 1431, 1432, 1433, 1434, 1435, 1436, 1437, 1438, 1439, 1440, 1441, 1442, 1443, 1444, 1445, 1446, 1447, 1448, 1449, 1450, 1451, 1452, 1453, 1454, 1455, 1456, 1457, 1458, 1459, 1460, 1461, 1462, 1463, 1464, 1465, 1466, 1467, 1468, 1469, 1470, 1471, 1472, 1473, 1474, 1475, 1476, 1477, 1478, 1479, 1480, 1481, 1482, 1483, 1484, 1485, 1486, 1487, 1488, 1489, 1490, 1491, 1492, 1493, 1494, 1495, 1496, 1497, 1498, 1499, 1500, 1501, 1502, 1503, 1504, 1505, 1506, 1507, 1508, 1509, 1510, 1511, 1512, 1513, 1514, 1515, 1516, 1517, 1518, 1519, 1520, 1521, 1522, 1523, 1524, 1525, 1526, 1527, 1528, 1529, 1530, 1531, 1532, 1533, 1534, 1535, 1536, 1537, 1538, 1539, 1540, 1541, 1542, 1543, 1544, 1545, 1546, 1547, 1548, 1549, 1550, 1551, 1552, 1553, 1554, 1555, 1556, 1557, 1558, 1559, 1560, 1561, 1562, 1563, 1564, 1565, 1566, 1567, 1568, 1569, 1570, 1571, 1572, 1573, 1574, 1575, 1576, 1577, 1578, 1579, 1580, 1581, 1582, 1583, 1584, 1585, 1586, 1587, 1588, 1589, 1590, 1591, 1592, 1593, 1594, 1595, 1596, 1597, 1598, 1599, 1600, 1601, 1602, 1603, 1604, 1605, 1606, 1607, 1608, 1609, 1610, 1611, 1612, 1613, 1614, 1615, 1616, 1617, 1618, 1619, 1620, 1621, 1622, 1623, 1624, 1625, 1626, 1627, 1628, 1629, 1630, 1631, 1632, 1633, 1634, 1635, 1636, 1637, 1638, 1639, 1640, 1641, 1642, 1643, 1644, 1645, 1646, 1647, 1648, 1649, 1650, 1651, 1652, 1653, 1654, 1655, 1656, 1657, 1658, 1659, 1660, 1661, 1662, 1663, 1664, 1665, 1666, 1667, 1668, 1669, 1670, 1671, 1672, 1673, 1674, 1675, 1676, 1677, 1678, 1679, 1680, 1681, 1682, 1683, 1684, 1685, 1686, 1687, 1688, 1689, 1690, 1691, 1692, 1693, 1694, 1695, 1696, 1697, 1698, 1699, 1700, 1701, 1702, 1703, 1704, 1705, 1706, 1707, 1708, 1709, 1710, 1711, 1712, 1713, 1714, 1715, 1716, 1717, 1718, 1719, 1720, 1721, 1722, 1723, 1724, 1725, 1726, 1727, 1728, 1729, 1730, 1731, 1732, 1733, 1734, 1735, 1736, 1737, 1738, 1739, 1740, 1741, 1742, 1743, 1744, 1745, 1746, 1747, 1748, 1749, 1750, 1751, 1752, 1753, 1754, 1755, 1756, 1757, 1758, 1759, 1760, 1761, 1762, 1763, 1764, 1765, 1766, 1767, 1768, 1769, 1770, 1771, 1772, 1773, 1774, 1775, 1776, 1777, 1778, 1779, 1780, 1781, 1782, 1783, 1784, 1785, 1786, 1787, 1788, 1789, 1790, 1791, 1792, 1793, 1794, 1795, 1796, 1797, 1798, 1799, 1800, 1801, 1802, 1803, 1804, 1805, 1806, 1807, 1808, 1809, 1810, 1811, 1812, 1813, 1814, 1815, 1816, 1817, 1818, 1819, 1820, 1821, 1822, 1823, 1824, 1825, 1826, 1827, 1828, 1829, 1830, 1831, 1832, 1833, 1834, 1835, 1836, 1837, 1838, 1839, 1840, 1841, 1842, 1843, 1844, 1845, 1846, 1847, 1848, 1849, 1850, 1851, 1852, 1853, 1854, 1855, 1856, 1857, 1858, 1859, 1860, 1861, 1862, 1863, 1864, 1865, 1866, 1867, 1868, 1869, 1870, 1871, 1872, 1873, 1874, 1875, 1876, 1877, 1878, 1879, 1880, 1881, 1882, 1883, 1884, 1885, 1886, 1887, 1888, 1889, 1890, 1891, 1892, 1893, 1894, 1895, 1896, 1897, 1898, 1899, 1900, 1901, 1902, 1903, 1904, 1905, 1906, 1907, 1908, 1909, 1910, 1911, 1912, 1913, 1914, 1915, 1916, 1917, 1918, 1919, 1920, 1921, 1922, 1923, 1924, 1925, 1926, 1927, 1928, 1929, 1930, 1931



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION  
01 STATE: WA 02 SITE NUMBER: WA0991281874

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A.  $10^{-4} - 10^{-6}$  cm/sec ☐ B.  $10^{-4} - 10^{-5}$  cm/sec ☐ C.  $10^{-4} - 10^{-3}$  cm/sec ☒ D. GREATER THAN  $10^{-3}$  cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

Basalt

☐ A. IMPERMEABLE (Less than  $10^{-10}$  cm/sec)  
☐ B. RELATIVELY IMPERMEABLE ( $10^{-10} - 10^{-9}$  cm/sec)  
☒ C. RELATIVELY PERMEABLE ( $10^{-9} - 10^{-8}$  cm/sec)  
☐ D. VERY PERMEABLE (Greater than  $10^{-8}$  cm/sec)

03 DEPTH TO BEDROCK

Approx. 140 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

unknown (ft)

05 SOIL CH

unknown

06 NET PRECIPITATION

-32.0 (in)

07 ONE YEAR 24 HOUR RAINFALL

TWO

0.8 (in)

08 SLOPE

SITE SLOPE

1-3 %

DIRECTION OF SITE SLOPE

W-SW

TERRAIN AVERAGE SLOPE

3-5 %

09 FLOOD POTENTIAL

SITE IS IN N/A YEAR FLOODPLAIN

10

N/A ☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

A. N/A (mi)

McNary Wildlife

OTHER Refuge

B. 3.0 (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

Not within one (mi)

ENDANGERED SPECIES:

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

1.0 mile to S.E.

A. 2.0 mile west

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,  
FORESTS, OR WILDLIFE RESERVES

B. 1.5 (mi)

AGRICULTURAL LANDS  
PRIME AG LAND AG LAND

C. 0.0 (mi) D. (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

The site is located in an area similar to Karst topography, in that the area is relatively flat with numerous closed depressions. In a 1.0 mile radius, the topography is a large depression/bowl, with the general land surface raising to the Northeast (elev. 508 feet) and lowering to the Southwest (elev. 340 feet). Over a two mile distance


VII. SOURCES OF INFORMATION (Cite specific references & Q. state test sample analysis reports)

U.S.G.S. Pasco 75 minute Quadrangle

Uncontrolled hazardous waste site ranking system users Manual August 1982

Basalt Waste Isolation Project Annual Report Fiscal year 1980, RHO-BWI-80-100, document prepared for U.S. Department of Energy under contract DE-AC06-77RL01030 by Rockwell International.







POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
WA WA0991281874

II. CURRENT OWNER(S)				PARENT COMPANY (If Applicable)			
01 NAME Larry Dietrich		02 D+S NUMBER		05 NAME		08 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 420 E. Ainsworth		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY Pasco		06 STATE WA	07 ZIP CODE 99301	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+S NUMBER		05 NAME		08 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+S NUMBER		05 NAME		08 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+S NUMBER		05 NAME		08 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (List prior owners first)				IV. REALTY OWNER(S) (If Applicable: list owner first)			
01 NAME John Dietrich		02 D+S NUMBER		01 NAME		02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) P.O. Box 650		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY Pasco		06 STATE WA	07 ZIP CODE 99301	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+S NUMBER		01 NAME		02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+S NUMBER		01 NAME		02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (List agencies, references, etc., in this section. Attach exhibits, if any.)

EPA Files, Seattle, WA  
Personal Communication with Larry Dietrich 9/25/84 and 12/12/84.



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE | 02 SITE NUMBER  
WA | WAD991281874

II. CURRENT OPERATOR (Provide a reference from owner)

OPERATOR'S PARENT COMPANY (If applicable)

01 NAME Pasco Sanitary Landfill	02 D+B NUMBER	10 NAME	11 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 420 E. Ainsworth	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD #, etc.)	13 SIC CODE
05 CITY Pasco	06 STATE WA	07 ZIP CODE 99301	14 CITY
15 STATE	16 ZIP CODE		
08 YEARS OF OPERATION 1982-Present	09 NAME OF OWNER Larry Dietrich		

III. PREVIOUS OPERATOR(S) (List most recent first; provide one if different from owner)

PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)

01 NAME Resource Recovery Corp.	02 D+B NUMBER	10 NAME	11 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 5501 Airport Way South	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD #, etc.)	13 SIC CODE
05 CITY Seattle	06 STATE WA	07 ZIP CODE 98108	14 CITY
15 STATE	16 ZIP CODE		
08 YEARS OF OPERATION 1972-1981	09 NAME OF OWNER DURING THIS PERIOD John Kimberly, President		

01 NAME John Dietrich	02 D+B NUMBER	10 NAME	11 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.) P.O. Box 650	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD #, etc.)	13 SIC CODE
05 CITY Pasco	06 STATE WA	07 ZIP CODE 99301	14 CITY
15 STATE	16 ZIP CODE		
08 YEARS OF OPERATION 1956-1972	09 NAME OF OWNER DURING THIS PERIOD Same		

01 NAME	02 D+B NUMBER	10 NAME	11 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD #, etc.)	13 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	14 CITY
15 STATE	16 ZIP CODE		
08 YEARS OF OPERATION	09 NAME OF OWNER DURING THIS PERIOD		

IV. SOURCES OF INFORMATION (Cite specific references, e.g., State Dept. records, etc.)

EPA Files, Seattle, WA  
Personal Communication with Larry Dietrich 9/25/84 and 12/12/84



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
WA WAD991281874

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	
05 CITY	06 STATE 07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
Chemical Processors, Inc. Ron West		Weyerhaeuser Company	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
5501 Airport Way South		P.O. Box 188	
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
Seattle	WA 98108	Longview	WA 98632
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
Chevron Chemical Co.		Rhone Ponlenc Chemical Co.	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
P.O. Box 3883		6200 N.W. St. Helens Rd.	
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
San Francisco	CA 94119	Portland	OR 97210

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
Basin Disposal Inc.			
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
1210 S. Grey (P.O. Box 650)			
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
Pasco	WA 99301		
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
Kennewick Disposal Co.		Resource Recovery Corp.	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
1611 S. Washington St. PO Box 6088		5501 Airport Way South	
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
Kennewick	WA 99336	Seattle	WA 98108

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, records)

EPA Erris Files, Notification of Hazardous Waste Site (EPA Form 8900-1)  
Personal Communication w/ Larry Dietrich 9/25/84



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

L IDENTIFICATION

01 STATE 02 SITE NUMBER  
WA WAD991281874

PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ D. SPILLED MATERIAL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ E. CONTAMINATED SOIL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☒ F. WASTE REPACKAGED  
04 DESCRIPTION

02 DATE 1973

03 AGENCY \_\_\_\_\_

Chloro-alkali sludge was moved from an unlined lagoon to a lined lagoon.

01 ☐ G. WASTE DISPOSED ELSEWHERE  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ H. ON SITE BURIAL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ I. IN SITU CHEMICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ J. IN SITU BIOLOGICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ K. IN SITU PHYSICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ L. ENCAPSULATION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ M. EMERGENCY WASTE TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ N. CUTOFF WALLS  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ O. EMERGENCY DIKING SURFACE WATER DIVERSION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ P. CUTOFF TRENCHES SUMP  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ Q. SUBSURFACE CUTOFF WALL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE WA 02 SITE NUMBER WAD991281874

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ S. CAPPING/COVERING  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ T. BULK TANKAGE REPAIRED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ U. GROUT CURTAIN CONSTRUCTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ V. BOTTOM SEALED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ W. GAS CONTROL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ X. FIRE CONTROL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Y. LEACHATE TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Z. AREA EVACUATED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 1. ACCESS TO SITE RESTRICTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 2. POPULATION RELOCATED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 3. OTHER REMEDIAL ACTIVITIES  
04 DESCRIPTION

02 DATE

03 AGENCY

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

WDOE Site Files, Olympia



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE: WA 02 SITE NUMBER: WAD991281874

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

3-17-84 Recommendation of enforcement action-problems with sewage handling practices.

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, records)

WDOE Site Files, Olympia, WA

APPENDIX D

PHOTOGRAPHIC DOCUMENTATION

RESOURCE RECOVERY CORPORATION  
PASCO, WASHINGTON

SITE INSPECTION - 9/12/84

COMPILED BY  
ECOLOGY AND ENVIRONMENT, INC.  
SEATTLE, WASHINGTON



# PHOTO IDENTIFICATION SHEET

Type of Camera: Nikon FM

TDD No.: 10-8408-22

Type of Film: Kodachrome

Resource Recovery Corporation, Pasco WA

EPA No.: \_\_\_\_\_

Photo No.	Date	Time	Taken by	Description of Photo
1	9/12/84	0750	Rich Brooks	Entrance Gate taken in N-NW direction
2	"	0830	" "	Waste Disposal Area A - taken in S direction
3	"	0835	" "	Waste Disposal Area C&D - taken in E direction
4	"	0840	" "	Waste Disposal Area C&D - taken in E direction
5	"	0845	" "	Waste Disposal Area C&D - taken in E direction
6	"	0850	" "	Dry Well - taken in SW direction
7	"	0855	" "	Waste Disposal Area E & Dry Well - taken in NE direction
8	"	0900	" "	Waste Disposal Area E - taken in NW direction
9	"	0905	" "	Sewage Lagoons - taken in E direction
10	"	0910	" "	Waste Disposal Area B - taken in E direction
11	"	0915	" "	Waste Disposal Area B & Sensor - taken in N direction
12	"	0920	" "	Wide Angle of Whole Site - taken in S direction

## PHOTO IDENTIFICATION SHEET

Type of Camera: Nikon FM

TDD No.: 10-8408-22

Type of Film: Kodachrome

Resource Recovery Corporation, Pasco WA

EPA No.: \_\_\_\_\_

[illegible]

Ref #18

RECORD OF COMMUNICATION		<input checked="" type="checkbox"/> PHONE CALL <input type="checkbox"/> DISCUSSION <input type="checkbox"/> FIELD TRIP <input type="checkbox"/> CONFERENCE <input type="checkbox"/> OTHER (SPECIFY)	
(Record of item checked above)			
TO: Richard Hehemeyer Lakeview Mobile Home Park		FROM: David Bennett NPL Coord-R10	DATE 7/17/87 TIME 9:30 am
SUBJECT Location of wells			
SUMMARY OF COMMUNICATION <p>All four wells are located in the trailer park + are interconnected prior to distribution. Trailer park is north of Sacajaweg State Park.</p>			
CONCLUSIONS, ACTION TAKEN OR REQUIRED			
INFORMATION COPIES TO: Pasco Landfill File			